

GOVERNMENT OF INDIA
DEPARTMENT OF ARCHAEOLOGY
CENTRAL ARCHAEOLOGICAL
LIBRARY

CLASS _____

CALL No

901.0942
Que-Que

D.G.A. 79



A
HISTORY OF
EVERYDAY THINGS
IN ENGLAND

Isidore

BOOKS BY THE QUENNELLS

EVERYDAY THINGS IN ENGLAND

Vol. I. 1066-1499.

Vol. II. 1500-1799.

Vols. I and II together. 16s. 6d. *net*.

Vol. III. 1733-1851.

Vol. IV. 1852-1934.

Vols. III and IV together. 16s. 6d. *net*.

Medium 8vo., cloth.

8s. 6d. *net each*

"EVERYDAY LIFE" SERIES

Vol. I. Everyday Life in the Old Stone Age.

Vol. II. Everyday Life in the New Stone Age, Bronze and Early Iron Age.

Vols. I and II together: Everyday Life in Prehistoric Times. 10s. *net*.

Vol. III. Everyday Life in Roman Britain.

Vol. IV. Life in Saxon, Viking and Norman Times.

Crown 8vo., cloth.

5s. *net each.*

EVERYDAY THINGS IN GREECE

Vol. I. Homeric Greece. 7s. 6d. *net*.

Vol. II. Archaic Greece. 7s. 6d. *net*.

Vol. III. Classical Greece. 8s. *net*.

The Three in One Vol.: Ancient Greece. 21s. *net*.

Large 8vo., cloth.

THE GOOD NEW DAYS

A Series of bright and informative talks about the fundamental factors of British Citizenship. Fully illustrated.

Demy 8vo., cloth.

6s. *net*





FIG. 1 —A Banquet at the Royal Pavilion, Brighton.

(From the coloured lithograph by Joseph Nodding.)



Written and Illustrated by
MARJORIE and C.H. B. QUENNEL
Published by
B. T. BATSFORD LTD LONDON

108
12.7.40
6/1/40
1/10/40
942
e 211 c 57
m 28

FIRST PUBLISHED AUTUMN 1933
SECOND EDITION AUTUMN 1938


CENTRAL ARCHAEOLOGICAL
LIBRARY, NEWCASTLE

Acc. No. ... 34 7/4 ..
Date..... .. 2 2 1952.....
Call No.... 901.09 .2.....
 Que Que

TO THE MEMORY OF
THE REV. JAMES WOODFORDE
WHO KEPT A DIARY FROM
1758 TO 1803

TO JOHN BERESFORD
WHO DISCOVERED IT

TO THE OXFORD UNIVERSITY PRESS
WHO PUBLISHED IT



NOTE TO THE SECOND EDITION

I have not found it necessary to do a great deal in the way of revision, for after the five years since its first appearance, the simple arrangement under three main heads with sections on subsidiary trades still stands as an effective and broad treatment of the subject. I have, however, replaced a number of architectural or antiquarian illustrations by some which I felt were an improvement or were more directly connected with social life. The text has been brought up-to-date where necessary, and through the kindness of friendly collaborators I have been able to add several colour plates.

M. Q.

PREFATORY NOTE

THE boys and girls for whom we write will know that we are mainly concerned with showing people at work, and that it does not matter what the work is so long as it is interesting—and we might add if work is natural and proper then it cannot be uninteresting. For example, take cleaning out a cattle-yard deep in manure. If you are a farmer or gardener you will be looking ahead to the crops which you will grow with the aid of the manure, and the smelly job becomes interesting.

It will be found that work divides itself quite naturally into three great trades. Men must eat, so the farmer's trade is the most important one. It does not matter whether the breakfast bacon comes from Denmark, or the dinner's mutton from New Zealand, the cheese from Canada, and the eggs from China, it is the farmer who feeds you; and though the food may be packed in a tin, this was not its natal couch. The farmer grows the raw materials also for the second great trade of Clothing. The fleeces of his sheep are woven into cloth, the hides of his cattle make shoes, and the flax he grows, the linen. The third great trade is the Builder's—he provides the houses. All the other trades are subsidiary and relatively unimportant, as can be seen in the chart on the opposite page.

Until the end of the eighteenth century we carried on these three great trades by ourselves for ourselves, and with the surplus over and beyond our needs paid for luxuries, like wine, which we imported. In the nineteenth century, from a variety of causes, all of which seemed very reasonable, this natural balance began to be disturbed. The emigrants who went to America and Australia sent home for the goods which they could not manufacture themselves, and paid us for them with foodstuffs grown on virgin soils. More and more it began to pay us to manufacture these goods, and so this Industrial Revolution altered our mode of living—it was rooted in money instead of in the land.

The idea of this book is to contrast these two modes of living—the simple natural methods of the eighteenth century, which first began in England when Neolithic man planted his crops on the lynchets and tended his flocks on the Downs, and the modern Industrialism, which is so recent, and difficult, and complicated. We cannot of course do more than touch on the many problems with which Man has been confronted, but we shall pay especial attention to the difficulties which he has had to overcome. Man is a cantankerous animal, very frequently wrong-headed and perverse; he will run a heel-line with the greatest joy and cause his friends despair, but he is ingenious and skilful—so much must be admitted. We will show him exhibiting his ingenuity and skill.

MARJORIE and C. H. B. QUENNELL.

BERKHAMPTSTEAD, *July*, 1933.

NOTE OF ACKNOWLEDGMENT

IT is a little difficult to acknowledge suitably the assistance which has been given to us in making this book, because we have a habit, unfortunately for our friends, whoso engaged, of laying under contribution every man, woman and child that we may meet. First our publisher, Mr. Harry Batsford, must be mentioned, there can be few men with the knowledge he possesses of the buildings of England and the books about them. Mr. John Berestord and the Oxford University Press generously allowed us to use the information in the Woodforde Diary. Sir Henry Lyons also helped us, and as he retires from the Science Museum, London, this autumn, we might, on our own and our readers' behalf, render thanks to him for the splendid work he and his men have done during the last few years. Sir Henry as well allowed us to publish the Science Museum photographs in this book. Mr. A. K. Sabin is another Museum Director who placed his knowledge at our disposal. Mr. W. H. Collin assisted us with information and slum photographs; Mr. W. B. Hopkins with farming details; Messrs. Bertram Hellyer, N. Paul Jasper, and A. F. Bean in sanitation; Mr. Paul Faraday in lighting; Captain Wilfred Dowman with details of the *Cutty Sark*, the Carron Co. with details of early ranges—and there were many others.

As regards the illustrations, we have been fortunate in having access to the incomparable collection of Mr. W. T. Spencer, of New Oxford Street, from which Figs. 21, 31, 71, 73, 145, 141 and 180 have been reproduced. Fig. 165 is from an original in the Royal Naval College, Greenwich, and is reproduced by permission of the Lords Commissioners of the Admiralty. For Fig. 106 we must thank Mr. Arthur T. Bolton, F.S.A., F.R.I.B.A., Curator of the Soane Museum, London; and for Fig. 178 Mr. R. E. Trevithick and the Committee of the Burlington Fine Arts Club. Fig. 185 is reproduced from Frank C. Bowen's "The Sea: Its History & Romance," by courtesy of the publishers, Messrs. Halton & Co. Ltd.; Fig. 116 is by kind permission of *The Times*, and Fig. 118 of the *Daily Herald*. Finally, a general word of thanks is necessary to the Trustees of the British Museum and Victoria and Albert Museum for permission to reproduce a number of subjects, whose sources are in every case given beneath the illustrations.

July, 1933.

M. Q. and C. H. B. Q.

ACKNOWLEDGMENT TO SECOND EDITION

For the illustrations we have again to thank Messrs. Spencer for their extreme kindness in placing at our disposal their incomparable collection of old prints. We have to lament the loss of Mr. W. T. Spencer, but Mr. Spencer, Miss Spencer and Miss Gray have been as helpful as ever. We have to thank them for Figs. 17A, 30B, 159-161, 163-167. Mr. Hancock of *The Shipping World*, has kindly provided the colour blocks of ships on Figs. 181 and 183, and *The Burlington Magazine* must be thanked for Fig. 65, the coloured dress. Mr. J. H. R. Body, of Kenton, has kindly supplied the material for the brief section on early electro-magnetic locomotives from a paper read by him before the Newcomen Society, who must be thanked for their kind permission. The remaining illustrations have been provided by the publishers

October, 1938.

M. Q.

A Note on the Methods and Influence of C. H. B. and MARJORIE QUENNELL on History Teaching in Schools

By FRANK ROSCOE, M.A.

Secretary of the Royal Society of Teachers

THE subject of history has formed part of the school curriculum for several generations, but it is only during recent years that any serious attempt has been made to enliven it with material likely to interest the young. A century ago schools began the practice of treating the dates of events as all-important while giving little attention to the events themselves.

Readers of Jane Austen will recall the comments made by Maria and Julia Bertram on the attainments of their ten-year-old cousin, Fanny Price :

" How long ago it is since we used to repeat the chronological order of the Kings of England, with the dates of their accession, and most of the principal events of their reigns ! "

" Yes," added the other, " and of the Roman Emperors as low as Severus."

At Rugby Arnold introduced a fuller treatment of ancient history, but for long after his death the public schools made little or no attempt to teach English history to their pupils. For younger children Mrs. Markham produced " Little Arthur's History of England " and Charles Dickens wrote " A Child's History of England." In the later middle of last century there were textbooks more ambitious in scope but even less attractive in form and content. They treated history mainly as a record of dynasties, wars and conquests, ignoring the lives and doings of ordinary men and women.

John Richard Green saw the defects of this kind of treatment, and wrote his " Short History of the English People " as a corrective and an example. His work was extremely useful, but the beneficial influence was limited in the main to students of mature years.

The panorama of agrarian and industrial development, changes in social structure, and the gradual growth of national institutions are less dramatic and picturesque than tales of royal persons, glittering pageants and knightly prowess.

The ever-widening scope of historical research has opened many different fields of study. We have to-day many " histories "—ancient, modern, political, social, local, economic, religious or literary, with countless specialised branches such as the history of architecture, of shipping, of games, localities or buildings.

Amid this vast and ill-ordered mass of facts, all falling under the general title " history," some guidance must be given to the young student. Lacking a coherent thread or clue he may be engulfed in confusion, unable to see the wood for the trees. The traditional scheme is the one of which Fanny Price knew nothing. Dates of kings and queens, the principal events of their reigns, and copious attention to " battle, murder and sudden death "—these formed the material of much school history down to a generation ago. Imperfectly retained and distorted in outline, it furnished a sorry equipment of historical knowledge for the British citizen. There was need for a fresh presentation of history which a child could follow with an understanding proper to his years and with that interest which is always aroused when familiar things are seen from a new angle.

The most vivid and striking contribution to the new method of treating history for young students was devised by C. H. B. Quennell, in happy collaboration with his wife, Marjorie Quennell. Neither of them had been through the conventional discipline of historical study and research. She is an artist by

training and inclination, while he was an architect to whom the War brought an interruption of a successful professional career. He had written an excellent handbook on Norwich Cathedral, but he never posed as a literary expert.

His chief interest was in architecture, and in the course of his practice he developed an abiding zest for examples of good workmanship, and a profound respect for skilled craftsmen in every field. The individuality and fitness of the work which they did in the days before mass-production gave him constant pleasure. His desire to convey something of his own knowledge and enthusiasm was the mainspring of his efforts in authorship. Beginning with the charming volumes entitled "A History of Everyday Things in England" (Batsford), he and Mrs. Quennell went on to describe everyday things at different periods and in different places.

It is hardly too much to say that they made history while writing it. By laborious research and careful selection they were able to present the story of people "in their habit as they lived." Skilful illustrations supplemented the text, making the successive volumes doubly interesting. The effect was strengthened by the fortunate choice of a publisher whose skill in the production of books goes far beyond the practice of the maker of cheap "best-sellers." This happy conjunction of author, artist and publisher furnished a memorable and permanent contribution to the list of books available for young students of history. The general run of school text-books might be described as drab in appearance and in contents, but the Quennell books are attractive and even exhilarating in both respects. We need not wonder that they are finding imitators and helping to raise the standard of book-production for schools.

It is fitting that readers of the Quennell books should have in mind a word-picture of the author. Yet it is impossible to convey any adequate impression of the man. His chief characteristic was an unquenchable enthusiasm for things that are "beautiful and of good report." He would journey for miles to see a well-built farm waggon or any good example of handicraft. He had about him no trace of self-assurance nor any of the windy rhetoric used by self-styled connoisseurs on art or architecture. Sometimes he would say, with a rueful smile, that he was too ignorant to understand the meaning of modern developments, but in truth he understood them well enough and formed shrewd estimates of their worth. This will be evident to readers of his last book, "The Good New Days" (Batsford), where he describes modern industrial and agricultural processes and is mindful of their significance as factors in the life of coming generations.

In the memory of those who knew him C. H. B. Quennell has an assured place. They will always be able to recall vivid pictures of one who radiated goodwill towards his fellows, treating their failings with whimsical humour and extracting merriment from circumstances untoward enough to have discouraged a spirit less well armed against fate. He had a blithe heart and an unflinching zest for simple human joys. Children loved him, the sure perception of youth enabling them to see in him one who was ready to share their interests without assuming the airs of a mentor.

This firm link with childhood was of a piece with the man, for he retained to the end the inquiring spirit and quick enthusiasms of youth. He died on December 5, 1935. A fitting epitaph for him might be found in the words of Robert Louis Stevenson:

"Every heart that has beat strong and cheerfully has left a hopeful impulse behind it in the world, and bettered the condition of mankind."

January 1936.

CONTENTS

	PAGE
DEDICATION	v
A TREE OF LIFE AND WORK	vi
PREFATORY NOTE	vii
NOTES OF ACKNOWLEDGMENT	viii
SHORT LIST OF AUTHORITIES	xiii
CHART I	xiv

PART I

CHAPTER I : The Eighteenth-Century Farmer	I
Common Fields — Common Property — Self Help — Ploughing — Roads — Industry — Punishment — Tull — Tillage — Organs — Drainage — Coulters — Sowing — Seed — Bread — Land — Turnips — Townshend — Bakewell — Coke — Washington — Woodforde — Dib- bling — Tithes — Food — Mead — Wages — Digesters — Baking — Puddings — Sweeps — Butter — Light — Squire and Parson.	
CHAPTER II : The Eighteenth-Century Builder	39
Wren — Burlington — Palladio — Gibbs — Walpole — “ Gothick ” — Chinese — Newgate — Adam — Dance — Prisons — Debtors — Yeoman of the Halter — Executions — Revett — Churches — Greece — Stuart — Classical Churches.	
CHAPTER III : Clothing	63
Shuttles — Spinning — Weaving — Kay’s Shuttle — Har- greaves — Arkwright — Crompton — Clothes — Calash — Muslin — Bonnets — Museums to See.	
CHAPTER IV : The Subsidiary Trades	77
Canals — Travelling — Bridges — Power — Steam Engine — Medicine — Vaccination — Fevers — Hydrophobia.	
CHAPTER V : Sanitation	87
Baths — Sewage Disposal — Wells — Cesspools — Pumps — Water Supply — Cisterns — Closets — Traps — Ventilation — Plumbing — American System — Cholera — London Drained — An Engineer’s Achievement.	

CONTENTS

PART II

PAGE

CHAPTER VI: The Nineteenth-Century Farmer .	107
Farming—Doses—Corn Law—Cobbett—Political Register—Paper against Gold—Gagging Bills—Labourers—Woodlands—Taxation—Wheat—Fairs—Crafts—Sensible Fellows—Truck System—Machinery—Reapers—McCormick—Scythes—Threshing—Winnowing—Windmills—Carts—Tumbrils—Waggons—Wheelwrights—“Summers”—Sturt—Thomas Hardy—Gates—Horses—Trucks—Electro-magnetic locomotives.	
CHART II	108
CHAPTER VII: Nineteenth-Century Building .	148
Ashridge—Beckford—Pugin—Regent Street—Bank of England—Brighton—The Pavilion—A Kremlin—Town-Planning—Slums—Back to Back—Garden Cities—Flats—Chadwick—Poor Law—Prince Albert—Ranges—Furniture—Chairs—Beds—Cooking—Kitchens—Ice Houses—Fog—Ovens—Lighting—Dating Buildings.	
CHAPTER VIII: Nineteenth-Century Clothing .	184
Jacquard—Loom—Sewing—Power Loom—Textiles—Dress—Hair-dressing—Crinoline—Macintosh—Whiskers—Bethnal Green.	
CHAPTER IX: The Subsidiary Trades	198
Macadam—Tom Brown—Omnibus—Locomotives—Trevithick—Catch-Me-Who-Can—Hobby Horse—Stephenson—Bicycle—Steamboats—Sailing Ships—Cutty Sark—P. & O.—Emigration—U.S.A.—Pilgrim Fathers—Pilgrim Mothers—Faraday—The “Wayside Inn”—Spending—Saving.	
INDEX	222

SHORT LIST OF AUTHORITIES

- Rural Rides. WILLIAM COBBETT. (Reeves & Turner, 1908.)
 Agricultural Implements and Machinery. SPENCER and PASSMORE.
 (Science Museum, 1930.)
 The Plumber and Sanitary Houses. S. STEVENS HELLYER. (Batsford, 1882.)
 Under Eight Reigns. BERTRAM HELLYER. (Dent & Hellyer, 1930.)
 Life in London. PIERCE EGAN. (Sherwood, Neely & Jones, 1821.)
 The Works of Sir John Soane. A. T. BOLTON. (Soane Museum Publication.)
 Ancient Egyptian and Greek Looms. H. LING ROTH. (Bankfield Museum, Halifax.)
 Primitive Looms. H. LING ROTH. (Bankfield Museum, Halifax.)
 The Wheelwright's Shop. GEORGE STURT. (Camb. Univ. Press, 1923.)
 Sleds, Carts and Waggon. CYRIL FOX. *Antiquity*, June, 1931.
 Cottage Economy. WILLIAM COBBETT. Published by him, 1828.
Country Life.
 The Crystal Palace and Its Contents. Published by W. M. Clark, 1852.
 "Travel" and "Clothing." By Col. F. S. BRERETON. (Batsford, 1931.)
 Road Transport. E. A. FORWARD. (Science Museum, 1926.)
 Railway Locomotives. E. A. FORWARD. (Science Museum, 1931.)
 Merchant Steamers. G. S. LAIRD CLOWES. (Science Museum, 1927.)
 Sailing Ships. G. S. LAIRD CLOWES. (Science Museum, 1930.)
 The Log of the *Cutty Sark*. BASIL LUBBOCK. (James Brown & Son, 1924.)
 The Diary of a Country Parson. JAMES WOODFORDE. Ed. by JOHN BERESFORD, London. (Humphrey Milford, Oxford University Press, 1924.)
 History of American Government and Culture. HAROLD RUGG. (Ginn & Co., 1931.)
 History of American Invention. Ed. by W. KAEMPFERT. (Charles Scribner's, Sons, 1924.)
 The Horse-Hoing Husbandry. JETHRO TULL. (1933.)
 Textile Machinery. (Science Museum, 1921.)
 Stationary Engines. H. W. DICKINSON. (Science Museum, 1925.)
 The Tour of Dr. Syntax. Eighth ed. Illustrated by ROWLANDSON.
 Rowlandson the Caricaturist. JOSEPH GREGO. (Chatto & Windus, 1880.)
 Scraps and Sketches. By GEO. CRUIKSHANK.
 Farington Diary. Ed. by J. GREIG. (Hutchinson, 1922.)
 The Smaller English House, 1660-1830. RICHARDSON and EBERLEIN. (Batsford, 1925.)
 English Interiors, 1660-1830. M. JOURDAIN. (Batsford, 1923.)
 Smaller Houses of Late Georgian Period. STANLEY C. RAMSEY. (The Arch. Press, 1924.)
 British History in the Nineteenth Century. G. M. TREVELYAN. (Longmans Green & Co., 1922.)

CHART I.

Kings, Political, and Social	Science and Industry	Art
1727 GEORGE II.	1724 Turnips first used for cattle	1726 "Gulliver's Travels" (Swift) 1727 Kent's book on Architecture Chiswick Villa 1728 Gibbs' book on Architecture
1732 Birth of George Washington	1730 Townshend turns to agriculture 1732 Birth of Richard Arkwright 1733 Tull's horse-hoeing husbandry Kay's flying shuttle introduce Industrialism	1734 Holkham started and foundation of Dilettanti Society 1740 "Pamela" published
1737 Death of Queen Caroline	1740 Foundation of London Hospital 1741 Death of Tull Birth of Arthur Young	1742 Batty Langley's "Gothic Architecture Restored and Improved" 1745 Lord Dacre gothicizes Belhus
1743 Dettingen	1745 Bakewell begins	1747 Woburn Abbey 1748 "Roderick Random" published 1750 Prior Park Bath Walpole builds Strawberry Hill 1751 Prison series, Piranesi 1753 Foundation Society of Arts Chinese buildings by Chambers
1746 Culloden	1750-7 Hargreaves designs his jenny	1755 Johnson's Dictionary
1747 Henry Fielding at Bow Street	1754 Railways (not loco.) at Bath	1758 Robert Adam returns from Italy 1759 Chambers' "Civil Architecture"
1755 Seven Years' War 1757	1759 Eddystone Lighthouse (Smeaton) Washington farming at Mt. Vernon	1760 "Tristram Shandy" published 1761 Kedleston, Derbyshire 1762 Stuart and Revett's "Antiquities of Athens" 1763 Chinese work at Kew, Chambers
1759 Wolfe's victory, Heights of Abraham	1761 Brindley's canals	1766 "Vicar of Wakefield" published "Antiquities Etrusque Greques et Romaine"
1760 GEORGE III.	1763 Watt begins on steam engine and Wedgwood starts pottery	1768 Adelphi, London 1769 Foundation of Royal Academy
1763 Peace with France 1765 Population of England and Wales 7,000,000	1769 Arkwright's spinning machine Wedgwood opens Etruria 1770 Cugnot's experiments Birth of Trevithick	1770 Newgate begun 1773 Works in Architecture (Adam) "She Stoops to Conquer" published
1767	1774-9 Crompton's mule 1775 Cumming's closet 1776 Coke of Holkham begins farming and starts the Holkham Meetings, 1773 Adam Smith's "Wealth of Nations" Jenner vaccinates	1776 Somerset House, London
1771 Johnson's journey to the Hebrides 1773 Boston Tea Riots	1780 Robinson's range 1781 Trade very bad Watt perfects steam engine Birth of George Stephenson	1779 Coalbrookdale Bridge 1780 Finsbury Square, London
1775 Bunker's Hill 1776 Declaration of Independence, U.S.A.	1783 Montgolfier balloons	1784 Brighton Pavilion begun (Holland) 1785 First edition Burns' poems Carlton House, London (Holland)
1777	1785 Cartwright's Power Loom	1788 Ayot St. Lawrence Church Soane made architect Bank of England 1792 Death of Robert Adam
1780 Gordon Riots 1781 Surrender of Cornwallis, Yorktown	1788 Bramah's closet	1795 Southill, Beds. (Holland)
1782 Rodney's victory 1783 Peace with America, France and Spain	1791 Birth of Faraday	
1787	1793 Young becomes Secretary of Board of Agriculture	
1793 France declares war on England Execution of Louis XVI.	1797 Trevithick makes his model loco Soane uses steam heating	
1795 Powder Tax 1796 Speenhamland decision 1797 1799		

Chart II.—George III to Victoria, 1799-1851, p.108

PART I

CHAPTER I

THE EIGHTEENTH-CENTURY FARMER

WHEN we look back on life as lived on this island of ours, up till the end of the eighteenth century, it seems to us to have been very comfortable and easy. Doubtless our forbears had their troubles, but they did have time to grapple with them. The first known Englishman, the Piltdown Man, hunted strange animals in Sussex, and his followers in the New Stone Age guarded their flocks on the chalk Downs, and grew corn on the narrow lynchets. The Bronze Age Men and those of the Early Iron Age, if they came as invaders, stayed to be absorbed into the stock. The Romans tried to teach us Town-planning, and made roads before we understood their meaning ; we were part of a mighty empire that stretched from Babylon to Britain. Then the Dark Ages descended, and Angles, Saxons and Jutes wandered through the ruins of Silchester, but preferred to make clearings for their own houses in the woods. The Normans brought us the vigour of the North once more, and the culture they had absorbed in Normandy, and then, under the Angevins, we again became part of an empire that included all the Western parts of France. But gradually our outlook became more insular, and so we came to the Renaissance and the discovery of the New World. Adventurers went there, and we contested with the Spaniards on the West Indian seas, but the placid stream of life at home flowed on, and there was little alteration in the colour of our thoughts or the mode of our living ; and so things remained until the beginning of the eighteenth century. Then came a series of happenings which brought the Industrial




FIG. 3.

COMMON FIELDS

Revolution in its train, and time became a kind of fourth dimension which could not be grappled with. Tull introduced new ideas which revolutionized agriculture, James Watt's monster was born. Bridgewater made canals, and Macadam, roads, and we were hardly used to these when Stephenson's iron horse ran on rails instead of roads. Industrial towns sprang up and introduced unheard-of complications of Town Planning and Sanitation. Problems to which a thousand years had gone to find a solution had to be settled in as many weeks. So we must be very charitable in dealing with the Industrial Revolution.

The first of the three great trades to be affected by the change was that of the farmer, but before we deal with the revolution in Agriculture, which was to be effected by Tull and Bakewell in the eighteenth century, it will be well to call to mind what the conditions were like before they started their work.

Fig. 3 shows our home-town of Great Berkhamstead, in Hertfordshire, in the early part of the thirteenth century, and it will serve our purpose quite well, because country life in England had altered very little in the 500 years between the early thirteenth and the early eighteenth centuries. This was one of the great difficulties with which the English people had to deal when Industrialism was let loose on them—not only the thorough-going nature of the change, but the suddenness of the transition.

The three Common Fields were in the south of the town. Wheat and rye were sown in one of these, and barley, oats, peas and beans in the second, while the third was left fallow. The fields were cut up into narrow acre or half-acre strips and divided from one another by grass banks, or balks. A man would have holdings in each of the three fields, so much time was wasted in going from one field to another. The two fields which were in cultivation were fenced off from the sowing to the harvest, and then the fences were taken down and the cattle driven by the herdsman to feed off the stubble and weeds. The meadows for

COMMON PROPERTY




FIG. 4.—The Smith.

hay were treated in the same way, cut up into strips, and fenced off between Lady Day and Midsummer Day, when the hay was cut, and after this the fences came down and the cattle grazed on the aftermath. The Waste, or Common, was for the pigs and the cattle when the fields failed and here the people went wooding to find what they could “by hook or by crook.” The rams and bulls were the property of the parish, as were the cumbersome ploughs, drawn perhaps by oxen.

There were mills where the corn could be ground, and in places like Berkhamstead markets where they could sell their butter, eggs and poultry. The exchange of commodities was a much simpler business than it is to-day, and the supply was regulated by a demand which could be estimated almost to half a pound of butter. The inns for refreshment were opposite the market place; the church where they worshipped close by. Then there was the smith, who shod the horses and forged the ploughshares; the wheelwright, who could make not only wheels, but the

SELF HELP

waggon to go on them. The carpenter was a good tradesman, and could construct anything in wood from a field-gate to a coffin. All these people were dependent on agriculture, and helped to build up a very healthy corporate life. The farmers themselves



RATTLE FOR SCARING ROOKS
FROM COLLECTION OF A.O. COLLARD

FIG. 5.

were very handy men and made many of their own implements—a winter's evening was well spent by the fireside in fashioning a flail for threshing. The women could spin and weave, make lace and plait straw, as well as milk the cows and bake their own bread in their brick ovens.

In fact they carried the doctrine of self-help to such extremes that they were very nearly self-supporting and independent of outside assistance. Occasionally there would be a fair in the Market Place, where pennies would be wrung out of the good man's purse for luxuries.

It was a civilization which was extremely strong and stable—it was broad-based on the land and sat securely like a pyramid, or stood erect if you will, like an oak held by its knotted roots in Wealden clay. And it was beautiful with the same unself-conscious beauty as the oak. Unfortunately they become rarer year by year, but where will you find anything more lovely than untouched English villages? They are always in tune with Nature, and that came about very largely because the people were content to build with local materials—stone in the Cotswolds, timber framing where the oaks grew, and brick where there were good brick earths. Architecturally the church and houses may be very simple, and not at all grand, but

PLOUGHING




FIG. 6.—Wooden Feeding Trough.

nevertheless they are just right. If something grander is demanded then there are the cathedrals to justify Faith by works. These people were not clods—they had Faith, lived in Hope, and practised Charity.

It was very difficult for the inhabitants of such villages to change ; why should they ?—especially if, as at Berkhamstead, an old castle watched over the place to remind them of their feudal origin. What had been sufficient for their fathers was good enough for them. If a man like Tull came along and suggested that by doing this, that, or the other, they could improve matters, they remained unconvinced, and experiments were very difficult. You could not, for example, cross-plough your long, narrow strips in the Common Fields, nor delay matters for observation. At the appointed time down came the fences, and the cattle nosed their way over your ground. If the open field system of agriculture did not lend itself to experiment it yet had many points. It was based on co-operation. If it did not produce much foodstuff per acre, it kept many people usefully employed. It helped a good many lame dogs over stiles who have since got left behind. From the economical point of view it was not very much good trying to grow more food than you needed. It was difficult to exchange, because the roads were so bad that wheeled traffic was nearly impossible. Where, as in the case of Berkhamstead, the little township had been built on a road which was old when the Romans came, and some traces of the foundations they had added might be found to prevent a waggon sinking in up to its




FIG. 7.—Wooden Scoop.

ROADS

axles, movement was possible. Off the Roman roads the country lanes, which twisted and turned, began their life as the paths between the Common Fields, which led up to the Waste, and so across it, avoiding quagmire and puddles by wide detour, until the next village was reached. The pack-horse was the only possible method of transporting the scanty manufactures of the early eighteenth century. In Celia Fiennes' Diary of the seventeenth century we read of the "very deep bad roads. . . . I was near 11 hours going but 25 miles," and Celia was riding, not driving. We find the same thing in Parson Wood-




FIG. 8.—A Well-made Implement.

forde's Diary of the end of the eighteenth century. Still this did not trouble a people very much who were nearly self-supporting, and, remember, there were not any great towns. Even London was only what we now call the city of London. Fig. 22 shows the Old Brompton Road, London, with fields and trees, in 1822, and Cobbett, in 1823, writes of a field of wheat at Earl's Court, set amongst the market gardens. The City of Westminster was reached by going along the Strand, where palaces stood in their own grounds running down to Thames side. The meat the cities needed walked




FIG. 9.—A Water Cart.

in on foot. Turkeys from Norfolk and cattle from Kent. We noticed once when we were motoring down the Old Kent Road that dismal, vulgar-looking public-houses still retained old pleasant

INDUSTRY




FIG. 10.—Tull's Common Two-wheeled Plough, 1733.

names as a reminder of a time when they were inns for the refreshment of drovers bringing their cattle to Smithfield.

Another point to remember is, that before James Watt perfected his steam engine there was no other source of power, except a man's own muscles, or those of his horse, or wind and water. As these were less powerful than the steam engine, fewer people were concentrated in the early workshops than the later factories. People could work in their own houses, and though they may have worked long hours, they could work to suit themselves. Celia Fiennes tells us of the manufacture of serges at Exeter in the seventeenth century. The yarn was made by the spinsters, who brought it into the market, where it was bought by the weavers, who wove it on their own looms. They sold their cloth to the fullers, who cleaned it with fullers' earth to remove the oil and grease. Fine flowered silks were woven in Canterbury; crapes, calamanco and damasks in Norwich; stockings in Nottingham, and paper in Kent; and so it remained in the eighteenth century. There were no hideous manufacturing districts in England, hatched in grey as they are to-day on the A.A. maps, as places to be avoided.

PUNISHMENT




FIG. 11.—Wooden Swing Plough.

We have written of the best side of the picture of life as lived in England in the early eighteenth century. It makes us agree with Socrates, in Xenophon's "*Œconomicus*," that agriculture is the mother and nurse of the other arts, and the best of all occupations by which men can gain a living—that when agriculture flourishes, all the other occupations are vigorous, but when the land lies barren, men decay.

There was the other side of course. If we could go back we should be shocked at many things. We should find the people cruel, or think them so. They could see a man hanged, and regard it as a spectacle—tell you how, when the man was left hanging, the executioner would pull on his legs to shorten his sufferings, and detail the length of them. In the Woodforde Diary we find that Robert Biggen, who had been convicted of stealing potatoes, was whipped through the streets of Cary at a cart's tail by the hangman. The triangular route is detailed, and sounds a long one. Because Robert was an old offender 17s. 6d. was collected and given to the hangman to encourage him not to shirk the whipping. The people's surroundings and habits cannot have been very cleanly, or they would not have suffered from diseases engendered by filth. The mortality was shocking—small-pox, consumption and fevers carried off people in their prime, and only the fittest of the babies survived. They gorged themselves like animals, and many of them, judged by pictures, were as gross as swine.

TULL



FIG. 12.—Breast Plough from Wellingore,
Lincolnshire.
(*Science Museum, London.*)

Now we come to the beginning of Industrialism, and we are going to suggest that this was really started, not by James Watt with his steam engine in 1765, but by Tull with his drill at the very beginning of the century. It was Tull who increased the food supplies—this increased the population, and without an increase

in the population there would not have been any surplus to be employed in tending James Watt's engine.

Jethro Tull was born at Basildon, Berks, in 1674, and lived till 1741. He matriculated from S. John's College, Oxford, on July 7th, 1691, when he became a Law student at Gray's Inn, London, and on May 19th, 1699, was called to the Bar. Tull married on October 26th, 1699. This sounds like the early history of a Lord Chancellor, and not of the man who was to revolutionize agriculture. Here is an interesting point to note—how often revolutionary work is done in England by the amateur. The average Englishman is critical and cantankerous and does better work on his own than working in a team. The Industrial Revolution was largely the work of amateurs, kicking against the pricks of established customs and authority.

Tull's opportunity and work came about in this way. His health was poor; in the Preface to his book he says: "tho' almost all my Life has been a continued Sickness"; so he returned to the country from where he came and, coming back with a seeing eye, took stock of farming,

TILLAGE




FIG. 13.—Jethro Tull's Four-coultered Plough (1733).

and found that it was still being carried on in the old-fashioned way that we have described on p. 3, and he thought that such methods must be altered.

Other people must have felt this too, because, though Tull was to meet with much opposition and receive little in the way of thanks, his ideas were found to be good, and gradually gained ground. His main idea is expressed in the title to his book, "The Horse-Hoing Husbandry: or, an Essay on the Principles of Tillage and Vegetation Wherein is shown a Method of introducing a Sort of Vineyard-Culture into the Corn-Fields, in order to Increase their Product, and diminish the common Expence; By the Use of Instruments described in Cuts." It should be noticed that Tull places the principles of Tillage first, and these were his main contribution. The Instruments he describes come second. His book was not published till 1733. Tull seems to have started farming soon after his marriage, because he invented his first drill about 1701, and before he had seen the vineyards on his travels between 1711 and 1714.

Let us first consider the disadvantages of the old system. Sowing broadcast was very wasteful of seed. Tull says, "It was very difficult to find a Man that could sow Clover tolerably; they had a Habit (from which they

ORGANS




FIG. 14.—The Tongue or Pallet
of the Organ.

could not be driven) to throw it once with the Hand to two large Strides, and go twice on each Cast; thus with nine or ten Pound of seed to an Acre, two-thirds of the Ground was unplanted, and on the rest 'twas so thick that it did not prosper." (See Cobbett's remarks on this on p. 118.) So Tull made his first drill, which did the same work with two pounds of seed. He also used his drill as early as 1701 for wheat, making the channels at 1 foot distance at a

cost of 6d. the acre, using only one bushel of seed to the acre. Now here were facts which could not be overlooked by Tull's neighbours—he not only saved seed, but by sowing it in drills, or lines, the weeds could be kept down by hoeing, and the ground cultivated and kept friable in a far more economical way than was possible when the field was covered with crops coming up just anyhow. This must be kept in mind, that Tull not only invented his drill, but initiated good cultivation. Tull suffered the common fate of innovators; his book hints at it. He expected acclamation, but received only grumbles. The farmer is the most conservative of men, and probably

DRAINAGE

Tull's neighbours complained amongst themselves of this lawyer, of all persons, who was drilling seed with a machine. Why could not the man be satisfied with the ways of his father?—and so on, and so forth—but the man Tull went on and must be reckoned as one of the makers of modern England.

But we are running on a little too quickly. We will follow Tull's example and start with the plough, or plow as he calls it, as Fig. 10. He shows first the common two-wheeled plough used in Berkshire, Hampshire, Oxfordshire, and Wiltshire, and most other counties of south Britain, except where there were miry clays to clog the wheels. In heavy land the swing plough with a more horizontal beam and no wheels was used, as Fig. 11. It is interesting to note that a wheeled plough is shown in the Norman Bayeux Tapestry, and a swing plough in the fourteenth-century Luttrell Psalter.

The function of a plough is to break up land that has been under grass, or lying fallow, and it works in this way. If we refer to Fig. 10, which is Tull's common plough, the coulter makes the vertical cut, and the share the horizontal one. The depth of the furrow, about 7 inches, is regulated by raising or lowering the beam on its pillow; with a swing plough the ploughman does this by raising up, or bearing down on, the plough handles. The furrow slice is turned over by the earth-board. In the ordinary way a ploughman does not plough up and down the field with the furrows side by side, but moves across the headland by the hedge, until the furrow slices lie in the direction of A, Fig. 10. Where the slices incline towards one another is the ridge, and where they go from one another is the water furrow used for drainage. The distance between these furrows depends on the character of the soil, and its need for drainage.

Now one of the difficulties with which the farmer has to contend is how to get rid of the grass and weeds. B, Fig. 10, shows the furrow slices upside down after ploughing,

COULTERS

and if the weather is favourable to them the weeds will soon grow up again between the slices.

Tull points out that "another way to conquer a strong turf, is, to plough it first with a Breast-Plow, very thin," as Fig. 12, but this was a very expensive proceeding. In the later plough, Fig. 85, there is an ingenious little share in front of the coulter, which skimmed off the weeds and turned them over to be buried under the furrow slice by the action of the earth-board.

It was to remedy this that Tull invented his four-coultered plow, as Fig. 13. You can think of the indignation of his fellow farmers, and almost hear them saying, "Whoever heard of a four-coultered plough?" The beam had to be made longer to accommodate the three additional coulters, and these were placed, each of them, $2\frac{1}{2}$ inches to the right of the one behind, and the points of the three in front were kept up somewhat higher than the one behind in front of the share. This made the vertical cut, which cut off the furrow slice 10 inches wide, but when this had been severed by the share and turned over by the earth-board the slice had three vertical cuts in it made by the other coulters, so that the roots of the grass and weeds were more easily dried and destroyed and the ground made more friable. We have put Tull's interesting old names for the various parts of the plough on the drawings.

JETHRO TULL'S DRILL.—The land having been prepared by ploughing and harrowing, we can pass on to the drilling which followed, and was made possible by Tull's great invention; and it was great and vital because it dealt with the food of man. It seems to us so simple an idea that it is hardly worth talking about, but then most great inventions are simple, and have to be if they are to be useful—the merit comes in having the idea.

The function of Tull's drill was to make the channels, sow the seed, and cover the rows all in one operation.

The principal parts of the drill were the seed-box, hopper, plough and harrow. Tull says, "Of these the

SOWING




FIG. 15.—The Seed Box of Tull's Drill (1733).

Seed-Box is the chief; it measures (or rather numbers) out the Seed which it receives from the Hopper: It is for this Purpose as an artificial Hand, which performs the Task of delivering out the Seed, more equally than can be done by a natural Hand." We will start then with the seed-box, and here Tull is of the greatest interest, because he tells us just how he went to work in designing his drill. Some of the boys and girls who read this book may have ambitions in the way of inventing things, and yet doubt their ability in this direction. Tull will give them comfort—great ideas do not spring from the head, fully armed, like Athene from the brow of Zeus. Happy accident plays a great part in invention, and the ability to see that adaptation may be useful.

Tull was confronted with this problem of the seed-box which was to take the place of the hand, and then he

SEED

thought of what he calls the tongue (and modern organ builders call the pallet) in the sound-board of an organ. He had learned to play the organ when he was young, and must have taken it to pieces, one hopes with the consent of his parents, because he seems to have thoroughly understood its mechanism. We have reconstructed this, with the assistance of an old friend, F. Pickering Walker, in Fig. 14. Odd information is sometimes very useful, and there may be some more ideas for inventors in the organ. In the smaller diagram A shows how when the playing end of the key is depressed the other rises, because the key is pivoted on its centre, and how by a series of rods the tongue at C is opened and lets the compressed air, provided by the bellows from a continuous chamber at B, into a series of grooves or mortices at D, on the top of which come the feet of the pipes. There is a groove for each key on the keyboard, each with its own tongue, and the grooves vary in width to suit the sizes of the pipes. But Tull points out that the tongue shuts flat against the surface of the groove and is kept in position by the spring shown. This was practical for measuring out the air to be let into the pipes, but clearly you could not measure out wheat in this way, because it would get jammed in between the tongue and its seating.

Tull's next step was to design his seed-box, as Fig. 15, in brass, in two halves, which were bolted together and made wider at the bottom than the top to prevent what Tull calls the "arching" or jamming of the seed in the box.

Fig. 16 shows the drill itself, which made channels for a treble row of wheat at 7-inch partitions.

We can now give Tull's summing up of his inventions :
"The first Idea that I form'd of this Machine, was thus ; I imagin'd the Mortise, or Groove, brought from the Sound-Board of an Organ, together with the Tongue and Spring, all of them much alter'd ; the Mortise having a Hole therein, and put on upon one of the iron Gudgeons of the Wheel-Barrow, which Gudgeon being enlarg'd to an

A. Hoppers
B. Funnel's
C. Sheats
D & E. Harrow
F. Main Beams
G. Plank
H. Standards
I. Slides
J. Shafts

Seed fed into
hoppers at A. A
fell into Seed boxes
fixed on bottoms of
hoppers - from seed
boxes seed fell into
funnel's at B B
these discharged
seed into trunks

at backs of Sheats at C.C.C.
then share on bottom of sheat
formed the furrow into which
seed fell. Two hinder sheats.
covered furrow made by front
sheat. Harrow at back
covered furrows made
by hinder sheats. Harrow
was attached by arms free
to move up & down & cross
bar D could turn
on E.E.: F.F., G,
Standards at H.H.
& Sheats at C.C.
& Slides at I.I. all
framed together as
one Unit. Hoppers, seed
boxes, spindles, & wheels
formed another Unit free
to move up & down on slides &
Standards if going was rough.




FIG. 16.---Jethro Tull's Seed Drill (1733).

BREAD

Inch and a Half diameter, having on it the Notches of the Cylinder of a Cyder-Mill, on that Part of it which should be within the Mortise, and this Mortise made in the Ear of the Wheel-Barrow (thro' which the Gudgeon usually passes) made broad enough for the Purpose ; this I hoped, for any thing I saw to the contrary, might perform this Work of Drilling, and herein I was not deceived."

Tull goes on to say that placing a box over the mortise to carry the seed was so obvious as to occasion little thought ; nor placing the spindle on two wheels, one at each end, instead of on one as the wheelbarrow, or contriving the plough to make the channels. At first the channels were left open and the seed covered by a harrow ; then this was added to the drill and the whole done in one operation.

And that, we think, is all that need be said about Tull's drill, and we have written what we have to say at considerably less length than the designer. In the 1733 edition of Tull's book he gives 12,662 words to describing the seed-box alone before he starts on the rest of the machine, and it is heavy reading, but very well worth the time and trouble.

After all it was a great achievement to take parts of an organ, wheelbarrow and cyder-mill and so alter and adapt them that it was possible to invent one of the most useful implements of agriculture. There is hope for us all in this direction. Tull saw to the root of the matter when he wrote : "Some waste their whole Lives in studying how to arm Death with New Engines of Horror, and inventing an Infinite Variety of Slaughter ; but think it beneath Men of Learning (who only are capable of doing it) to employ their learned Labours in the Invention of New (or even improving the Old) Instruments for increasing of Bread."

These remarks of Tull apply to the invention of tanks in the war of 1914-18. "These engines of horror" were designed by clapping a fighting turret on to an agricultural Holt caterpillar tractor.

LAND

William Cobbett, of whom we shall have more to say presently, gave Tull the credit for inventing the first drill. If the effect of this was the "increasing of bread," then an increasing of the population followed as a natural result, so Tull can be counted as one of the makers of Modern England. When men were hunters in the Old Stone Age the factor which decided the number of the hunters was the area which was necessary to support and feed the animals which they hunted. In the New Stone Age men caught the animals and tended them as herdsmen, and began to grow crops to feed both the animals and themselves, and in this way the land could support a larger population. The extraordinary thing is that from the time of the New Stone Age up to Tull there was not any very real or essential change.




FIG. 17.—Dibbling.

The system of farming which is described on p. 3 was really very primitive; just sufficient was grown to keep the people alive, and there was very little margin. The population could not increase because there was no great margin of food left over. When the winter came there was only hay to feed the cattle on, so many of them were killed and salted down—there was no possibility of increasing the flocks and herds. If a bad summer came and the hay failed, then the herds starved. It was this fact which made the landowners so keen on the Game Laws; they were pot-hunters and chased the wild deer and hare, and shot the pheasant and partridge, because it gave them fresh meat in the winter and made a change from salted meat. It was an explanation of the large pigeon cots

TURNIPS

which can still be found ; a plump pigeon in a pie was prettier eating than pickled pork. It explains as well why "Peter Piper picked a peck of pickled pepper"—it was to try and make the pickled pork palatable.

THE TURNIP.—All of which leads us to the turnip ; and here Tull did good work, because he invented a special turnip drill. He says in his book, "As far as I can be inform'd, 'tis but of late Years that Turneps have been introduc'd as an Improvement in the Field." Again, "The greatest Turnep-Improvement used by the Farmer is for his Cattle in the Winter."

The turnip of course was known as a garden vegetable long before this. It may be that a flock of sheep, cropping the scanty herbage of a winter field, raided a farmer's garden, as once occurred to us, and ate off all the turnips. If this happened the farmer may well have thought : Why not grow the turnips on a large scale in a field, and then let the sheep eat them there, and to regulate their eating and not let them spoil the whole field we will move them along in enclosures made by hurdles. This was first done in Suffolk about 1724. It sounds so simple, yet nobody had thought of it before. Yet though it sounds simple it was destined to be revolutionary. Other stock could be fed on turnips, so that it meant not only more meat, but more milk and butter, and, what was just as important, more manure. Tull had already by 1724 shown the farmers how to grow more corn ; more corn meant more straw ; the straw could be placed in the yards and there turned into manure, which would not only improve impoverished old soils but enable new light ones to be brought into cultivation.

Again, it is usual to state that enclosures were necessary to meet the demand for food from an increasing industrial population ; but there would not have been an industrial population except for Tull.

We shall have something to say about the Enclosure Acts presently, but here we may remind boys and girls that




FIG. 17A. Lively Activity on an Eighteenth-Century Farm.

From an anonymous colored engraving.



FIG. 17B -A familiar and welcome country figure : the Pechar and his pack, mounted and on foot.

Agathot, by W. H. P. and C. C. 1800.

TOWNSHEND

enclosing the land did not reclaim it—planting quick-set hedges does not make corn grow. The enclosures followed as a natural result of the work of Tull.

Charles Townshend, the second viscount (1674–1738), is another great name. Townshend was an enthusiast who carried on agricultural experiments at Raynham, Norfolk, 1730. He was called “Turnip” Townshend by

the wits, who, because they were turnip-headed themselves, were amused by his enthusiasms. Pope tells us that a favourite subject of his conversation was “that kind of rural improvement which arises from turnips.”

Townshend is as well credited with the introduction of the Norfolk, or Four Course, system of cultivation. The fields were cropped in the following rotation. First came wheat or oats sown in the winter; the next year oats or barley, sown in the spring. The third year clover, rye, vetches, swedes and kale for winter feed, and the fourth year turnips. The sheep were then hurdled over the turnips, and manured the ground so that it was ready for wheat the next year.

This four-course system has lasted until to-day, when the land is being put down to grass and the wise farmer grows meat, milk and poultry.




FIG. 18.—Sickles given to the Authors by Alfred Hills of Braintree.

BAKEWELL

The next great name to be mentioned is that of Bakewell, a farmer of Dishley, near Loughborough, in Leicestershire, who was born in 1725. He devoted his attention to the improvement of cattle. Before his time they had been leggy beasts, who wandered about over the common fields after harvest or were taken on to the waste to pick up a living as best they could. The sheep were more valued for their golden fleece than the mutton they produced. Bakewell started his experiments about 1745, and by carefully selecting the animals from which he bred produced far more meat per animal than had been done before. Tull had already produced the bread, and when Bakewell added the meat times were ripe for the increase in the population which was to produce the Industrial Revolution, as well as manufactured goods for the Empire overseas.

Another great name in agriculture is Thomas Coke of Holkham. He came into his estate in 1776, and there carried on the experiments which were to raise his rent roll from £2200 in 1776 to £20,000 in 1816. He carried on the good work of Townshend, and worked on the principle that "No fodder, no beasts; no beasts, no manure; no manure, no crop."

Coke must have been a very pleasant man. It was in 1778 that he started the meetings of farmers at his home which were held annually afterwards and became known as the Holkham meetings. They were held in the great house which had been built by Coke's ancestor, Lord Leicester. This house was started about 1734 and was a quarter of a century in building, and seems to have been inspired by Lord Leicester and his friend, Lord Burlington, with professional assistance from Kent, but was carried out by a Norwich architect, Matthew Brettingham. It is shown on D, Fig. 33.

Though not built by Coke himself, Holkham well illustrates a great eighteenth-century house, and the eighteenth was the century for great houses. The chart

COKE (OF HOLKHAM)

on p. viii gives the dates of some of these, and in many cases they now remain as an embarrassment to their owners in these




FIG. 19.—Wooden (Sycamore) Trencher.

harder days. When they were built, however, they were centres of life centred on the land. The Holkham gatherings lasted for a week, and were attended by hundreds of people from all over the world. Agriculture was recognized as the mother of all the crafts and a matter of interest to all; where an aristocrat like Coke was a good man and a leader of the people, he needed a large house to entertain his friends.

Cobbett spoke well of him in his "Rural Rides," when he says that "expressions made use of towards him that affectionate children use towards the best of parents."

Arthur Young is another great name in eighteenth-century agriculture. Born in 1741, he became Secretary of the Board of Agriculture in 1793, and died in 1820. He was an enthusiastic advocate for enclosing the common fields and adopting Tullian methods of tillage.

Prof. S. E. Morison, writing in *The Times* on February 22nd, 1932, 200 years after the birth of George Washington, said of him, "Washington's greatest teacher and deepest love was the land." He was one of Arthur Young's correspondents, and in one of his letters wrote, "How much more delightful is the task of making improvements on the earth than all the vain glory which can be acquired from ravaging it by the most uninterrupted career of conquests." And again, "To see plants rise from the earth and flourish by the superior skill and bounty of the labourer fills a contemplative mind with ideas which are more easy to be conceived than expressed." When Washington went to Mount Vernon in 1759 he found that his estate was in bad order and devoted himself to putting things right.

WASHINGTON

He became an eager student of Tull's Horse-Hoing Husbandry, Horne's "Gentleman Farmer," and Weston's New System of Agriculture, with fox-hunting as his recreation. Perhaps because of this training he was able to do his other work so well.

This is hardly the place to discuss the technical details of the Land Enclosure Acts, but briefly the principle was to gather the land together in larger holdings on which Tullian methods could be carried out. Without the Enclosures the people would have starved during the Napoleonic Wars. The bad part of the Enclosures was that the smaller men became dispossessed of any holding, and so had no stake in the land. They became labourers, and their position was very bad indeed, as we shall see when we get to the beginning of the nineteenth century.

THE WOODFORDE DIARY.—Having dealt with the great men and shown how their fortunes were affected by the times, we can now turn to humbler folk, and here we have been helped by the wonderful diary of a country parson. This deals with the life of the Rev. James Woodforde, who was born in 1740 and died in 1803. So the diarist, in the short span of his life, saw the end of the Old Merry England and the foundations laid of the Empire and Modern Industrial England. The Diary was edited by Mr. John Beresford, and published by the Oxford University Press, and we should like to thank them here for their permission to make use of the information contained in it.

So far as we are concerned the great interest to us in the Diary begins when Woodforde is presented to the College Living of Weston, in Norfolk, in 1774. This was supposed to be worth £300 per annum. As Woodforde was able to lead a very pleasant life at Weston and keep two maids, a footman, a house boy and a farm hand, it shows that money was worth at least four times more then than it is now.

AGRICULTURE.—It must be remembered that Woodforde was not only a parson—and a very good one—caring



FIG. 20.—A Dog Turnspit in an Inn Kitchen at Newcastle Emlyn, South Wales.

By Thomas Rowlandson, about 1800.



FIG. 21 — A Farm Kitchen and Bakehouse, about 1800



FIG. 22 — The Suburbs — Old Brompton Road in 1822

By G. S. S. S.

WOODFORDE

for the souls of his parishioners, but a practical farmer, farming his own glebe. When the farmers who paid him tithe came to the tithe frolics we may be sure that he and they had very much in common and, like Townshend, could discuss "that kind of rural improvement which arises from turnips."

He was assisted in his farming by the faithful Benjamin Legate, whom he engaged in September, 1776, as farm hand at £10 per annum—Ben living at the parsonage house. He was assisted by one of the maids, who did the milking, and the footman and boy helped on occasions.

Women were paid 6*d.* a day for weeding, plus 1½*d.* extra for beer; a man for ditching got 10*d.* a rod of 16½ feet.

The land was ploughed in October with a plough of the type of Fig. 10, and after it had been harrowed and rolled the wheat was set in November. Now here comes a very interesting detail. One would have imagined that, after Tull, his drill would have come into general use, but this was not the case in East Anglia; the seed was often set by hand. Arthur Young, later on, was in the course of his journeys to find that wheat was still sown broadcast, dibbled and set by hand, and sown by a drill. It takes a tremendous time in England for new ideas to filter through.

There is an entry in the Woodforde Diary that they "Finished setting 3½ acres of Wheat this even. The Quantity of seed Wheat to set the whole was 6 bushels 1 peck, that is, as near as can be 7½ pecks to the Acre. Expence of setting it 8*s.* per acre, allowance, etc., included—I had 4 dibblers and 16 setters and they finished the whole in 2 days."

From "Sketches of Rural Affairs" (1851) we find that dibbling was extensively practised in Suffolk, Norfolk and the lighter lands of Essex. "The soil being duly prepared for the crop a light roller is passed over it. A man then walks backwards with an iron dibble in each hand with which he strikes two rows of holes in each sod, and he is

DIBBLING

followed by children, who drop a few grains in each hole. The seed is covered in by a bush harrow and sometimes by a roller," as Fig. 17.

To dibble a hole to set a plant or seed in must be nearly as old as the hills. Its application to setting wheat was first advocated by Sir Hugh Plat in 1600, in his book on "The Setting of Corne." Plat traces the idea to a "silly wench" who, when dibbling some other seed, accidentally dropped some wheat in one of the holes. This did so much better than the broadcast-sown corn that some adopted the idea.

Woodforde's dibbling was fairly successful; he tells us that he measured a stalk of wheat from a field that was formerly a furze cover, and it measured 6 feet 7 inches and about a barley corn, and when harvested weighed 4 stone 9 lb. to the bushel.

Going through the year we find that turnips were sold for 30s. an acre, and these were to be fed off by sheep, not pulled, by old Lady Day.

The point of this was that, though the owner of the sheep got feed for them when it was scarce, the land was well manured for the following corn crop.

So we come to the harvest in August. The oats were cut in the morning before the dew was off them. It was cut with a sickle having the form of a reap-hook, with an edge like a saw, as Fig. 18. You often see sickles drawn which are not all sickle shaped. Fig. 18 has been made from a full-sized tracing made from the blades of old ones, so it should be correct. The Norfolk custom was to give the reapers a good breakfast; at eleven o'clock plum cakes with caraway seeds in them, and liquor to drink; a good dinner with plum puddings and beer again at four. So they did not do so badly.

In September it was usual for the harvesters to call upon the principal inhabitants, and each set was given 1s.—as a harvest thanksgiving one supposes. When one lived as close to the ground as the eighteenth-century

TITHES

people did a good harvest was a matter for general thanksgiving and happiness.

The corn went into the barn and was threshed out on the threshing floor just inside the doors. It was not put up into stacks until threshing machines were invented which could be taken to the stacks. Fig. 92, Vol. II. "Everyday Things," shows the details of the flail used in threshing.

After the harvest the farmers settled their accounts, and in a small village it is quite easy to see that the basis of trade is the exchange of commodities, and money only the medium by which this is done. Farmer, miller, carpenter, smith, butcher, and so on, paid their bills with a few guinea pieces and some small change. The farmer let the carpenter have some wheat, which he sent to the miller to grind, but as he had done work for both of them it did not take them very long to settle up.

When the farmers paid their tithes to the parson early in December, they did so at a party or frolic, as it was called in Norfolk, held in the Parsonage. It was really a very good feed of roast beef and boiled mutton, with plenty of plum puddings, with wine, punch and ale to drink.

The Woodforde Diary helps us as to the rent of land. When Woodforde leaves Ansford for Weston he lets 30 acres in Somerset to a farmer for seven years at no less than £35 per annum, tenant paying all taxes except Land Tax.

Again, 15 acres of charity land was let at £16 5s. In 1801 an estate of about 100 acres near Chichester, in Sussex, was sold for £3500.

FOOD.—Woodforde had not been long at Weston before he was invited to join the "Rotation Clubb," for dining at one another's houses on Mondays. This brings up the subject of food, which plays such a large part in the Diary. Here is the first Rotation dinner which Woodforde gave when his turn came on January 20th, 1777: "A couple of Rabbits smothered with onions, a Neck of Mutton boiled

FOOD

and a Goose roasted with a Currant Pudding and a plain one. They drank Tea in the afternoon, played a pool of Quadrille after, drank a glass or two of Punch, and went away about 8 o'clock." One rule was that the Club did not add a supper or give any vails (tips) to servants. This was an important detail, because tipping was very general in the eighteenth century.

Breakfast seems to have been a lighter meal—oysters and tea and bread and butter, or cold tongue instead of oysters. Elevens at noon was in the nature of a snack. Dinners at two to three were heavy, and followed by tea-drinking, with cake perhaps, but supper about nine was quite substantial enough to be regarded as another dinner. The food was all good and wholesome, though once Woodforde complains of heartburn after eating pike with a sauce compounded of anchovy sauce, walnut pickle and melted butter. Again he has a bad night after roasted lobster for supper. He ate Parmezan cheese in 1779 for the first time, and liked it.

They ate all the coarse fish. Tench is a favourite dish, as is pike, stuffed with a "pudding in its belly."

They were enormous meat eaters. For example, on December 7th, 1790, Woodforde pays £46 5s. for a year's meat, and in the same period spends £22 18s. 6d. for malt, and only £5 7s. 6d. for 48 stone of flour. He may of course have provided the miller with his own wheat. As breast of veal and pork was 3½d. per lb. and hind quarter of lamb and turkey 4½d. per lb., turbot 6d. per lb., salmon 7d., and a pair of soles weighing 1 lb. cost 3d., oysters 8d. per score, we can see the quantities of food which were consumed. There can be no doubt that far more people died of over-eating in the eighteenth century than starvation; they were continually taking rhubarb and vomits.

People brewed their own beer, and for 36 gallons allowed 1 coomb (4 bushels or ½ quarter) of malt and 1½ lb. of hops.

The large houses could brew eight barrels at a time.

MEAD

Mead was another home-made drink. 14 lb. of honey were put into 4 gallons of water, with ginger and two handfuls of dried elder flowers, and boiled for more than an hour, and skimmed meanwhile. It was then poured into a tub to cool, and a large gravy spoon of fresh yeast added when almost



FIG. 23.—A Turnspit.

cold, and kept in a warm place at night. The mead was drawn off next day and put into a barrel. We have made mead from this recipe, and excellent stuff it is, with, curiously enough, a slightly beery flavour.

The tea was bought from a smuggler, and even then cost 9s. and 10s. 6d. a pound. From the same source a tub of gin (19 bottles and 1 pint) cost £1 6s., and half an anchor of rum £1 15s.

It is misleading to judge the drinking habits of the eighteenth century by our own time. Woodforde's niece Nancy came to live with him, and a very nice person she was. She had a bad knee, and her doctor prescribed at least a pint of port wine a day ; to be on the right side she drinks "between a Pint and a Quart"—say $1\frac{1}{2}$ pints—as medicine !

All the eighteenth-century table appointments were very beautiful ; the china, stoneware and silver have never been bettered, but these must have been kept for the parties. In the *Lonsdale Magazine*, 1822, we find that "the richer sort of people had a service of pewter, but amongst the middling and poorer classes the dinner was eaten off wooden trenchers," as Fig. 19, turned out of sycamore.




FIG. 24.—Idle Back.

While we are dealing with food we will return to the question of the vails, or tips, which were not allowed at the dinners of the Rotation Club. Tips must have made a substantial addition to eighteenth-century wages—you tipped after a dinner-party and on every other possible occasion. The wages seem very low until you remember the value of the money. A maid got £5 a year, and perhaps picked up as much more; it was really the equivalent of £40 a year to-day. A charwoman was 6*d.* a day.

COOKING.—Food leads us naturally to cooking, and there were no very great developments in the eighteenth century. In a

country parsonage they probably cooked their food in much the same way as shown in Fig. 20, from the original by Rowlandson. This is interesting, as it shows a dog as the power for turning the spit. In other turnspits the power was supplied by a weight which had to be wound up. We illustrated a beautiful specimen of this type in Fig. 65, Vol. II. Perhaps the house boy was sometimes called the skip-jack because he had to skip to this type of jack to wind it up.

The meat was roasted in front of the fire and basted as it turned round on the spit, and the fat which dripped out

DIGESTERS

of it into the pan under was called dripping. Fig. 23 shows a very simple arrangement where the spit was turned by a boy. Now we come to a pretty problem. In 1787 Woodforde had two stoves put up in his kitchen. Were these the new-fangled kitchen ranges which we discuss on p. 181? We rather doubt it ourselves, and think the ranges were for the smaller houses




FIG. 25.—Suspended Frying Pan.

which were beginning to be built in the industrial towns. In the country the old open fire and roasting continued for a long time.

Over the fire hung a great kettle on an adjustable hanger to supply hot water, because of course there was no boiler, or any tap over the kitchen sink. The kettle was fitted with an ingenious little contrivance by which it could be tipped to pour out boiling water, as Fig. 24. A caldron could be suspended in the same way for boiling meat or making porridge, or a frying pan, as Fig. 25.

Papin's Digesters may have continued in use. John Evelyn the diarist mentions how, on April 12th, 1682, he went to a supper with several members of the Royal Society where all the food, both fish and flesh, had been cooked in a digester with less than 8 oz. of coal. The digester was really a large saucepan with an air-tight lid fitted with a safety valve. Evelyn says that the hardest bones were made as soft as cheese, that the food was delicious, and that "this philosophical supper caused mirth amongst us." Of course all the pots and pans

BAKING

which were used over a coal fire got filthily black and dirty.

The eighteenth-century baking was done in the brick oven. This came on the side of the open fire, so that the smoke from the oven when it was lighted could escape up the main chimney (Fig. 21).

The oven itself was circular in plan, and domed over in brick. A bundle of faggots was put inside the oven and lighted with hot ashes. When these had burned themselves out the hot ashes were raked on one side, and into the oven went the bread and all the pies and cakes, and the entrance was closed by an iron door and, as there was no chimney from the oven, or escape for the imprisoned heat, except through this doorway, the cooking was done. It was really exactly the same principle as the cooking hole outside the huts in the New Stone Age, where, after the fire had burnt itself out, the food was cooked by turves heaped over the hole. It may of course be just so much antique imagination, but one of the authors spent a considerable time in a farm-house in Kent when young, and in this way learned to love the land and farmers and all their doings. The loaves there were made of home-grown wheat ground into flour in the local windmill; their shape was that of large buns; the colour of the bread greyish; its texture close and smell most appetizing, and it possessed remarkable staying powers. Whether any other ovens were used besides the large brick ovens we cannot say. Camp ovens as Fig. 26 were advertised for sale by the Carron Co., of Falkirk, in 1782, and they tell us that they still sell these ovens for use in the country places in Ireland, Australia and New Zealand. Made of cast iron, their sizes vary from 6 to 24 inches in diameter, and they are provided with a cover like a saucepan lid. Pushed into the glowing ashes of an open fire on their short feet, they can be used for baking, frying, stewing or boiling. It would be excellent practice for the juvenile members of a family living in the country to invest in a camp oven, build a camp round

PUDDINGS

it and see if they could bake, fry, stew and boil, all in this wonderful implement. If the eggs and bacon carried on into the stew what matter? It would be sooner than later—that is all.




FIG. 26.—A Camp Oven.

The girdle, as Fig. 27, was suspended over the fire, and on it the cakes, made of a batter of buttermilk and flour, were cooked—anyone who has eaten these all hot, and split with a pat of dairy butter inside, will agree that they are very good eating indeed; and these we once ate in a Welsh farm in prodigious quantities.

There is another interesting cooking note in the Woodforde Diary. Niece Nancy had been making jam, and complained of giddiness after. Woodforde thought she was “too long at the stove where charcoal was burning tho’ the outward Door was open all the time.” This meant the kitchen door, because the stove was probably no more than a raised brick hearth on which charcoal fires could be made, and saucepans used over them on tripod stands. Such a raised hearth can be seen in the old kitchen at Hampton Court. Remember, a saucepan started life as a small deep pan with a handle, in which sauces could be made. When Nancy made red-currant jelly she used 4 lb. of currants and 4 lb. of best lump sugar, which cost 1s. 2d. per lb. She made as well cakes, tarts, custards and jellies when they had parties. The plum puddings served at Tithe frolics were made of 1 lb. of sun raisins, 1 lb. of suet, 1 lb. of flour and two eggs.

Then all the washing was done at home, and they washed every five weeks. If they changed their clothes as frequently as we do they must have had a tremendous




FIG. 27.—The Girdle.

amount to wash, but we don't think they did. There is an amusing note in Boswell's *Life of Johnson*. Johnson was talking with Dr. Burney about a poor mad poet, one of whose failings was that he did not love clean linen, and then Johnson added, "I have no passion for it." However that may be, there was enough in the Woodforde household to em-

ploy two washerwomen for two days, who were paid 6*d.* a day each, plus breakfast and dinner; the ironing, done by the maids, took another two days.

When the chimneys wanted sweeping the chimney sweep came with his boy, who climbed up the flue, brush in hand. Woodforde wrote that when his sweep, Holland, came to him, "he had a new Boy with him who had likely to have lost his Life this Morning at Weston House in sticking in one of their chimneys. I gave the poor boy a shilling." It seems extraordinary that such things could happen. In the nineteenth century, when brushes were introduced, the sweeps who used the new brooms called themselves Mechanical Chimney Sweeps.

As well as cooking and washing the butter had to be made. The milk was brought in and poured out into large pans and scalded over a copper (Fig. 21), and then placed in the dairy to cool. The cream was skimmed by a flat skimmer and came off in thick golden folds. For a minute it was held while the milk drained away through holes in the skimmer, and then the cream went into a crock, and the skim milk into the swill-tub for the pigs. The cream went into the churn. Fig. 28 shows one of 1 h.p., but




FIG. 28.—1-h.p. Churn formerly at Broughton Manor Farm, near Brierton, Bucks, now in the Science Museum, London.

BUTTER



FIG. 29.—A Wooden Measure.

generally the farmer's wife supplied the power which turned the handle. The churns were either of plunger or barrel type, mounted on a stand, and inside the barrel long blades beat the cream into butter. Sometimes it took a long time for the butter to come, but when it did and the churn was opened the butter was found like granulated crumbs in the buttermilk. The butter was taken out and washed, and smacked with pats to give it shape in the kitchen sink (Fig. 21), which was a very large one made of stone, and instead of water taps there was a pump, and you plied the handle good and hard to pump up the water you wanted to wash the butter, and you used platters and bowls and pats and moulds to give it shape, all made of wood. In fact, most of your utensils were made of wood or earthenware, because enamelled iron had not been invented. Fig. 29 shows an interesting wooden measure. In Norfolk the butter was sold by the pint and not the pound.

Skim milk introduces pigs and pig killing. Pigs mean pork, bacon, sausages and oddments which are all edible. For example, souse was pickled pigs' feet and ears, and black puddings are as old as the hills. The goats' bellies filled with fat and blood mentioned in the "Odyssey" were black puddings.

We have mentioned all these things because we wanted to make the point that it was very necessary for the

LIGHT

eighteenth-century woman to know her job. Almost everything was done within the home, and little help came from outside. Woodforde of course was fortunately placed; he was a bachelor, and lone men have an uncanny knack of finding devoted women who will work their fingers to the bone for them; and as there were very few, if any, labour-saving appliances it did mean hard work, but it did provide work to do. Take lighting for one example; to-day we enter a room and by turning on a switch light up the room at once. In the eighteenth century they only had candles, and this meant cleaning candlesticks and using snuffers to keep the wicks in order while the candles were burning, and they guttered in draught, so that the candlesticks had to be cleaned. Though the light was soft and beautiful, you wanted many candles to make a good light. Primitive oil lamps as Fig. 30 were used.




FIG. 30.—Scottish Cruzie.

We should like to close this chapter with a strong recommendation to our readers to read the Woodforde Diary for themselves. There are five volumes, but after a little this will only be a cause for regret. We know of no other books which give so true a picture of eighteenth-century everyday life in the country. There are many other diaries, some gossipy, others scandalous; some political, and others military; but there is only one Woodforde.

SQUIRE AND PARSON

There is not only the life in the village, but its government by squire and parson ; a thing the Radicals used to shudder at, but now that it is going others may be found to regret this. You must have some form of government ; either a council, or a Soviet if you will, and these will have to be very good indeed to be better than the mild autocracy practiced by Custance, the Squire of Weston. He evidently belonged to that class of whom Cobbett wrote (p. 114) "as the resident native gentry attached to the soil and knowing the people." If the squires enjoyed the privileges of their position, they accepted their responsibilities as well and played Providence in an amiable fashion.



A conversation piece in silhouette.



FIGS. 30A, 30B. — A Fishmonger's and a Butcher's Shop.

Coloured engravings by James Pollard.



FIG. 31 —The Waggon, c. 1800.

By W. H. P. & Co.




FIG. 32 —A London Mail and a Stage Coach on the Brighton Road, c. 1830.

By J. P. & Co.

CHAPTER II

THE EIGHTEENTH-CENTURY BUILDER

WE can now pass on to the building trade, which is the second of the three great trades we are considering, and it was a very important one indeed in the eighteenth century—kings, princes and nobles, as well as ordinary common or garden people, considered that it was necessary for them to know the rules of architecture as laid down by Andrea Palladio. He was an Italian architect, born in Vicenza in 1518, where he did most of his work, and died in 1580. His book "*Quattro Libri dell' Architettura*," was first published in Italy in 1570, and in England in 1676, and became the Bible of the Later Renaissance. Inigo Jones, the architect of the first completely Renaissance building in England, the Banqueting Hall, Whitehall, London, 1622, had a copy of Palladio which he annotated, and this is now in the Library of Worcester College, Oxford. Jones was in Italy in 1600, and again in 1613-14. In Palladio the Tuscan, Doric, Ionic, Corinthian and Composite Orders of Architecture, in the Roman manner, could be studied in detail, with all the parts properly proportioned, on the basis of the module, which was half the diameter of the column: and not only the Orders but the plans of buildings themselves, showing how the Italian architects had translated Roman details into bricks and mortar. Palladio, then, ranks with Vitruvius, of whom we had so much to say in our Greek books, and whose book was written about the time of Augustus, at the beginning of the Christian era. Palladio would have known Vitruvius' book, because there were many editions of it brought out in the sixteenth, seventeenth

WREN

and eighteenth centuries, and it was translated into many languages. One point should be borne in mind, and that is that Palladio was concerned with the Roman version of classical architecture.

So we come to the beginning of the eighteenth century, and we showed in Vol. II. of E.D.T. how far the English architects had advanced by the time Queen Anne was on the throne. We gave as an example of domestic architecture Fig. 96, of a house in the Close at Salisbury, and there is no better house of the middling type in England. We show the type again as A and B, Fig. 33, in this book. The pleasantly designed door and window over, as the central feature, with the sash windows with good fat bars, and sometimes slightly bevelled glass as at Hampton Court, on either side all under the roof, with its good cornice, as a brim to the hat, and the wrought-iron railings across the front, go to make up a pleasant picture in peaceful surroundings of English architecture at its very best. It was the genius of Wren, following in Inigo Jones's footsteps, that made this possible. Wren was like some old alchemist—he could draw his details from Classical Rome, assimilate the notions of Dutch William and the practical requirements of an Englishman, and, passing them all through the crucible of his brain, produce houses which were real homes, and this is more than can be said of some of the later palaces. Think of Belton House (1689), or the house at Chichester which is now the Council Offices, or Hampton Court itself, with its mellowed brick and stone—all are charming. At Hampton Court you have the ironwork of Jean Tijou (1690–1710), which led to a renaissance of that craft, shown in Fig. 71, Vol II.

The Fire of London helped forward this movement—of wood before, it was rebuilt after in brick, and the building trade benefited by the opportunity and set a fashion. Celia Fiennes, to whose journeys we refer in Vol. II., talks of the houses built in the provinces in the "London manner."




FIG. 33.—Evolution of the English House in the Eighteenth Century.

A.—The Moot, Downton, Wilts.
B.—Council Offices, Chichester, Sussex.
C.—Mereworth, Kent.

D.—Holkham Hall, Norfolk.
E.—At Lavenham, Suffolk, c. 1750.
F.—At St. Albans, c. 1783.




FIG. 34.—Holkham Hall, Norfolk. Plan of the Principal Floor.

BURLINGTON

Internally the houses of this period were as good as the exteriors. Rooms were panelled in oak, as Fig. 58 in Vol. II., which is one of the rooms at Belton—one run of panels under the dado rail, and one range of large panels over, and the doors and fireplaces very much part of the panelling, but enriched perhaps with carving from Grinling Gibbons's bench. The woodwork was superb, and can be seen by Londoners at St. Paul's, or in the City churches. The staircases were massive performances in wood. In the mid seventeenth century the balustrades were sometimes formed of flowing scrolls of acanthus, and we illustrated one of these in Vol. II., Fig. 59. The supporting string under was straight, and the steps were housed into this, which was called a Close String. Sometimes the balustrade was formed of large turned balusters. You can see many specimens in Gray's Inn and the Temple.

With the advent of the Georges a certain pomposity crept into planning, and people began to build in a grand rather than a comfortable manner. It is amazing now to think that any one man and his family can have contemplated living in some of the piles of masonry which date from this period.

Lord Burlington was the great patron of the Palladian movement. Burlington lived at Burlington House, in Piccadilly, and when our readers go to the Royal Academy they pass in under the new façade of 1716, which was designed by Colin Campbell, who lived with Burlington. The arcaded entrance and the Diploma Gallery on the top were added much later. Colin Campbell published "*Vitruvius Britannicus*" (1715), and included the Burlington House front in it; but far more important than this was Mereworth Castle, in Kent, as C, Fig. 33, which was illustrated as well in the third volume, published 1725. Campbell says this house was covered in in 1723.

The importance of the house is that it was an attempt to transplant pure Palladian architecture. Palladio in his second book or chapter illustrated a villa that he had

PALLADIO

built for a Monsignor Paolo Almerico, and Mereworth was copied directly from this and surrounded by a moat. Campbell says, "I shall not pretend to say that I have made any improvements in this Plan from that of Palladio." So that is how it was in the early eighteenth century Palladio was the architect's Bible, Holy Writ that must not be altered. In the Palladian villa the four porticoes and the central hall made cool places where the glare of the southern sun could be avoided, but at Mereworth, where only two are real porticoes, the only purpose they served was to cut off the pale northern sun. Then fire-places had to be added at Mereworth, and Palladian villas are not improved by chimneys, so the twenty-four flues were brought up in brick arches to discharge their smoke out of the top of the dome (see Fig. 33).

Mereworth, then, is amazingly interesting, but it is the beginning of the end. Neither Jones or Wren would have designed in such a fashion. They were like those admirable birds who, content to swallow almost anything, yet pre-digest it before they beak it on to their young. So imagine Lord Burlington and Campbell sitting together in Burlington House with Palladio open before them, and determining to try this Almerico villa on the Hon. John Fane, who was the builder of Mereworth. He was amenable, because Campbell says, "Never architect had a more beneficent and liberal Patron"; and they were not wantonly wicked, because Burlington built himself another villa, at Chiswick, in 1727, in much the same manner. Still they seemed to have tried it on the dog first. Burlington was in Italy in 1718, and brought back with him Kent, who was a young painter then, and was to become an architect after his association with Burlington. He lived in Burlington House—this was one of the nice things of being a young architect in the eighteenth century; your clients not only provided you with jobs, but threw in board and lodging.

Kent is thought to have helped with the interior



FIG. 35.—Staircase, John Street, Bedford Row, London (1760).

GIBBS

decorations of Burlington House, and he published a book in 1727. A little later he was assisting Burlington, who was advising his friend, Thomas Coke, on the house he intended building at Holkham, in Norfolk. This was started in 1734, and the elevation is shown in D, Fig. 33, and the plan in Fig. 34, with an interior in Fig. 36A. This type of plan of a central block with outlying wings connected by corridors is better treated at Holkham than other examples, such as Kedleston, Derbyshire (1761), where the connecting corridors are much longer and curved in plan. Thomas Coke, who became the Earl of Leicester, died leaving no children, so that the estate on his death passed to his grand-nephew, the great Coke of Norfolk, of whom we have written on p. 22.

James Gibbs, the architect of St. Martin's Church, Charing Cross, and St. Mary le Strand, another very gifted man, published a *Book of Architecture* in 1728—that was one of the troubles; there were too many books, and the architects designed according to Palladian rules instead of practical considerations of comfort. Inside the houses in Palladian times the warm background of oak panelling gave way to plastered walls, with moldings planted on, and the doors and fireplaces, instead of being one with the walls, often stood apart by themselves as architectural compositions, complete with columns and entablatures, in the various orders. The ornament was far more architectural and mechanical than in Gibbons's day, with an inclination to rococo work at the beginning.

In the eighteenth century the staircases began to have "cut strings"—that is, that the support was cut out to the shape of the stairs, and the balusters stood in groups of threes on each step. These were lighter than in the seventeenth century, and often beautifully turned in twists and spirals.

The Dilettanti (which did not mean then what it has come to mean now) Society was established in 1734 by five gentlemen who had travelled in Italy and wished to con-




FIG. 36.—In the Chinese manner, 1760.

(*Bed and Dress from the Victoria and Albert Museum, London.*)

WALPOLE

tinue their studies. Italy was the source of inspiration. The Society of Arts was founded in 1753.

It was in 1741 that Horace Walpole returned from his Grand Tour, and he, for all his affection towards architecture, was to be one of the first to introduce doubt into the minds of the architects. The Palladian architects had carried on the Classical tradition, even if they did it in a pompous way. Walpole was to suggest that they might follow a fashion instead and become Gothicists, or anything else which took their fancy. Walpole, in fact, was a Goth. It was in 1750 he wrote, "I am going to build a little Gothic Castle at Strawberry Hill," a house at Twickenham, Middlesex, which he had bought two years before. This is a long time before the Wyatts and Pugins were to attempt the impossible, but Walpole was not the first Goth. Lord Dacre had altered and enlarged Belhus, Essex, a Henry VIII. house, in the same style, in 1745, and Batty Langley brought out his "Gothic Architecture Restored and Improved" in 1742. Fig. 37 shows the staircase at Strawberry Hill with its "Gothic fretwork paper." Peter Atkinson, a York architect, was another who designed in the same manner. He added a "Gothick" front and gatehouse to Bishopthorpe, in York, the seat of the Archbishop of York, in 1765. Atkinson took an ordinary Georgian oblong building with a central pediment, and trimmed it up with a Gothic porch, sham battlements and arched windows.

We have said these people were attempting the impossible, and their followers ever since have been doing the same thing. The real mediæval Gothic church and cathedral was the sign manual of a society constituted in such a way that it is far more foreign to us than those of Greece and Rome. We find it difficult to understand the Middle Ages, and mock Gothic architecture is consequently a terrible and painful thing.

So it was with the early Gothicists. The work at Belhus is poor, thin and lifeless. In one of the rooms

“GOTHICK”

Dacre put a classical marble mantelpiece, which Walpole, who had gone there in 1754, noted as “one little miscarriage into total Ionic.” Another interesting thing at Belhus is that a new staircase, built in 1745, was carried out in a better imitation of Jacobean than the Gothic work. In one of the drawing-rooms the walls were covered with canvas painted to look like oak, and then on top Gothic arches and columns, printed on paper, were cut out and pasted on to the background. “Capability” Brown was called in, and recommended a 10-acre lake of “Form very irregular.”

Still this early “Gothick” revival fitted in very well, as all architecture does and must, with the spirit of the time. People were beginning to be tired of classical rules and wanted freedom and romance.

The opening to the fourth chapter of Henry Fielding’s “History of Tom Jones” (1749) is very interesting. We are told that “The Gothic stile of building could produce nothing nobler than Mr. Allworthy’s house—it rivalled the beauties of the best Grecian architecture.” The description of its surroundings strike the new romantic note: there is a grove of old oaks—the lawns slope down—springs gush out of fir-covered rocks, and cascades tumble over mossy stones with lesser falls into a lake from which a river winds its way to the sea. One of the prospects is terminated by the ivy-clad towers of a ruined abbey, and then the country (in Somerset) rises to a ridge of wild mountains, the tops of which are above the clouds.

It was not the end, but it was the beginning of the end, because from now on there were constantly changing fashions in architecture, instead of continuous growth and the feeling of permanence. Buildings, like a woman’s hat, looked foolish and old-fashioned in a year or so.


The Chinese fashion came into being because of the ideas which Sir William Chambers brought back with him from China. He published a book on Designs of Chinese Buildings in 1753, and another on the Chinese work he did

CHINESE

at Kew Gardens in 1763. The architects and furniture-makers managed this Chinese work a good deal better than the Gothic, and some of their interiors were very quaint and amusing, especially if the walls were covered with the hand-painted Chinese wall-papers which were imported about this time. Wall-papers started with patterns raised up in "flock," in imitation of hangings, but these were not much used until the middle of the eighteenth century. Figs. 35 and 36 show Chinese treatments. The staircase from John Street, Bedford Row, of about 1760, is very interesting and beautifully made of mahogany. The bed from the Victoria and Albert Museum is in black lacquer and gold.

These changing fashions were caused by the fact that many people were being subjected to the awful trial of making money too quickly. The South Sea Bubble was the beginning of modern speculation and gambling. Tull had shown the way to raise the rent of land, and the Nabobs were beginning to come back from India—they were different from the old landed gentry and so had to have something different, or their womenfolk had to. Still the Goths and the Chinese did not have it all their own way. Robert Adam came back from his Italian tour in 1758 and carried on the classical tradition, and became the leading architect, until he died in 1792, leaving behind him a peculiar impress on design. His death was followed by the declaration of war between England and France in 1793, and this closed a period both architecturally and politically.

Adam does not appear to have gone to Greece, but did go to Spalato, or Split as it is called now, in Dalmatia, and there made a study of the Palace of Diocletian. The Roman work here, though it is of the greatest interest because of the peculiar freedom with which the classical details are used, is very coarse in feeling, and without any of the delicacy of Adam's work. It would seem as if Adam must have gone to Pompeii when he was in Italy, and



(a) The Dining-Room, Holkham, Norfolk, by William Kent,
with Regency Furniture.



(b) Mecklenburgh Square, Bloomsbury.

(a) Palladian, and (b) Regency.

FIGS. 36A, 36B—Contrasted Interiors:




FIG. 37 —Gothic Staircase at Strawberry Hill, Twickenham, c. 1750
Designed by Horace Walpole

By E. T. Atwood

NEWGATE

A. KEEPERS HOUSE WITH CHAPEL BEHIND ON 1ST FLOOR: B. TURNKEYS LODGE: C. PRISONERS WARDS: D. OPEN YARDS: E. INFIRMARY F. SEPARATE CELLS: G. PRESS YARD: H. CONDEMNED CELLS. I. CONDEMNED ROOM: J. VISITORS ROOM: K. WOMENS YARD: L. Do. FOR CONVICTED WOMEN WITH THEIR




FIG. 38.—Newgate, from Britton and Pugin's "Public Buildings of London" (1838).

have been influenced as well by the publication of Stuart and Revett's book on the Antiquities of Athens in 1762, four years after Adam had set up in practice, and "*Antiquités Etrusques Grecques et Romaines.*" published by Sir William Hamilton in Naples in 1766. Adam's work certainly had a Greek flavour. Wedgwood, who opened his works in 1769 and called them "Etruria," was another who was influenced in this way, as was Flaxman, who worked with him.

Leverton was another architect who followed the same tradition as Robert Adam. Their smaller houses became much plainer outside—yellow bricks were used, and the cornices and string courses were all flatter. The sash bars of the windows were made much narrower as the century proceeded. Inside the typical Adam decorations were carried out in a composition of whitening and glue stuck on to the walls, and the flatness of this called for colouring, which was carried out in very light tints of delicate greens and blues, lilacs and dove greys, and faint yellows. Set in these painted walls were very beautiful mahogany doors, and this wood began to be used about 1720. The typical

ADAM

Adam fireplace was made of marble and inlaid in a very dainty fashion. Stone staircases began to be used in houses, with very beautiful wrought-iron balusters set into them supporting a light mahogany handrail ; later on cast-iron balustrades were used by Robert Adam.

But Adam must not be thought of as a mere decorator ; he was a brilliant planner of state rooms and could fit great bows and apses and work in the twists of his compass with anybody. He was no mere copyist ; all the information he gathered passed through his brain and was given out with the true Adam impress. He and his brother James published the " Works in Architecture " in 1773, and a book on Spalato in 1764.

Bay windows, which had been out of fashion since Elizabethan and Jacobean times, began to be used again about the middle of the eighteenth century, as E, Fig. 33. F shows a house of 1785, and it should be noted how towards the end of the century the attics, which earlier had been accommodated in the roof, were now given outside walls of their own, so that the house becomes higher.

Sir William Chambers, whose book on Civil Architecture was published in 1759, carried on the more masculine traditions of the Palladian school, and his best-known work is Somerset House, in London (1776).

Now we come to the work of a man who produced one terrific masterpiece, and as it was a prison, and as most of us, with luck, keep out of prison, we have added notes on its use, so that the architectural solution of the problem and the mental attitude of the authorities at the time may be more readily understood.

The masterpiece was Newgate Prison, London, which was pulled down at the end of the nineteenth century to make way for the present New Sessions House. Newgate was the work of George Dance, one of the sons of the City Surveyor who designed the Mansion House. Born in 1741, he went to study architecture in Italy in 1758 and, returning




FIG. 39 —The Debtor's Door, Newgate Prison, London, in 1821.

(George Dance, Architect, 1770)




FIG. 40. The Condemned Sermon, Newgate Chapel, 1809.
By Pugin and Bechtold.

DANCE

to England in 1764, set up in practice. In 1768 he was elected as one of the original members of the R.A., and he was commissioned to design Newgate, and the buildings, started in 1770, were nearly destroyed by fire in the Gordon Riots in 1780, and finally remodelled, improved, and completed in 1782. The extraordinary thing about George Dance is that while his other work, like All Hallows Church, London Wall, and St. Luke's Hospital, Old Street, were scholarly buildings, Newgate had the indubitable hall-mark of genius about it. Think of the difficulties of the problem—the site had a frontage of about 130 feet to Newgate Street, and 300 feet to the Old Bailey. Dance put the keeper's house in the centre of the long side (see Fig. 38); behind came the chapel, on the first floor. The north or Newgate Street end of the building was occupied at first by debtors, male and female. There was an internal courtyard, divided up by low walls, which are shown on the plan, and around these yards came the wards in which the debtors lived, rising three stories above the pavement. In Ackermann's "*Microcosm of London*" (1808) it states that a room of 23 feet by 15 feet was usually occupied by fifteen to twenty people. The plan at the south end of the building was much the same, and was occupied by felons and persons confined for offences against the Government.

If our readers, after having studied the plan of Newgate (Fig. 38), will turn to our chapter on Sanitation and realize what the sanitary conditions of buildings were like in London in the early nineteenth century, they will understand why gaol fever was rampant in Newgate, with its narrow courts and lack of drainage. Conditions inside the gaols were terrible, and the fettered prisoners not only died themselves, but were a source of danger to the citizens when brought into court. Fig. 41 shows the Justice Hall, commonly called the Sessions House, which adjoined Newgate, where the prisoners were brought to trial through a passage connecting the two buildings. Ackermann




FIG. 41.—The Sessions House, Old Bailey, London, in 1809.

PRISONS

illustrates the Court, and says that it had been "rebuilt entirely of stone . . . and that every precaution has been taken to render it airy, and to prevent the effect of the effluvia arising from that dreadful disorder, the gaol fever." The prisons were farmed out to people for profit, and the keeper charged exorbitant fees. Poor Cobbett had to pay £12 12s. a week (see p. 113). John Howard, the great prison reformer, had visited gaols at the end of the eighteenth century and drawn attention to their terrible condition. He pointed out that the real use of a prison was to reform the criminals and train them to habits of industry, but the war prevented reform and it was not till after 1815 that any progress was made, and it was due mainly to the Quakers. Gaol Acts were passed in 1823-24, and Inspectors of Prisons appointed condemned Newgate as a monstrous place, and about 1835 Pentonville Prison, with its tiers of separate cells, radiating like the spokes of a wheel, became the accepted type of plan.

To revert to Newgate, one thing to note in Fig. 38 (which, by the way, dates from Britton and Pugin, "Public Buildings," 1838) is how the prison, with the exception of the Keeper's House, looked inwards on itself, not outwards on the world. Through no window could the unfortunate felon see his more fortunate fellows who were free, and what is curious, Dance seems to have been helped by this, because the windowed Keeper's House was the least satisfactory part of the design. In our drawing (Fig. 39) just the edge of the Keeper's House shows on the left. In the centre is the Debtors' Door, and on the right the end of the Felons' Blocks. Here and at the debtors' end, and on the return frontage to Newgate Street, the walls rose sheer up to the cornice in plain rusticated blocks of masonry, and the only relief was the niches we have shown, deeply shadowed and housing rather gay eighteenth-century figures. These figures always seemed to us a grim jest because of their gaiety. One held a cap of Liberty, and another a cornucopia with fruit and flowers, and the

DEBTORS



FIG. 42.—Knocking off the Irons in the Press Yard, Newgate, 1821. (After Cruikshank.)

inhabitants were not free, and the harvest garnered in Newgate was a sad and sorry one—as one looked at the figures the building became grimmer. Relief was given to the composition by breaking back the line of the walling around the Debtors' Door as shown in Fig. 39, and another of similar design on the north side of the Keeper's House, and these doorways Dance treated in a very satisfactory way, from the architectural point of view; and here he used leg-irons and fetters and chains as an ornament. And there was nothing more than this—no shams anywhere—just the great sombre walls shadowed by their heavy cornices, and practically the entire face of the building had been pitted with the mason's chisels into what is called a "rusticated" surface, and the London soot had found lodgment in the rustications, which added to the sombreness except where, here and there, the surface of the Portland stone had been bleached white by sun and rain.

It was impossible to pass Newgate without a lowering of the spirit—it spoke of man's inhumanity to man. How Dance managed it we cannot say—perhaps as a young man



FIG. 43.—The East Front of Ayot St. Lawrence Church, Hertfordshire.

(*Nicholas Revett, Architect, 1788*.)




FIG. 44.—Interior of Ayot St. Lawrence Church, Hertfordshire

Nicholas Roeb, Architect 1888.

YEOMAN OF THE HALTER

coming back fresh from Italy he remembered the heavy walls of the Palazzo Strozzi, or the Pitti in Florence, and, taking them from the sun, achieved the results in our grey gloom: or he may have been influenced by the extraordinary prison drawings published by Piranesi in 1751. In this "Carceri" series the great Italian draughtsman "let himself go," and in interminable staircases and endless corridors showed poor humans struggling for freedom denied to them. Dance himself was a very fine draughtsman.

Fig. 40 shows the chapel at Newgate during service on the Sunday preceding the execution of criminals. Quoting from Ackermann's "Microcosm," we are told that: "Upon this occasion, a suitable sermon, called *the condemned sermon*, is preached by the ordinary; during which a coffin is placed on a table within an inclosure, called the Dock; and round this coffin are prisoners condemned to die." The public were admitted at charges varying from 6d. to 2s., the money received being the perquisite of the turnkeys.

Fig. 42 shows the Press Yard in Newgate on the morning of an execution. The yard was long and narrow, and contained a great number of cells one above another, three stories in all. Each cell measured 9 feet by 6 feet. When the death warrant arrived at Newgate the prisoners to die were allowed the freedom of the yard, and here the clergyman attended them, and generally sat up praying with them all the night before the execution. In the letter-press describing the plate in *London Life*, from which we have drawn Fig. 42, the figure on the left talking to the parson is said to be "Lively Jem," who ran through a fine fortune before coming to a sad end. His leg-irons have been removed in the same way as those of his sturdy companion. The Yeoman of the Halter is in waiting to put the ropes about them, and the Sheriffs are in attendance to see that the sentence is carried out; meanwhile the tolling bell added "a terrific solemnity to the proceedings."

Then the procession was formed and passed out of the

EXECUTIONS

Debtors' Door to find the scaffold erected in the Old Bailey, as shown in Fig. 39. Again quoting from Ackermann, we read that "The mode of executing criminals at Tyburn had long been complained of, as tending rather to introduce depravity, by a want of solemnity, than to operate as a preventive to crimes, by exhibiting an awful example of punishment. To remedy this evil, both the place and manner of execution were changed : a temporary scaffold was constructed, to be placed in the open space before the debtors' door of Newgate, having a movable platform for the criminals to stand on, which, by means of a lever and rollers, falls from under them. The whole of this building is hung with black ; and the regulations which are observed on these mournful occasions, are calculated to produce that impression on the minds of the spectators which is the true end of all punishments."

We know now that public executions attracted the worst elements in the population. It was one of the things to do. The night of waiting was spent in drinking to pass the time, until the dawn came and the poor wretches passed out of the Debtors' Door to their doom. By 1840 people were only hanged for murder, but they were hanged publicly till 1868.

Now look once more on Dance's design for Newgate and see how well he realized all this in stone. Perhaps it is just as well that Newgate was pulled down. The building which succeeded it, if very poor architecture, is at all events rather kindlier in appearance.

We are interested in Newgate, and have illustrated it rather fully, because it does enable us to understand a side of late eighteenth and early nineteenth-century character which seems very remote to us, and that is their treatment of criminals. If we take the words of Mr. Lewis E. Lawes, our ideal should be to make the criminal "unskilled worker to learn a trade ; the illiterate to acquire the education needed to hold a job ; the wanderer to find for himself a home and responsibility ; the deficient mentally




FIG. 45.—Plan of Ayot St. Lawrence Church, Hertfordshire.

to attain a better understanding of the values of life ; the cynic and perverse to adopt a saner attitude towards society and government ”—reformation rather than punishment.

In the early nineteenth century it was punishment, and capital punishment, not only for murder, but theft and forgery, and as it was the law of the land it met with general acceptance. It is quite wrong to judge our forefathers by twentieth-century standards. We still retain capital punishment for murder, and Mr. Lawes in his book “20,000 Years in Sing Sing” says that he has “been directed to kill lawfully one hundred and fifty men and one woman,” and his experience has convinced him of the futility of capital punishment. So in a few years books may be written on lawful killing as a thing of the past.

Now we shall have to go back to p. 51, where we suggested that Robert Adam was influenced in the detail of his work by the publication of Stuart and Revett’s book on the Antiquities of Athens in 1762. Beyond this the

CHURCHES

book does not appear to have had very much influence at the time of its publication. The Palladian tradition was too strong, and Walpole's "Gothick" caught the public favour first. At the end of the century though, and the beginning of the nineteenth, the Greek Revival was in full blast, and Stuart and Revett came into their own.

Nicholas Revett, born about 1721, was the son of a Suffolk squire. He went to Rome in 1742 and became acquainted there with James Stuart. He was the son of a Scottish sailor, and was born in 1713. While in Rome the two men decided to go on to Athens, and there they made the drawings for their book.

Any design, then, by either Stuart or Revett must be of interest, because we can see if they practised what they preached. The building we have selected is a church designed by Nicholas Revett in 1788.

To find it we shall have to try and persuade such of our readers as can to go to Ayot St. Lawrence, in Hertfordshire. This village is to be found in the pleasant winding lanes of the country to the west of Welwyn, of Garden City fame. You could on the same day see both Ayot and Welwyn, and so be able to contrast the old and new. But the particular attraction at Ayot St. Lawrence, so far as we are concerned, is that you can contrast two kinds of churches there. First there is the original church of St. Lawrence, which gave its name to the village. The nave is twelfth century, to which a north aisle was added in the thirteenth century; the chancel and north chapel are fourteenth century, and the tower fifteenth century, but the church is now ruinous, and ivy is tearing the walls to pieces. Yet as a ruin the old church is part and parcel of the countryside, and as much at home as the cottages of the villagers.

Leaving the old church and walking on to the one which was built by Sir Lyonel Lyde in 1788, we shall find this in the park of Ayot House. It can be seen from the road, and at once it arrests one because it is so evidently foreign

GREECE

to the English countryside. There is a public footpath across the park to the churchyard, and as we walk along this path we approach the east or entrance front shown in Fig. 43. This is strange, because the Christian practice is to have the entrance at the west. The roof of the nave is covered with copper which has turned a lovely verdigris green, and the walls are stuccoed with plaster. As we come nearer the strange classical façade reveals itself as one of great interest, but there is nothing to denote that it is a church—it might be a mausoleum or a dozen other things, and the only Christian symbols are the crosses over the graves in the churchyard. If the sun is shining and the sky is blue the total effect is happy, but if the day is grey and the rain falling the building looks dismal and sad, and like some poor Pan who has gone piping through the woods and lost his way and strayed into a foreign country, so foreign that his friend Echo and attendant nymphs have deserted him. That is the fault with this very interesting building of Revett's—it is an importation from the sunny land of Greece, and not really at home. If we go into the church the first thing which strikes us is the disproportionate size of the porch. If we look at the plan, Fig. 45, we see that the porch is nearly half the size of the nave. We saw the beginnings of this porch in the Megaron at Tiryns, Fig. 59 (Homeric Greece), and the house at Priene, and the pronaos or portico of the Parthenon, Figs. 44 and 17 (Classical Greece), but in the sunny climate of Greece the portico was used as a very agreeable outdoor sitting-room, and it was added to their temples because these were not used for congregational purposes, but as the homes of their gods ; if the people needed porticoes where they could take the air, so did the gods. So the portico which was reasonable in Greece is foolish at Ayot St. Lawrence.

The actual interior of the church (as Fig. 44) is again of the greatest interest, but it would do just as well for a banking hall ; the organ is rather a beauty and appears to be original, but someone has Gothicized the altar and added

STUART

stained glass windows which are not happy ; nor is the modern font in the Wren manner, and manner only. To sum up, then, the fault with the Church is, that it represents drawing-board architecture ; it was designed, and did not grow out of the soil. It is foreign and not indigenous—but here is a problem for the young architect. He will admit that the old church is real English, and the new imitation Greek, yet he will feel more at home sketching the new than the old because he will be more attracted to it.

We do not know if the new church was dedicated to St. Lawrence or Sir Lyonel Lyde, Baronet, but he was buried in the right-hand pavilion of the entrance front, and Lady Lyde in the left-hand one. The English inscription in the front of Sir Lyonel's memorial says that he died on June 22nd, 1791, in the sixty-eighth year of his age, and on the back is a Latin inscription, which being translated explains the building. It is as follows : " Nicholas Revett of Suffolk who spent many years in Rome, Athens and Smyrna, designed, built, and decorated this church according to the examples of ancient architecture which are yet to be seen in Greece and Asia Minor and raised this monument at the expense of Sir Lyonel Lyde Baronet A.D. 1788."

Neither Stuart nor Revett appears to have done very much architectural work. The house in St. James's Square, London, now occupied by the Clerical Life Assurance, is one of Stuart's best works.

Robert Adam also remodelled a Georgian church at Mistley in Essex. With its two towers and cupolas it was like an extra-magnificent stable block. Unfortunately it gave way in 1870 to a " neat edifice in the Early Decorated style," but the two towers remain. The general effect can be judged from the Engravings in Adam's " Works." (p. 76).

That is perhaps all we need say of eighteenth-century building. There was the Palladian tradition still carried on by Chambers and Dance, the more delicate work of Adam and his school, the " Gothick " of Walpole, the " Chinese " of Chambers, and the " Greek " of Stuart and Revett.

CHAPTER III

CLOTHING

THE third great trade is that of the clothier, and in the Northern Hemisphere, with its rigorous climate, it is a very important one indeed. In the Old Stone Age man was a hunter, and clothed himself and his family with the skins of the animals he killed, and sewed them together with sinews, punching holes with a bone awl and pulling the sinew through with another like a crotchet hook. We illustrated his outfit in *Everyday Life Series*, Vol. I—but man did not weave in the Old Stone Age.

In the New Stone Age he learned to domesticate some of the animals, and by the Bronze Age was spinning and weaving their fleeces into cloth. If our readers care to consult Mr. Ling Roth's books they will find how widespread an art weaving has been. The loom on which Penelope wove the shroud for Laertes is illustrated on Greek vases, and, excepting that it is vertical instead of horizontal, the principles on which it worked are the same as the eighteenth century A.D. one illustrated in Fig. 47. Nobody in all the centuries had been hurried or worried; they wove as their fathers had and were content with trifling alterations and improvements—but the loom was not to escape. We have seen that in 1733 Jethro Tull brought out his book and revolutionized the practice of Agriculture; in the same year John Kay of Bury




FIG. 46.—Carding Implement.




FIG. 47.—The Hand Loom up till A.D. 1733.

(Science Museum, London.)




FIG. 48.—Replica of Crompton's "Mule" (1774-9).
(Science Museum, London)




FIG. 49.—Replica of Hargreave's Spinning Jenny (1750-57).
(Science Museum, London)




FIG. 50. Original Spinning Machine
(Arkwright, 1769).
(*Science Museum, London*.)




FIG. 51. Spitalfield's Hand Loom with Jacquard
(*Science Museum, London*.)

SHUTTLES



FIG. 52.—The Hand-Weaver's Shuttle, $9\frac{7}{8}$ inches long.
(*Science Museum, London*)

invented the flying-shuttle, and as this immensely increased the speed of weaving the whole trade was disorganized, with tremendous dislocations and alterations in the lives of the people. To understand this it may be as well to take stock of the position before Kay's invention.

We cannot deal with all the processes in cleaning and




FIG. 53.—John Kay's Flying Shuttle, 1733.
(*Science Museum, London*.)

preparing the wool or cotton before it is spun, but the final one was by the use of carding instruments, as Fig. 46, to arrange the fibres of the material lengthways, loosely rolled into a very delicate rope-like form called a roving. Until Hargreaves invented his spinning jenny (1750-7) this was spun into thread on a spinning wheel, as Fig. 140.




FIG. 54.—The Weaver's Shuttle, 12 inches long, Early 19th Century.
(*Science Museum, London*)

SPINNING




FIG. 55.—The Mechanical Part of Hargreave's Spinning Jenny.

This interesting little machine—for machine it was—had been introduced into England in the sixteenth century. The rovings were placed on a distaff and paid out by hand on to a bobbin on a horizontal spindle turned by foot pedal. One very important detail to be remembered is that the material to be spun was not put on to the distaff in one mass, like cotton-wool, but had already, by means of the cards, been turned into the continuous roving, and the function of the hand was to draw out this roving and give it the necessary stretch which settled the thickness of the thread, and the spinning wheel spun *one thread at a time*.

We can now pass on to the loom before 1733, as Fig. 47. The long threads called the warp were put on the warp beam or roller at the back, and then brought forward as shown to the healds—here each warp thread was passed through a loop on the healds; the healds were attached to heald shafts, and here was a very simple but ingenious bit of mechanism. From the two treadles under came two cords, one attached under each heald shaft. From the tops of the heald shafts went four cords attached to two little yokes suspended on two cords, and free to move up and down like seesaws on them. In Fig. 47, of the four cords shown between the yokes and the heald shafts, the two outer cords are attached to the front heald shaft, and the two inner cords to the back heald shaft.

It is easy to see that with this arrangement if one treadle were depressed one heald would go up, and one

WEAVING

down, and as the warp threads went through eyes on the healds one set of threads went up, and one down. When the other treadle was used another set of threads could be raised and lowered to form the shed or space through which the shuttle was passed. The warp threads were passed through the vertical wires of the reed, and this was arranged on a swinging batten, and banged the weft threads from the shuttle tightly together to form the cloth. This when woven passed on to the cloth beam, which had handles on it so that the material could be rolled up.

The actual process of weaving consisted of throwing the shuttle through the shed with the right hand, say, and catching it with the left. The batten was then swung forward and returned back before the shuttle was thrown through the shed again, this time with the left hand. Fig. 52 shows the type of shuttle used, with its pirn or bobbin.

This was how spinning and weaving was done before 1733, and as the development had been gradual there was a nice balance about the business; and balance is an essential quality. We can explain what we mean by taking the seesaw as an example; an 8-stone boy 5 feet from the centre will balance a 5-stone boy 8 feet from the centre. If either moves a foot in, bang down goes the other. Life since 1733 has been unbalanced; first one




FIG. 56.—The Mechanical Part of Arkwright's Spinning Machine.

KAY'S SHUTTLE




FIG. 57.—Mechanical part of Crompton's "Mule."

thing and then another has happened, which has either banged you on the ground or left you shuddering up in the air wondering what was going to happen next.

Now one of the prime causes of all this was Kay's flying shuttle. Fig. 53 shows this, and it is the most innocent-looking contraption. All the weaver had to do was to hold the picking stick in his right hand and, with a quick jerk, throw the shuttle through the shed. The warp strings forming the bottom of the shed came through the reed on the top of the beam under it. The left hand was free to swing the batten, so it is easy to understand that the speed of weaving was increased. Each throw of the shuttle is called a pick; hence picking-stick. The shuttles sometimes had four wheels under. Fig 54 shows a later type.

Kay's flying shuttle was the beginning of industrial discontent, because it upset the balance of things. The next step came when James Hargreaves, a poor weaver of Blackburn, saw his wife's spinning wheel upset on the floor,

HARGREAVES

where it continued to spin. In this position its horizontal spindle would have been upright, and Hargreaves evidently thought: Why not drive the spindles upright, and why not drive more than one? This he did in his spinning Jenny, so named because that was his wife's name, and Fig. 49 shows a replica of the original machine in the Science Museum. As this looks far more complicated than it is in reality we have prepared a diagram in Fig. 55 which explains the principle. The various parts are noted by the same letters in Fig. 49.

In the original spinning wheel which Hargreaves' wife used she thinned out the roving to the required thinness to make the thread by pulling it off the distaff by hand. In Hargreaves' Jenny he did this with his travelling carriage D, and he must have watched this part of the work carefully. Spinning it after this was much the same on the jenny as on the wheel, except that the spindle was vertical instead of horizontal. Hargreaves was experimenting with his jenny between 1750 and 1757, and patented it in 1770. He earned no gratitude by his invention, because the spinners by this time had caught up with the flying shuttles and so could keep pace with the weavers.



FIG. 58.—Riding Dress (1774).

ARKWRIGHT



FIG 59.—Housekeeper (1777).
White muslin cap, large
ruffled frill.

ing round the mills to fit his customers with wigs he heard talk of the many attempts which were being made at the time to improve spinning and weaving methods; so he determined to try his hand at it, and produced his first spinning machine in 1769. This is now at the Science Museum London, and next to it there is the improved type made by Arkwright about 1775. We have shown the one of 1769 in Fig. 50, though it has lost some of its parts, because it has the great interest of being the original conception. Arkwright drove



FIG 60.
Country Woman (1777)
Muslin cap, wool cloak.

As the jenny could spin 120 threads at a time against the hand spinner's one, the spinners thought that large numbers of them would be rendered unemployed by the jenny, so they broke up Hargreaves' machines, and he had to fly for his life to Nottingham.

The next step was taken by Richard Arkwright, and he must be noted as another of the amateurs who did good work. Born in 1732, he became a barber, and go-



FIG 61
Parasol.

his machines, or frames, by water power; hence they are sometimes called water frames. The principle is explained in Fig. 56. It will be remembered that Hargreaves drew out his roving by attaching it to a travelling carriage. Arkwright did his drawing by passing the roving through pairs of rollers revolving at different speeds—the under roller was grooved

Cane stick
1½ yds long,
green silk,
brown fringe

steel, and the upper one wood covered with leather. The thread was then wound on to bobbins as shown in Fig. 56. Paul had experimented with rollers in 1738, but his machines had not been successful. Arkwright was a clever and business-like man, and built up a large fortune and became Sir Robert. One great advantage of his frame was that it spun a cotton thread sufficiently strong to be used for warp, which hitherto had had to be spun in flax.

Fig. 50 shows that

in appearance it was more like a gate-legged table than a machine.

Samuel Crompton of Bolton followed with the machine which he designed between 1774-9, and as it was a combination of Hargreaves' jenny and Arkwright's rollers it was called a mule. Fig. 48 shows a replica of the mule in the Science Museum, London. Fig. 57 explains the principle. Crompton did not do much good for himself with his mule, and seems to have been jockeyed out of receiving any benefit.

All these spinning inventions had enabled the spinners




FIG. 62.—Silk Sack Dress (1775-85).
(Victoria and Albert Museum, London)

CLOTHES



FIG. 63.—Dress of Striped Poplin with a Quilted Petticoat (1780-95).



FIG. 64.—Riding Dress with Velvet Skirt (1780-95).

(Victoria and Albert Museum, London)

to catch up the weavers, so times were ripe for new developments. These came with the invention of the power-loom by the Rev. Edmund Cartwright, D.D., in 1785. The weaving principle remained the same, as can be seen by the power loom of 1851 which is illustrated in Fig. 138. It was the application of power, first by means of a bull, and then, in 1789, by a steam-engine, which was revolutionary and affected not only weaving but the planning of towns and the general life of the people. We discuss this in the next chapter.



FIG. 65.—Dress of Spitalfields Silk with Pink Satin Quilted Petticoat, second half of eighteenth century

(Victoria and Albert Museum)

CALASH

As to the clothes which were made of the materials woven on the looms we have described, we gave the general development of dress in the eighteenth century in Vol. II, so that it seems to us in this Vol. III all we need do is to add some details.



FIG. 65A.—Skating in 1784.
(After Rowlandson.)



FIG. 66.—Dress about 1785.
(Victoria and Albert Museum, London.)

Readers of the Woodforde Diary may be glad to know that when Mrs. Howes appeared in her silk sack in 1778 she must have looked like Fig. 62, and Nancy might easily have worn the dress in Fig. 63. See also Fig. 65.

Fig. 67 shows an amusing form of head-covering called a calash, worn outdoors as a protection, and

MUSLIN



FIG. 67.—Calash (late Eighteenth Century).

(Victoria and Albert Museum, London.)

was of blue cloth, with gold buttons and a gold braid belt. The stock was blue. The black hat had cock's feathers and a gold band, and underneath it was worn a black curled wig, and the lady wore yellow boots. This can be truthfully described as "some outfit." The lady on the right is Grecian, and so that there can be no mistake her bonnet follows the lines of Athene's helmet. Underneath a flaxen wig was worn. The white muslin dress was embroidered with green and red, and pink shoes and gloves built up a pretty ensemble.

made of whale-bone and silk. Woodforde gave his sister and Nancy the black and white silk hat-bands worn at funerals to make calashes.

Fig. 69 shows a riding habit, which must have looked more like a livery than a dress. The habit



FIG. 68.—White Muslin Dress with Cherry Ribbon.

(Heidehoff Gallery of Fashions, 1764.)

BONNETS



FIG. 69.—Riding and Walking Dress.

(He. Iseloff Gallery of Fashions, 1799)

Fig. 70—which our publisher has kindly allowed us to have in colour—shows the interesting development which took place in the design of special dresses for wearing on the new-fashioned seaside holidays. The first lady on the left wears a white India calico overdress, with muslin under, and on her head a mob cap under, and then a straw bonnet over, with a green silk detachable eye-shade stiffened with wire. The same headdress is repeated on the second lady, and her dress is all in muslin, with a blue silk underbodice. The third lady has a Dunstable straw bonnet over a laced

MUSEUMS TO SEE

cap, a striped gingham gown, and a white Norwich shawl, probably made of wool. All the shoes were of gaily-coloured morocco. The unfortunate female infants are replicas of mamma, and any boy of to-day dressed as the one in Fig 70 would die of shame. As to the young women, doubtless the young men found them attractive. It is a little bit unfair; the young girl can wear almost anything and yet not lose her charm.

Here we should like to recommend our readers to pay a visit to the Dress Gallery at the Victoria and Albert Museum, South Kensington, London. Here is a wonderful procession of figures, all clothed in the real clothes of all the times, from James I down to the present day, and in cases at the sides are the little etceteras like lace, and shoes, and so on. The Gallery gives one a splendid idea of the development of dress. There are other good collections at the Bethnal Green and the London Museums.



Mistley Church, Essex. Designed by Robert Adam.
The church was demolished in 1870; the towers remain.
(For notes *v* p. 62.)



Fig. 70 - Dresses for the Seaside.

CHAPTER IV

THE SUBSIDIARY TRADES

TRANSPORT.—We saw in Vol. II what difficulties Celia Fiennes had to encounter when she went on her travels in England in the seventeenth century. How near Leicester she found “very deep bad roads. . . . I was near 11 hours going but 25 mile”—and that on horseback. Turnpikes had started at the close of the Stuart epoch, and progress was made in the eighteenth century; still there were many gaps. Because of the bad roads, which made wheeled traffic impossible, pack-horses were used, and carried 280 lb. of coal, for one example, in panniers on their backs.

Then it occurred to the Duke of Bridgewater to make a canal between his coal pits at Worsley and Manchester. There had been river traffic before, but not canals, so two Acts of Parliament were obtained in 1759-60, and Bridgewater set his engineer, James Brindley, to work. Here is a thing to note: the tide of invention stimulated men's minds to an extraordinary extent. They had no data to go on—no standards—no gauges—yet they went out into the blue and performed the most wonderful feats of construction.

An engineer to-day, on the strength of what these men did, knows the strength of all his materials, and their sizes and qualities. The early engineers may have been devoid of any sense of beauty and fitness, as many are to-day, alas! but they were plucky and inspired builders. Take the aqueduct over the Irwell, as Fig. 71, which enabled Brindley to dispense with many locks; it would be quite a feat to-day, and must have seemed a miracle when it was

CANALS

constructed in 1761. The later viaduct over the River Medlock and the Ashton Canal, as Fig. 73, is an involved and difficult piece of construction.

Brindley had been a millwright, and though we should call him illiterate he was a great genius. His method of working, when confronted with a difficult problem, was to go to bed for a few days and think it out. When he knew what he was going to do he got up and did it.

As a result of Bridgewater's canals coal fell from 7*d.* per cwt. in Manchester to 3½*d.* This success led to many more canals, which were used for the transport of all kinds of goods. Pottery, which used to get damaged on the backs of the pack-horses, travelled quite safely by canal. Inland navigation was the term used, so the men who made the canals were called navvies (see Fig. 71).

So much for the transport of goods. When people travelled, they used the roads, because there was nothing else to use. When Woodforde went to Weston to take up his residence there he rode on horseback, first from Somerset to Oxford, and then on to Norfolk, by way of Thame and Tring, where he struck Icknield Way, the oldest road in England, and followed this to Dunstable, Baldock, Royston and so on. For years afterwards he rides, hiring a chaise for his niece when she wanted to go calling.

When they went to Somerset together for their holiday, May, 1782, they went by the London coach, which started from Norwich at nine o'clock at night and reached London at two on the next afternoon. Two inside places cost £1 16*s.*, and one outside one for their manservant was 10*s.* 6*d.*, luggage being 8*s.* 6*d.* extra. By 1795 these fares had been increased to two insides £2 10*s.*, and one outside 16*s.* In 1774 Woodforde went from Oxford to Ansford in one day by post-chaises at a cost of £4 8*s.* for fares, meals, tips and turnpikes. In 1779 Woodforde and his nephew rode from Weston to Ansford, and the six days' journey cost £6 3*s.* 3½*d.* When Woodforde passed through London a day or so was spent in seeing the sights, including




FIG. 71.—The Canal Aqueduct over the Irwell at Barton, Lancashire.



FIG. 72 —A Passenger Barge to Uxbridge on the Grand Junction Canal at Paddington, 1801.



FIG. 73 —Railway Viaduct over the River Medlock and Ashton Canal, Lancashire.

TRAVELLING

the Lions of the Tower. He and Nancy stayed at the Bell Savage Inn, on Ludgate Hill, and Woodforde says it was a very good house, but as he was "terribly bit by bugs" we should hardly have agreed with him.

The next stage was by the Salisbury coach, in which two inside places cost £2 2s., one outside 10s. 6d., and luggage 16s. 6d. They left London at ten at night, and got to Salisbury between two and three next afternoon, and then continued their journey by chaises into Somerset. In 1786, when returning from Ansford, they see Mr. Pitt, the Prime Minister, held up at Hindon because all the posting horses were engaged. In 1786 they go there on holiday again and travel by the "Balloon" coach, so called because it was a fast one. Balloons were fashionable and had come over from France, where the first ascent was made by the Montgolfier brothers, paper makers of Annonay, in 1783. The motive power was hot air, generated by a fire in a brazier suspended by chains under an opening at the bottom of the balloon—which sounds fairly hazardous. Woodforde saw his first balloon at Norwich in 1784. Balloons satisfied the feeling which most of us have for something that is fast—that was hardly Nancy's motive, though, for wearing "a neat genteel and pretty Balloon hat."

"Balloon" coaches meant that the roads were being improved, and this was done by setting up toll-gates and making the users of the roads pay for their maintenance. We talk of a turnpike road and forget that the name arose through first setting up a frame which turned like a turnstile, only with spikes on it to prevent people passing until the toll was paid. For slower traffic and goods there were the waggons; Woodforde in 1793 speaks of meeting a large one with a tilt and drawn by eight horses, as Fig. 31.

BRIDGES.—Improving the old and making new roads turned the attention of the engineers to bridge building—and it is an inspiring subject. To throw a bridge across a chasm or overcome the obstacle of a swiftly-flowing river

BRIDGES

has always tuned up the bridge builders. We see in the "Iliad" how the Greeks thought of a river as something alive: "Nor shall the river avail you anything, fair-flowing with its silver eddies, though long time have you made him sacrifice of many bulls, and thrown down single-hooved horses, still living, into his eddies." The early bridge builders had to watch their rivers in case a sudden flood overwhelmed and whirled them away, still living. It gives us an added respect for the early engineers, who tackled their bridge problems so courageously. Take the Coalbrookdale Bridge, crossing the Severn near Brosely, in Shropshire, as Fig. 74. This was the first cast-iron bridge built, and the circular arch has a span of 100 feet rising 4 feet.

The roads were made by throwing down gravel and depending on the broad-wheeled waggons rolling it into the mud.

SMEETING.—All through the eighteenth century experiments were being made in smelting iron with coal and coke, instead of charcoal as had been the case. As the processes were perfected there was a great change over from counties like Sussex, which used to be a Black Country, to the northern industrial areas, where coal and iron were found together. This brought in its train great alterations in the lives of the people.

STEAM POWER.—But the most momentous change of all was the perfecting of the steam engine by James Watt. When he was a mathematical instrument maker in Glasgow he was asked, in 1763, to repair a model of Newcomen's engine, which gave him many ideas. In 1767 he was trying to make steam engines with Roebuck of Carron; but Roebuck went bankrupt in 1773, and it was not till 1776 that Watt found the ideal partner in Matthew Boulton of Birmingham, and the steam engine was turned into a success by 1781. One partner could write to the other in 1786 that people were "steam-mill mad." Remember that for thousands of years men had depended on simple

POWER




FIG. 74.—The Coalbrookdale Bridge, of Cast Iron, erected 1779.
(*Model in Science Museum, London*)

mechanical aids like the lever, and wind, water and their own muscles, and those of the horse and ox. In steam they saw endless applications and possibilities. At the end of the eighteenth century steam was used in sugar, flour and paper mills, and as we saw on p. 72 Cartwright started driving his power loom by a steam engine in 1789. In the textile trades water power had been used before, but it was steam that really started the modern factory system, and steam which destroyed the Old England and put Industrialism in its place.

To see how this came about we shall need to go back a little. In Vol. II we found out from Celia Fiennes' description of the serge trade in Exeter that the spinners brought their yarn to the market and sold it to the weavers, who in turn sold their cloth to the fullers. The good part of this system was that, though it did not turn out large quantities, the quality was good and the industry widespread. The workman could live outside the town in the country, and his family could assist him. They could if they felt so disposed take time off to grow their own vegetables, and keep pigs and poultry. In the same way

STEAM ENGINE

they helped to keep the farmer going, because his corn went to the mill and was ground into flour and baked by the village baker into bread. The countryside was not one-sided as it is now, with a solely agricultural population ; life was well-balanced.

The steam engine altered all this, because the operative had to go where the power was, so the factory came into being, and the people were steam-mill mad because they saw that there was money to be made. And a new class came into being—a hard and bitter race, without any culture or tradition behind them. The amenities meant nothing to them ; they even invented a saying : “Where there’s muck there’s money.” How were such a people to solve the tremendous problems with which they were confronted? The country village had a thousand years of tradition behind it as a guide ; the industrial town and factory had none. There had been workshops before, but no factories. When an architect designs a building, unconsciously he draws from his experience—the things he has seen and been taught. When the engineers started designing factories they had no such experience. The actual installation of the central steam engine was simple, but how to distribute the power by shafts, pulleys and belts was a problem. That all had to be invented. Then the lay-out of the looms and the working space necessary for them. The height of the workrooms and the lighting. Water supply probably worried them, and sewage disposal was an awful problem. Then the steam engine itself was inhuman ; it worked continuously, and to make it pay man had to follow its example, and was lucky if he escaped with less than once round the clock on six days of the week. So he had to come and live near the mill and leave his garden and his pigs and poultry behind him, so the countryside suffered as well. And there was no superfluity of houses, because the population was increasing. New houses had to be built, and nobody thought of Town Planning.

MEDICINE

A thousand years had gone to make a town before the Industrial Revolution ; during it towns had to be planned at once, and built quickly and cheaply. So back-to-back houses and alleys and slums came into being, and still remain with us. We describe industrial housing on p. 164.

It hardly seems possible that the factory operatives could have been happy. They probably made the best of a bad job ; but compared to the life which is depicted in the Woodforde Diary theirs seems cramped and colourless. The great charm of the Diary is that it gives you the life of the village as well as that of the vicarage. There was poverty at Weston, but much kindness. There is one delightful entry : " We had a very merry, laughing Day of it," and one feels, as one reads, that there were many such days, and that many participated in them.

One of the greatest of the difficulties of the change over to industrialism was that it came at a time when little was known of the precautions which were necessary to maintain the public health.

MEDICINE.—When we come to the gentle art of healing it does not seem to us an over-statement to say that the fifth-century Greek probably had a better chance of recovery under Hippocrates, who was born 460 B.C., than the people of the early eighteenth century.

The Woodforde Diary is extremely interesting from the point of view of health and medicine. The diarist notes his illnesses and the cures. We find that Dr. Clarke, his brother-in-law, was inoculating in 1764 against small-pox with the virus of the disease itself. Small-pox was the great scourge of the eighteenth century, and pock-marked faces must have been general. The doctors then discovered that, if persons had a slight attack of small-pox, afterwards they were immune, so this inoculation came about.

At the end of the eighteenth century they noticed that dairy farmers, who contracted cow-pox, seemed to be protected from small-pox, so Jenner in 1776 introduced vaccination with cow-pox, and this was found to give

VACCINATION

immunity if the vaccination were repeated at intervals. Jenner, in fact, appears to have been forestalled by a farmer named Jesty. On his tombstone in the churchyard at Worth Matravers, near Swanage, Dorset, is the following inscription: "(Sacred) To the Memory of Benj^m Jesty (of Downshay) who departed this Life April 16th 1816 aged 79 Years. He was born at Yetminster in this County, and was an upright honest Man: particularly noted for having been the first Person (known) that introduced the Cow Pox by Inoculation, and who from his great strength of mind made the Experiment from the (Cow) on his Wife and two Sons in the Year 1774." As the adjoining gravestone of his wife shows that she died in 1824, aged 84, we have proof that she survived her vaccination. The subject is controversial, but the fact remains that a pock-marked face is now uncommon, whereas up till the end of the nineteenth century it was still fairly common.

So far as surgery was concerned, generally this was in the hands of the Barber Surgeons, who were a City company—you could have your hair, corns or throat cut in the same establishment. By 1745 the surgeons had broken away from the barbers, but as the latter kept the funds the first surgeons' society was in great difficulties, until the Royal College of Surgeons was founded in 1800.

John Hunter was one of the first great men to free medicine from quackery and adopt a scientific treatment of disease.

If small-pox was the plague of the land, scurvy was the curse of the sea, but here attempts were made to combat it, and Captain Cook kept his sailors free from the complaint. Lemon juice was one of the preventives.

Fevers were rampant. The wretched prisoners in the gaols, kept there in dirty condition, infected their judges when brought into court (see p. 53). At the Black Assize at the Old Bailey, in London, in April, 1750, the Lord

FEVERS

Mayor, one of the Justices and forty to fifty others died of typhus fever contracted in this way.

In the Woodforde Diary we read that in 1781 fifty-three people died of fever in one week at Norwich.

The window tax, like all taxes, was bad. It was ingenious and seemed fair, yet it had a bad effect on the public health. It was really taxing by appearances. If you lived in a little Georgian house with a pleasant front door, and a window on each side, and three above, then you did not offer a very easy mark for the vulture tax gatherer; but if you had two or more on each side then the carcass became tempting, and the wretched tax-payer had to pay or brick up his windows. This we find that Woodforde did in 1784, when he had three windows bricked up. Though he saved part of his tax he shut out the sun and fresh air. He paid on the dairy and corn chamber windows as well as the house.

This brings us to another revolution. Until the middle of the nineteenth century the poor consumptive was kept in the warmest and stuffiest conditions, whereas the only chance of recovery for the lung was the fresh-air method which is now employed.

Here are some prescriptions culled from the Woodforde Diary. In 1790 he comes to the conclusion that "near a pint of Port Wine everyday" of the preceding winter was not good for him. It was held to be good to take one hour before breakfast $\frac{1}{2}$ pint of water in which had been steeped the second rind of alder stick. You could be bled 2 ounces, and your horses 2 quarts each. Friars Balsam and "Family Plaister" were used. Rhubarb was the great medicine, and a roasted onion put into your ear cured ear-ache. It was well to have a black tom-cat in your house, because its tail came in handy to rub your eye if you had a sty on the eyelid. A pond in the garden was necessary if there was ague in the house; the patient was given a dram of gin, pushed headlong into the pond, and then taken out and put to bed. If you had toothache, the farrier, being a

HYDROPHOBIA

handy man, came along and, if he were lucky, drew "the tooth at the first pull." Even the doctors were alarmed if your village was visited by a disorder called "Whirligousticon," as Weston was in 1783. Sea-bathing became fashionable at the end of the eighteenth century, and was one of the best things which ever happened, because the people's bodies were exposed to the sun and air and had a few baths. People went to Bristol Waters, which were held to be a cure for consumption.

In 1793 Woodforde notes that a mad dog ran through his village one day, and that one entry is sufficient to call up what was a constant terror till well towards the end of the nineteenth century. The friendly dog in hot weather was apt to go mad and run slavering at the jaws, biting all he met. Terrible tales were told of the awful death of those who contracted hydrophobia; how the patients howled and bit like dogs and were thrown into the most fearful convulsions. When there was an epidemic of hydrophobia all the dogs had to be muzzled, and very miserable they looked with wire or leather guards all over their faces, and then a cure was found by Pasteur. This great man, like many others, was led to his discovery in a roundabout way, and began by studying the culture of the vine. If on their death-beds men look back and think of their work, Pasteur could find comfort in the thought that he had saved as many lives as Napoleon sacrificed.

This leads us to the very important subject of our next chapter.

CHAPTER V

SANITATION

(Chapter dedicated to Venus Cloacina, the Goddess of Sewers.)

NOW here is a chapter which the delicately-minded can skip if they will, because it is concerned with Sanitation—but we hope they will not. Some of the boys and girls who read this book may become doctors, or engineers, or architects, or any one of the occupations which deal with the Public Health, and if they do they must deal with sanitation. It is as well one of the triumphs of the nineteenth century; a lost art was revived and people remembered that cleanliness, and all that it connotes, ranks next to Godliness. The subject has a long history behind it. We saw in our book on Homeric Greece that Sir Arthur Evans found a drainage system at Minoan Cnossos which was carried out in socketed and jointed drain-pipes, and disaster fell on Cnossos as early as 1450 B.C. Fifteenth-century B.C. Cnossos was ahead of eighteenth-century A.D. London so far as sanitation was concerned.

We do not know much of Greek methods of sanitation, but when we come to the Roman there are many evidences. The Romans not only had house drains, but sewers which carried the sewage away. The Cloaca Maxima in Rome can still be traced from the Forum of Nerva to its overflow into the Tiber. This probably started life as a stream, then it was covered with a vault of stone, and had a paved floor of lava added. The Romans even had a goddess of sewers, Venus Cloacina, who was regarded as the Purifier, and it is, when you think a little, a very beautiful idea. To wage war on dirt and disease, to clear away foulness, to make things clean, to purify—is a good work.

BATHS

The Romans brought water to their cities in noble aqueducts, which still remain, here and there, as triumphs of Civil Engineering.

When the Romans came to England in A.D. 43 they brought their ideas of cleanliness with them. We tried to illustrate these in our book on *Everyday Life in Roman Britain*. At Silchester, which was built in the first century A.D., the public baths there had latrines, where the sewage was carried away by water running through drains. The baths themselves were on a very grand scale for a small provincial town, and were arranged as Turkish baths are to-day, with a series of hot rooms which induce perspiration with a cold plunge to finish off with. Then there was the Great Bath at Bath, with five bathing pools and all kinds of other baths grouped around; there is nothing comparable to the Roman Bath at Bath in England to-day. Then disaster fell; Bath was sacked by the Saxons in 577, and its hot pools, lead-lined baths and elaborate system of pipes must have been as incomprehensible to them as a stranded Schneider Cup waterplane would be to-day to the pygmies of the African forests. So the springs choked up and the baths themselves disappeared into a morass. The words of Isaiah on the triumph of Israel over Babylon can be applied to the Roman baths: "I will also make it a possession for the bittern, and pools of water." In the museum at Bath is a teal's egg found when the Baths were excavated in the nineteenth century.

Incredible as it may sound, no real advance was made for 1400 years; from the early fifth century until the beginning of the nineteenth century people were not concerned with Public Health.

Our Anglo-Saxon ancestors did not like, or understand, city life. Tacitus knew the breed when he wrote: "They live apart, each by himself, as woodside, plain, or fresh spring attracts him." This does not mean single individuals, of course, but families which, with all the uncles and aunts and grandparents, would be like a small tribe,

SEWAGE DISPOSAL

and the spring was the first essential for the English settlements, as it is to-day—if you are building in the country away from Water Companies. Little can be known of sewage disposal until we come to Norman times, and then in all their castles we can find the closets which are called *garderobes*. These are generally planned with care, and decently tucked into a corner. They are usually approached from a window recess in the thickness of the wall, which acts as a disconnecting lobby, and the *garderobes* have a narrow slit themselves for ventilation. The actual fitting consists of a stone riser, over which a wooden seat was fixed, and the sewage fell down a vertical stone shaft, discharging into the open at the base of the wall, or in the later castles, into the moat. *Garderobes* are shown in the plans of castles in “Everyday Things in England,” Vol. I. Again the Norman never built his castle until he was sure of the water supply. The well was always in the keep, so that in case of siege the people were sure of water.

The monks in their monasteries seem to have been a little ahead of the citizens in their castles so far as sanitation was concerned. People did bathe in the Middle Ages, because there are frequent illustrations, in the illuminated manuscripts, of them having baths in wooden tubs. Water of course had to be brought in jugs and pails, and poured into the tubs. The Bath has its own order of Chivalry, instituted with us at the Coronation of Henry iv. in 1399. This received its name from the candidates for the honour being put into a bath, on the preceding evening, to denote a purification from evil deeds.

The first mention we have come across of a fitted bath is in Celia Fiennes’ Diary, of the time of William and Mary, to which we referred in Vol. II.

But baths like this would only have been for the very grand folks. We do not think there is any mention of a bath in the Woodforde Diary, or of bathing. Woodforde was a charming man—he may, or may not, have bathed.

WELLS

There was nothing very remarkable about this, because there were many country houses which were still without fitted baths right up to the end of the nineteenth century. A footman or maid brought in a big bath mat first, and then placed on it a large circular tin bath with a rim about 6 inches high, and two cans of water, one hot and the other cold, and in this you sat, or stood, and rinsed off the soap suds as best you could.

Thackeray, who should have known, writing "Pendennis" in the nineteenth century, said, "Gentlemen, there can be but little doubt that your ancestors were the Great Unwashed."

So far as sanitation is concerned the closet was outside in the garden, screened for privacy's sake, and Woodforde refers to it as "Jericho." This was a small outbuilding with a wooden seat, and a pit dug in the ground to receive the sewage. This pit necessarily had to be dug so that it projected at the back of the building for the purpose of cleaning it out. The danger was that surface water could get in, and then percolate through the soil, and so contaminate the water supply. Water was obtained by sinking a well, and this was the first thing done in building—to sink the well and find out if there were a good water supply. Local knowledge or diviners would be employed. We have several times employed diviners who have found water. Now assuming that in sinking the well the shaft passed through a thin vein of clay, it would be quite possible for sewage seeping through the soil from "Jericho" to be held up by this vein of clay, and then be conducted, if the levels were favourable, to the well. This was the cause of the terrible fevers—tainted water supply. Men, women and children still to-day, unfortunately, live in conditions of dirt and squalor and survive, but if they drink foul water they die, and that speedily and dreadfully. Inside the house, in cases of illness, close-stools, or commodes, were used.

These were the conditions in the country in the

CESSPOOLS

eighteenth century, and, in fact, in remote places they continue still. Granted that the water supply is good, and kept free from contamination, they are tolerable. When, however, as was the case in the eighteenth century, much the same state of affairs ruled in the town, it is easy to see how, when the Industrial Revolution brought many more people to the cities, the conditions soon became intolerable and a grave challenge to public health. We will see what happened in London in the eighteenth century.

In some of the older houses, such as those in Bedford Row, London, no provision was made on the upper floors for any water closet, and originally this office was at the end of the small yard or garden at the back of the house, and it consisted of a privy, or Jericho, which stood over a cesspool. When this needed cleaning out, in many cases the buckets had to be carried through the house. There were cesspools in Red Lion Square and Bedford Row, Holborn, up to 1854. This had to be so because there was no general system of sewers in London. One was constructed in the Strand in 1802, and this probably just ran into the Thames, or down Fleet Street into the Fleet. If you happened to be on the line of a sewer you could connect up to it—otherwise you had to depend on a cesspool. It was not till 1865 that London was provided with a system of main drainage or sewers(p. 106). Even then the difficulties were not over, because it was found as the result of turning the sewage into the streams that a nuisance of a new character was created, as serious as the one which the construction of sewers had relieved.

What house drains there were, were made of brick, in cylindrical form, or with vertical brick sides covered with a stone top as they were in the Middle Ages. Stoneware drain pipes, as used now, were first introduced in 1845, and made by Doultons in 1846. These were jointed with clay up till about 1880, when cement began to be used.

Now for the water supply of London. In Stow's

PUMPS



FIG. 75.—The Well Winch.

“Survey of London” (A.D. 1598) we find that the citizens at first depended on the Thames and its smaller tributaries, like the Fleet and the Walbrooke, and various wells. Water would not have been laid on to the houses, but was fetched by servants from the parish pump. Here and there these still remain, though not in use—there is one at the south end of Bedford Row, London. As the buildings increased these sources began to fail, and water was brought into the city by pipes of lead.

In the sixteenth century a Dutchman obtained a lease

WATER SUPPLY

from the City of the first arch of London Bridge, on the north side, and put in water wheels which worked pumps that forced the Thames water up to a reservoir, and from thence it was laid on to some of the houses in lead pipes. Pretty foul stuff it must have been, with the incoming tide bringing up garbage from the ships in the pool below the bridge, and the outgoing one sewage from the Fleet.

The New River Company, of which Sir Hugh Myddelton, a goldsmith and citizen of London, was the moving spirit, marked the beginning of the search by great cities for pure water supplies. Springs were discovered near Hertford, twenty miles away, high enough up for the water to run down to London by gravity, and in James I. reign the surveyors got to work, and by 1613 the water flowed into a reservoir at Islington.

Going through Red Lion Square, Holborn, about 1930, we saw some of the old wooden water supply pipes being dug up. These were made of elm trunks, bored out to about 6 inches diameter, and according to Mr. Austin, the Holborn Surveyor, were laid about 1620. Probably at first the water was conducted to pumps at intervals in the streets, and may afterwards have been laid on to storage cisterns in the basements of the houses with lead pipes, and then pumped up to other cisterns to give the head of water for the first water closets which we shall discuss presently. The elm water mains, though very thick, would not have stood a great deal of pressure, and there must have been leakage at the joints; again, until a proper ball valve was invented, which would shut the valve by its ball rising on the incoming water, the supply must have been regulated by taps; ball valves are mentioned 1748. The cast lead cisterns which were made in the eighteenth century are very fine, and Fig. 76 shows one. The cistern would not have been cast as a whole, of course, but each side separately, and then soldered together. Sand was spread on the casting table, and then the pattern indented into it from various stock





FIG. 76.—Cast Lead Rain-water Cistern.


pattern moulds and the lead poured on. All sheet lead was cast in this way, and the pipes were made by cutting up this cast sheet lead and soldering the joints together, as was done in Roman Bath. At the beginning of the nineteenth century lead was rolled out into sheets in rolling mills, hence it is now called milled lead, and about 1820 lead pipes without any seam began to be drawn under hydraulic pressure.

In the "London and Country Builders Vade Mecum" of 1748, Section IV., on Plumbers' Work, we find that "Its usual with the Plumbers to cast their Sheet-Lead of various Thicknesses, for Guttering, laying of Flats, covering of Roofs, etc., *viz.* from 7 to 12 lb. the Foot Square"; to-day we use 5 lb. 7 lb. lead was worth 1s. 1½*d.* per foot and 12 lb. 1s. 11*d.* in London. No mention is made in the book of any work in connection with closets. Rain water would have been collected from the roofs. This was made obligatory in London in 1724, for roofs to have gutters and down pipes. Many other private water companies were formed after the New River Company to deal with the growing needs of London, and remained



THE FIRST WATER CLOSET
DESIGNED BY
SIR JOHN
HARRINGTON IN
1596. WATER
SUPPLY AT 1
PLUG WASTE
AT 2.




AN 18TH CENTURY
FITTING ORIGINALLY
AT OSTERLEY HOUSE
WATER SUPPLY AT 1
OVERFLOW AT 2
WASTE PLUG 3
D TRAP AT 4
MARBLE PAN 5




CUMMINGS CLOSET
1775-WATER
SUPPLY 1
SLIDE VALVE 2
TRAP AT 3



BRAMHA'S
CLOSET 1778.
WATER SUPPLY 1.
TRAPPED OVERFLOW 2
FLAP VALVE 3 OPERATED
BY CRANKED ARM 4



PAN CLOSET
1790 PAN AT 1
OPERATED BY
CRANKED ARM AT 2



19 TH. CENTURY
WASH-OUT CLOSET.

FIG. 77.—The Evolution of the Water-Closet.

CLOSETS

until 1903, when they were all taken over by the Metropolitan Water Board.

The next detail to be considered is the actual water closet itself, and there is evidence that, though the simple privy in the backyard was quite common in London in the eighteenth century, inventors had been experimenting much earlier than this to improve matters. Sir John Harington is generally credited with being the designer of the first water closet. He did this for use at his home at Kelston, near Bath, and brought out a book about it in 1596. By the use of his closet he claimed that "unsavoury Places may be made sweet, noisome places made wholesome, filthy places made cleanly." A, Fig. 77, has been drawn from the details given in the book. Water was pumped up into a cistern, and then conducted to the pan of the closet and retained there by a valve or plug, which could be pulled up by a handle in the seat. When this was pulled up the sewage was discharged into a cesspool under, and there was no disconnecting trap between the closet or cesspool or any drain.

In Sir John's instructions he says the pan is to be "like the pot of a close-stool," and this is just what his closet was—a close-stool with water laid on, and a plug waste.

The next development came with the type of closet that Mr. S. Stevens Hellyer discovered at Osterley House, of which he wrote in one of his books (1882). He considered it then to be an eighteenth-century fitting. This is B, Fig. 77. It is a valve closet, in that water was kept in the pan by the plug, but it shows an improvement on Sir John Harington's closet, in that sewage was discharged into a lead soil pipe, and this may or may not have been trapped; it probably was, because of a reference made by Alexander Cumming, a watchmaker of Bond Street, London, who took out the first patent for a water closet in 1775. C, Fig. 77, shows this. In his specification Cumming claimed, as advantages for his closet, the shape

TRAPS

of the pan, the manner of admitting water, and that the stink trap was of an improved shape which totally emptied itself each time the closet was used. He then goes on to state that hitherto, though the stink trap had cut off the smell of the drains, it was offensive in itself because it became "a magazine of fœtid matter."

W.C.'s were beginning to be fitted inside houses, and are shown on plans of 1775, and very dangerous they proved to be. The apparatus was held to be so magical that all you had to do was put it in under the stairs, with or without a window, take an unventilated pipe to a cesspool, and live happy ever after. Instead, you very frequently died, because foul gases were conducted into the house.

The question of traps which cut off the stink had better be dealt with now. The vertical pipe below the trap in C, Fig. 77, was taken down to the ground level, and as often as not inside the house—there it was connected up to the drains which went to the cesspool. There was no fresh air inlet to the drains, or ventilator to the soil pipe as shown in Fig. 78; so traps were invented to cut off the smell. The first patent for a stink-trap seems to have been taken out by John Gaillait, a cook, in 1782, for "the invention of an entire new machine a stink-trap, . . . which will entirely prevent the very disagreeable smells from drains and sewers." At first these were made up by the plumber, out of sheet lead soldered together, in the form shown on B, Fig. 77; because of their shape they were called D traps. It is also quite obvious that they were not self-cleansing, and that Cumming's trap, as shown in C, Fig. 77, was a very much better type. The valve in Cumming's closet took the form of a slide.

The next development came when Joseph Bramah, a cabinet maker, took out a patent, in 1778, for another form of valve closet. This is shown in D, Fig. 77. The basin is the same shape as Cumming's—the difference was in the arrangement of the valve. This was hinged on its side and by a cranked arm was shut up against the bottom




FIG. 78.—The English Two-pipe System of Drainage.




FIG. 79.—The American One-pipe System.

VENTILATION

of the basin. Bramah's principle is still retained in such modern valve closets as the "Optimus." The difficulty about all valve closets is that they must be well made and so are expensive.

The pan closet dates from the end of the eighteenth century (1790) and, being simpler to make, was cheaper, but the container under, as shown in E, Fig. 77, was much too large to be cleansed by the flush, and so it was a very offensive type. Still it continued in use until 1881, because it was condemned by Mr. Hellyer in his lectures given in that year.

Wash-out closets were another bad nineteenth-century type, and are shown in F, Fig. 77—they failed because they were not self-cleansing. Still they led the way to the modern pedestal wash-down type as shown in Fig. 78.

Having said as much as is necessary about the fittings, we can turn to the drains. We will begin with the things which should be avoided first. It is useless to put good fittings on to bad drains. One of the authors remembers being called in, as late as 1913, to advise a doctor who was retiring and had bought a lovely old house in Kent without having the drains tested. There were good modern water closets which were visible—everything else was invisible. The oldest inhabitant assured us that the sewage was taken to a cesspool in the garden, but as there were no inspection chambers, or visible soil pipes, or any fresh air inlets, or means of ventilating the drains, this statement was not taken on trust. Exploration was put in hand, and the vertical soil pipe from the W.C.'s was discovered buried in the wall descending to the ground level. Here it was connected to stoneware drains which ran about on the surface of the ground under the wooden floors inside the house. Straight pipes had been used to get round curves, so that the flanged joints, of course, were well open on the outside of the curve. It was a terrible spectacle—yet people had lived in the house, on the top of sewage continually seeping into the soil under it.

PLUMBING

This, of course, was a survival of a state of affairs which had been general in the nineteenth century. It was in 1871 that King Edward VII., who was then Prince of Wales, caught typhoid fever when staying at a house in Yorkshire. This was traced to bad drainage; so even Princes were not immune from danger. The Prince's illness served, however, to focus public attention on the matter, and a group of men which included Edwin Chadwick, Professor W. H. Corfield, Rogers Field and S. Stevens Hellyer evolved the modern system of sanitation. Hellyer, being the head of a plumbing firm which had been established in London since 1706, was enabled to put the principles into practice, and he it was who gave a series of lectures at the Society of Arts in 1881, and published them in book form in 1882. Fig. 78 can be taken as illustrating the result of the work that these men did. The details to be noted are that though the drains are cut off by traps, there are not nearly so many stink-traps as there used to be, because the drains themselves are ventilated.

The scheme shown in Fig. 78 seems so simple that one's first impression is that it is so ordinary that it calls for no remark at all—yet it took a long time to come about. Mr. Norman Shaw, the well-known architect of the nineteenth century, fixed valve closets without any traps under the fitting, and took a branch drain into an open head on the top of the soil pipe. This was not carried up, so any unpleasant smell was free to escape from this head, and be carried by draught into any adjacent open window. The fresh air inlet was at the foot of the soil pipe, and this was trapped beyond just under the ground level. This was in 1878.

The end of the nineteenth century was a great time for English plumbers, and it can be said quite safely that for some time then they led the way and plumbed the whole world—but this success led to rigid bye-laws which have since blocked the way to progress. Fig. 78 will show that

AMERICAN SYSTEM

we still regard drainage as a foul thing which is going to stink, and this must be kept outside the house. There seems also behind it the idea the English are a dirty, careless race, who cannot be trusted to keep themselves clean and decent without fool-proof apparatus and constant inspection. This may be typical of the official mind, but it is a gross libel, for with little exception the reverse is the case. The exterior pipes get stopped and often cracked during even a moderate frost, and a long spell of our old severe weather would cause dislocation of drainage and possibly a nasty epidemic. The system involves the provision of very expensive drainage laid in the ground, with all the apparatus of inspection chambers and so on ; yet the soil pipes above the ground are of iron jointed in lead, and as they are tested by being plugged at the bottom, and filled with water, they are watertight and airtight. Outside the house they give the appearance of varicose veins, and are very unsightly. Connecting the ground floor W.C. directly to the manhole as shown in Fig. 78 is bad practice, because it is unventilated. The outside gullies, too, attract rats.

Fig. 79 shows the American one-pipe system, and the notes on the side explain how it was developed by the severe weather conditions. It is at once obvious that it is a cheaper and better system than the English two-pipe one.

Here only one set of pipes is shown—but if you bear in mind that in addition there are those which supply hot and cold water to the fittings—the heating pipes—those which carry wires for electric light and bells—others for refrigeration and so on, you will get some idea of what a complicated organism a modern building is, especially if, as is the case in the Empire State Building of New York, there are eighty-two storeys—that the building is about 1250 feet high, and houses round about 30,000 people.

That is perhaps all we need say about Sanitation, but it will be sufficient to show what an awful problem confronted the civic authorities during the Industrial



FIG. 79A.—Monmouth Street, Soho, an illustration by G. Cruikshank for Dickens' "Sketches by Boz."

CHOLERA

Revolution. Here are some notes on plumbers' wages taken from Mr. Bertram Hellyer's book. In 1837 plumbers worked nine hours a day for 6*l.* an hour, and six full days in the week, which made their wages 27*s.*—by 1844 they were getting 5*s.* a day—1854, 5*s.* 6*d.* a day—in 1855 they started leaving off work at four o'clock on Saturday instead of 5.30—from 1861-1873 6*s.* 4*d.* a day was paid and the Saturday half-holiday started at one o'clock.

There is one other point to be borne in mind, and that is the clearance of dust and garbage in modern cities. Our dustbins are emptied and that is all we know about it—but our ancestors were not so fortunate. Here is a quotation from a letter in the *London Times* of February 15th, 1832, only just over 100 years ago, "As the cholera is in London, I beg to call your attention to some parts of Westminster, which, above all other places, is the most probable to furnish fuel to the contagion. The Almonry, near Westminster-abbey, is inhabited by the very scum of society: it is unpaved, and the receptacle of all sorts of rubbish. This street has long been a disgrace to the City of Westminster, and the attention of the Board of Health ought to be directed to it, and also to Duck-lane, Pie-street, Cathead Lane, Gardener's Lane, and Stratton-ground, all of them filthy places, where refuse of vegetables rotting and corrupting lies in the streets, contaminating the air, and affording a repast to a herd of swine, which are continually to be seen in those disgusting dens." Perhaps we can get some slight idea of such conditons from the illustration (Fig. 79A), of one of the vanished rookeries in Soho. Notice the wizened brats sailing boats and making-believe to fish in the gutter, and the woman and baby emerging from their trap-door cellar. But the artist cannot reproduce the smells!

Defective and primitive conditions still largely obtain in some of the continental cities, and explain why, in a country like France, with a higher birth-rate, the death-rate is higher than in England, so that the population does



FIG. 80.—Death, the Avenger
The outbreak of cholera at a Masked ball in Paris in 1831.



John Richardson & Co.
Grocer


at the Corner and three Super-Sizes
against Hatton Garden Holborn

London.

*Wills, Tea, raw Coffee, Chocolate, Sausages, Sugar,
Marsh, in Vermouth, French, Home & Foreign Wines*

With all sorts of Groceries, Confectionary, &c.

Wholesale and Retail



Mary & Ann Hogarth
from the old French shop the corner of the
Long Walk hiring the Clerical co. Removed
to y Kewy Arms, joining to y Little Britain
gate near Long Walk, Wells y best wine & fresh
onable Ready Made, Frecks, suits of English,
French & Scotland, strict Family & School
Wagons, black & various French & blue coat & Regatta
Likewise, Indian, Stockings, it all kinds, n-hole
strict, French, white & striped, Flannels in y piece,
by Wholesale or Retail, at Reasonable Rate,

LONDON DRAINED

not show even the same slight rate of increase as in this island. Toulon is a charming old picturesque city to visit, but its little narrow side-streets are full of heaps of garbage, which at night are rummaged over by the starveling cats. You find much the same state of affairs if you pay a visit to Corsica.

Fig. 80 shows that Death was the Avenger, and death always stalks a little behind, and is only kept at bay by the work of men like those we have mentioned ; wherefore we say this chapter has been worth writing and reading.

An extraordinary thing is that we searched the metropolis for a memorial to the men who won the fight against dirt and disease, a greater battle than many of those which are commemorated by statues of generals. We may say that the whole town in its cleanliness is their best memorial. It almost seemed as if there was nothing at all, until at last we found on the Victoria Embankment a bronze roundel containing a bust, with flowing moustache and whiskers, of Sir Joseph Bazalgette, the Civil Engineer. He was the man to carry out the great scheme of the main drainage of London, by which the sewage of the whole vast metropolis is collected and finds its outlet in a great sewer into the Thames at Barking. But few of the myriad workers of London who go backwards and forwards by the trams along the Embankment realize what they owe to him who is commemorated in this modest fashion, or how frightful were the conditions before the drainage of London was thus carried away and rendered harmless. Mr. Batsford tells us that as a boy he saw a copy of the classic paper read by Bazalgette before the Institution of Civil Engineers on the main drainage of London, extracted from their Transactions.

The way the one great central drainage system of London came into being is a remarkable story and covers a good many years of the middle of the nineteenth Century. There were all sorts of Commissions and schemes, but nothing was done because all the suggestions got thrown

AN ENGINEER'S ACHIEVEMENT

out by Boards or Government Departments who had the right of veto. At last in 1855 the Metropolitan Board of Works was constituted and Bazalgette became Chief Engineer. Still controversies caused endless delay until Disraeli passed a short Act in 1858 which gave the Board full control. The fight had gone on for ten years, but now the designs could be put in hand and contracts let, and in 1865 the main drainage was opened by Edward, Prince of Wales, though the whole work was not finished for another ten years. It certainly is on a metropolitan scale. Even in those days more than eighty-three miles of large intersecting sewers were constructed; over 100 square miles, comprising a vast population, was drained, with a daily discharge of 120 million gallons; the total works cost £4,600,000. There was still one more Commission to be appointed (1882-1884), but that reported strongly in favour of the scheme, and praised the engineering genius which Bazalgette had put forth "in carrying it through all the intricate difficulties of its construction," with remarkable results in improving the general health of London's people.

It is appropriate that Bazalgette's monument should commemorate him on the Embankment, because at the same time as he was working on the draining scheme, he carried through the complicated construction of the Victoria Embankment and later the Albert and Chelsea Embankments, with Northumberland Avenue, at a total cost of £2,150,000.

Bazalgette also carried out alterations to many of the old bridges and designed new ones at Putney and Battersea, with the steam ferry at Woolwich.

He remained the Chief Engineer to the Metropolitan Board of Works until it was merged in the London County Council in 1889, and he presented in all thirty-three Annual Reports setting forth the engineering work on which he had been engaged.

PART II

CHAPTER VI

THE NINETEENTH-CENTURY FARMER

IN more ways than one, the perfecting of James Watt's steam engine in 1781 marked the close of one epoch and the beginning of another. In the same year, on October 19th, Cornwallis surrendered at Yorktown, and the American Colonies, almost against the wish of the colonists, were lost to us. The discontent had been simmering since the Stamp Act of 1765, and boiling point was reached at the Boston Tea Party of 1773—hostilities started at Lexington in 1775, and the Declaration of Independence followed (July 4th, 1776). The noble opening preamble of this: "We hold these truths to be self-evident:—That all men are created equal; that they are endowed by their Creator with certain unalienable rights; that among these are life, liberty, and the pursuit of happiness," is indicative of much. When Thomas Jefferson of Virginia drew this up he felt life, liberty and happiness were endangered. Thirteen years later the citizens of a much older civilization felt the same, and it was overthrown to the cry of Liberty, Equality and Fraternity, and from the French Revolution Buonaparte was to arise and threaten Europe. The pursuit of happiness became terribly difficult.

We were to go to war with France, and this was to last till 1815 and include another war with America, in 1812. Political history is not in our line of country at all, but it must, at this period, be borne in mind. George III. and his advisers, and the Regent, had a fearful task pre-

CHART II.

Kings, Political, and Social	Science and Industry	Art
GEORGE III. (contd.)		
1801 Victory at Copenhagen	1800 Royal Coll. of Surgeons founded 1801 "Charlotte Dundas," steamboat Trevithick's steam carriage	1800-12 Elgin Marbles come to London
1802 Peace of Amiens	1802 Sewer constructed in the Strand Bodley Range	1802 Pitzhanger House, Ealing (Soane)
1803 War against Buonaparte		1803 Sheraton's Cabinet Dictionary
1804	1804 Jacquard's apparatus Trevithick's first railway loco	
1805 Battle of Trafalgar		1805-15 Scott's Romantic Poems 1806-13 Ashridge, Herts (Wyatt) 1807 Downing Coll., Cambs. (Wilkins)
1807 Abolition of slave trade Population of England and Wales 11,000,000		
1808	1808 Trevithick's "Catch-me-who- can"	1808 Ackermann's "Microcosm"
1810 Cobbett imprisoned 1811 Prince of Wales becomes Regent		1809 Tavistock Square (London)
1812 The Luddites		1811 Dulwich Picture Gallery (Soane)
1812 War with America	1812 Birth of A. W. N. Pugin George Stephenson at Killing- worth	1811-14 C. R. Cockerell in Greece Regent St., London (Nash)
1814		1814 Scott's Waverley Novels begun
1815 Battle of Waterloo	1815 Steamers on the Thames	1815-23 Shelley, Keats and Byron writing
1816 Corn Law		1816 British Museum buy Elgin Marbles
	Hobby horse introduced	1817 Waterloo Bridge, London (Rennie) Customs House, London
1818		1819 St. Pancras Ch., London (Inwood)
1819 Peterloo massacre		Menai Bridge (Telford)
1820 GEORGE IV		1820 Brighton Pavilion completed (Nash)
1821 Cobbett begins his Rides	1822 George Stephenson goes to Stockton and Darlington Rly.	
1823 Cornfields at Earl's Court, London		1823 British Museum, London (Smurke)
1825		1825 London Bridge
1826	Patrick Bell's reaper	
1827		1827 Carlton House Terrace, London University Coll., London (Wilkins) (cast-iron girders used)
1828 Arnold at Rugby, 1828-		
1829 "Peelers" make first patrol	1829 Shillibeer's bus Rainhill trials won by "Rocket"	
1830 WILLIAM IV		
1831	Faraday discovers electro-mag- netic induction	
1832 Reform Bill		
1833 Oxford Movement Abolition of Colonial slavery	1833 Death of Trevithick Cholera in London Enterprising Steam Coach	1833 National Gallery, London (Wilkins)
1834 National education be- gun	1834 Hansom designs his cab McCormick's reaper	1834 Fishmongers' Hall, London (Roberts)
1835		
1836	Birth of Mrs. Beeton (her book 1859-63) P. & O founded	1836 "The Pickwick Papers" (Dickens)
1837 VICTORIA		1837 Carlyle's "History of French Revolution"
	1838 Lord Brougham's brougham	1838 Britten and Pugin's "Public Build- ings"
1839	1839 First bicycle	1839 Harvey Lonsdale Elmes wins com- petition for St. George's Hall, Liverpool
		Taylor and Randolph Buildings, Oxford (C. R. Cockerell)
1840		1840 Houses of Parliament, Westminster
1841		
	1842 Royal Commission of Mines found that women pulled the coal trucks on hands and feet, and children of five worked alone in the darkness	
1843		
1845	1845 Stoneware drainpipes introduced Howe invents lock-stitch machine	
		1846 Thackeray begins "Vanity Fair"
1847		1846-47 Cockerell finishes Baser's Fitz- william Museum, Cambridge
		1847 Elmes dies and Cockerell finishes St. George's Hall, Liverpool 1848 The end of traditional architecture
1849		Macaulay's "History of England"
1851	Great Exhibition, London	"Jane Eyre" (Charlotte Bronte)
	1864 London sewerage system	

Chart I.—George II and III, 1727-1799, p.xiv.

FARMING

sented to them at a time when the whole social and economic structure was being rebuilt.

NINETEENTH-CENTURY FARMING.—The closing years of the eighteenth, and the beginning of the nineteenth century, found farming in a difficult and unreal position. The War was on, and prices had risen to famine heights. The Woodforde Diary is very interesting in this respect. Wheat sent in to Norwich from Weston sold for anything between 47*s.* and 54*s.* a quarter between 1784 and 1794. In 1795 and '96 it was 84*s.* and 105*s.* In 1797 44*s.* In 1800 and 1801 114*s.* to 160*s.* This was thoroughly bad, because the money which the farmers were making came out of the pockets of the community, and the poor suffered. 1795 was a very cold winter, and £46 15*s.* was collected in Weston for the poor people, and there was mobbing at Norwich because of the dearness of provisions. Woodforde and Nancy on their way back from their holiday stayed in London to see the opening of Parliament, and got mixed up with a violent mob which broke the windows of the King's Coach, and insulted him, and cried out, "Give us Peace and Bread!" There were riots again in London in 1796. It was this year that Woodforde went to a dinner party where the bread served had been made of all brown wheat meal, with one part in four of barley flour added. Woodforde said of this it "eat very well indeed, may we never eat worse." In this year he instances the following food prices as very high indeed. Beef 6½*d.* per lb., Mutton 6*d.*, Lamb 6*d.*, Veal 5*d.*, Honey 6*d.* lb. In 1799 bread was being distributed to the poor in Weston, and in 1801 the Diary complains of high prices and no sign of Peace; a 6*d.* loaf sold for 17*d.*, and the poor stole turnips to stay their hunger; there were mobs and risings, and wages were not increased. Woodforde still paid Ben Leggatt £10, Bretingham Scurl £8, Betty Dade £5 5*s.*, Sally Gunton £5 5*s.*, and the skip-jack £2 2*s.* per annum.

This led to one of the most disastrous steps ever taken in English history. In May, 1795, the magistrates met at

DOLES



FIG. 81.—Milkman with Yoke.

Speenhamland, Newbury, Berks, and there they agreed to raise the labourer's wages to 3*s.* a week for himself, and 1*s.* 6*d.* a week for the other members of his family, when the loaf cost a shilling, by payments from the parish rates—if the loaf increased so did the dole. This gradually spread through most of the counties, and pauperized the labourers. The enclosures had cut them off the land. Pitt's Combination Acts of 1799 prevented any combinations of workmen who might

wish to meet to discuss their grievances. Poaching was a dangerous form of pot-hunting, because you could be transported if found carrying a net, and man-traps and spring guns were used until 1827.

Probably Nelson's victory at Copenhagen on April 2nd, 1801, when he turned his blind eye to Hyde Parker's signal to leave off action, saved England in more ways than one. It put an end to the armed neutrality, and opened the Baltic to trade, and enabled us to import corn. The Peace of Amiens led to a short cessation of the War. Corn at Norwich fell to 76*s.* a quarter.

The main reason for all this trouble in England was fear. The authorities had before them the spectacle of the French Revolution leading to the execution of Louis XVI. in 1793.

CORN LAW

They feared revolution at home—they feared invasion by the French. They had to carry on a war while the whole economic structure of the country was being changed. There was no time for kindly inquiry, and repression took its place, with the result that we had labour troubles during the nineteenth century which could have been avoided if the workers had felt that they had been given a fair deal.

War was declared against Buonaparte in 1803 and continued until the bogey was finally laid at Waterloo in 1815. Now here is a point to be remembered. We are apt to think that no other war made such demands on the manhood of the nation as the War of 1914-1918. Sir John Fortescue, the very distinguished military historian, in *The Times* of July 30th, 1932, wrote: "I am not so sure of that. Between 1804 and 1814 the proportion of men under arms, afloat and ashore, to the total population of Great Britain, was exactly the same as in the last war, one in fourteen." In 1914 the industrial machine was at its highest state of efficiency—in 1804 Industrialism was producing muddle and confusion.

After Waterloo the Corn Law of 1815 prevented importation of corn until the price was 80s. a quarter. This was passed by members who represented the agricultural interests—it went against those of the industrial towns who wanted cheap food, but places like Manchester and Birmingham were unrepresented.

Bearing these details in mind we can turn to Cobbett, because, if Tull is the first name which comes to one's mind when writing of farming in the eighteenth century, then William Cobbett's does the same thing when the early nineteenth century is being dealt with.

Cobbett commenced his *Rides* on October 30th, 1821, when he was fifty-nine years old. His object was to talk to all the people he could meet and try and find a solution of their troubles. He was born at Farnham, in Surrey, on March 9th, 1762, and his father was a small farmer. Cobbett's boyhood was passed in scaring birds from

COBBETT



FIG. 82.—The Bailiff.

growing crops, until, in the end, he was promoted to driving a team and ploughing. His father, who was a man of parts, taught his sons the three R's of Reading, Writing and Arithmetic in the winter evenings, and this carried William through.

When he was eleven he went off with $6\frac{1}{2}d.$ in his pocket to see the Royal Gardens of Kew, where he obtained work, and then later returned to Farnham. At Kew he read the "Tale of a Tub." In 1782 he went to Portsdown Hill to visit a relative, and saw the sea for the first time. Here he tried to become a sailor, but was dissuaded. In 1783 he found his way to London, and took a job as a clerk in a lawyer's office in Gray's Inn for some nine months. Then he went to Chatham, and enlisted in the 54th Foot Regi-

ment—for some twelve months he stayed there learning his drill. Here it was that, finding his grammar shaky, he bought a Louth's Grammar, and memorized the whole book, repeating it to himself when on duty as a sentry.

Cobbett did his duty well, and became a good soldier, and finished as sergeant-major. The regiment was sent to Nova Scotia, and Cobbett remained there until 1791, when he obtained his discharge and returned to England. In 1792 he was in France, but in October of that year back in America, this time in Philadelphia, where he taught English to French refugees. By 1795 Cobbett was writing pamphlets, and brought out a monthly political paper called *Peter Porcupine*. This was aptly named, and an

POLITICAL REGISTER

action for libel compelled Cobbett to return to England in 1800. Cobbett, of course, could not keep out of a row. Feelings at the time were very high between the Federalists and Republicans, and the rule of the former came to an end with the election of Jefferson to the Presidency. When Cobbett got home he was at first kindly received by the supporters of the Government, and this is interesting, because afterwards he was to be persecuted and prosecuted and imprisoned, and was thought of as a dangerous scribbler who wished to overthrow established government. This was entirely wrong; Cobbett loved his country with a great and abiding love, but it was the country rather than the town.

He would have agreed with Socrates' quotation in Xenophon's *Economicus* that "agriculture to be the mother and nurse of other arts; for when agriculture flourishes, all other pursuits are in full vigour; but when the ground is forced to lie barren, other occupations are almost stopped."

By 1802 Cobbett was publishing his *Political Register* (which lasted till his death in 1835). In a year or so he was able to take a house in Botley in Hampshire, and here he grew many trees. He was always extolling the virtues of the Locust, or Acacia tree, which he imported from America. He carried on his farming on the Tullian principles of planting by drills in rows.

Then in 1809 a mutiny broke out among the local militia at Ely, and was suppressed by German cavalry, and the ringleaders sentenced to 500 lashes each. In the *Political Register*, Cobbett remarked on the brutality of the punishment, and described what such a flogging meant. Again he was prosecuted for libel, and sentenced in 1810 to two years' imprisonment, and a fine of £1000. In Cobbett's own words, he "was put into a place among felons (Newgate), from which I had to rescue myself, at the price of twelve guineas a week"—the gaolers were entitled to make a profit in this way. His enemies thought

PAPER AGAINST GOLD



FIG. 83.—A Leather-Legged Chap.

that they had ruined him, but the *Register* was written in prison, and published regularly, and a book as well on "Paper against Gold."

Cobbett was prosecuted once more for libel in 1831, but was acquitted.

After the War was over the situation was further complicated by the returning soldiers, by unemployment, and intolerable taxation. The people felt Reform was needed, but had no real voice where rotten boroughs and villages returned members to Parliament. Statesmen were not honest—peculation was rampant—even the parsons were pluralists who collected livings, and the tithes, and farmed them out to curates without influence. Into this

nightmare world of 1812 came Cobbett, fresh from, and refreshed by gaol, more of a porcupine than ever, and determined to smash what he called the THING; he spoke of it as if it were unclean, and hated all the people who had lent money to the Government to prosecute the War, because they had lent the money when wheat was three times the price that it came to be after, so they were called Fund Lords—stockjobbers he detested because they gambled in War Loan—he described them as "huckstering reptiles who had amassed money by watching the turn of the market"—and bankers because they manipulated currency. Here is what he said of an M.P. who absented himself from Westminster, "He must turn-to or turn-out: he is a sore to Westminster; a set-fast on its back; a

GAGGING BILLS

cholic in its belly ; a cramp in its limbs ; a gag in its mouth : he is a nuisance ; a monstrous nuisance, in Westminster, and he must be abated," and he had never a good word for the parsons, but he loved the village labourer, and pointed out how hard his lot was, and that he was paid so little in wages, that he was worse off for food than the felon in gaol—and he hated London, which he called the Wen, because it drew all the goodness out of the country.

Cobbett loved the old "resident native gentry, attached to the soil, known to every farmer and labourer from their childhood, frequently mixing with them in those pursuits where all artificial distinctions are lost, practising hospitality without ceremony from habit and not in calculation"—he loved these people because they knew their job, but foresaw that they would disappear under the load of taxation, and their place be taken by profiteers. It was for these latter that he reserved the lash of his tongue.

Here was a pretty kettle of fish. Cobbett was no mere vulgar agitator to be bought off by some little preferment—he was entirely honest, and a lover of England, and all he wanted was to make it a better place to live in by Parliamentary Reform. He might have been all this, and yet not have achieved so much, but for the fact that the gods, knowing that he was to have a hardish life, dropped a little magic into his cup and gave him the power to move men ; he was a poet as well as a political propagandist. So his enemies are forgotten and his name lives.

By 1817 Cobbett had to go to America once more—publish his *Register* there, and send it to England. In this way he defeated the Government who were trying to stifle the demand for Reform by the Gagging Bills. Cobbett was a great warrior in the fight that was waged then for the Freedom of the Press.

Cobbett returned in 1819, and by 1821 had started his Rural Rides. He entered Parliament in 1832, in the days of the Reform Bill.

Now for some details of everyday life culled from

LABOURERS



FIG. 84.—Sowing Broadcast.

Cobbett's pages. On November 20th, 1821, he goes in pilgrimage to the farm of Tull at Shalbourne, Berks (see p. 10). He goes again later, and many times he acknowledges his debt to Tull's teaching.

He suggests that the labourers in the woodlands and clays of the Weald, did better for themselves than in the rich cornlands. He describes them as "leather - legged chaps"—their dress was as follows: "Under the sole of the shoe is iron:

from the sole six inches upwards is a high-low; then comes a leather bam to the knee; then comes a pair of leather breeches; then comes a stout doublet; over this comes a smock-frock; and the wearer sets brush, and stubs, and thorns, and mire, at defiance." What Cobbett meant, of course, was that woodlands provide pleasant and profitable work for the winter in cutting hop-poles, faggots, and the like, and as well the labourer was sure of firing for himself.

Commons and wastes gave the opportunity for raising geese. Cobbett wrote, "I have seen not less than 10,000 geese in one tract of common, in about 6 miles, going from Chobham towards Farnham in Surrey." This sensible

WOODLANDS

habit of keeping geese on the commons lasted until the last few years in our part of the country, and was a very economical method of raising food. The geese were turned out in the morning to find their own living, and the attendant gander protected them during the day and brought them back at night.

Now we can give the other side of Cobbett. In reading "Rural Rides" his denunciations of stock-jobbers do become a little tiresome, though from his point of view these were good journalism. It was necessary for him to keep on saying the same thing until he established his point, but the jolly part of his books is that you never know when he may forget his enemies and write of the country he loved.

Here is a beautiful description of woodlands :

"Woodland countries are interesting on many accounts. Not so much on account of their masses of green leaves, as on account of the variety of sights, and sounds, and incidents, that they afford. Even in winter, the coppices are beautiful to the eye, while they comfort the mind, with the idea of shelter and warmth. In spring, they change their hue from day to day, during two whole months, which is about the time from the first appearance of the delicate leaves of the birch, to the full expansion of those of the ash ; and, even before the leaves come at all to intercept the view, what, in the vegetable creation, is so delightful to behold, as the bed of a coppice bespangled with primroses and blue-bells ? The opening of the birch leaves, is the signal for the pheasant to begin to crow, for the blackbird to whistle, and the thrush to sing ; and, just when the oak-buds begin to look reddish, and not a day before, the whole tribe of finches burst forth in songs from every bough, while the lark, imitating them all, carries the joyous sounds to the sky. These are amongst the means which Providence has benignantly appointed to sweeten the toils by which food and raiment are produced ; these the English Ploughman could once hear, without the sorrowful reflection that

TAXATION




FIG. 85.—Old Plough at Hemsby, Norfolk.

he himself was a *pauper*, and that the bounties of nature had, for him, been scattered in vain ! ”

Then Cobbett gets on to his cob again, and begins to lay around him with prodigious thwack, thwacks, at taxation, and accursed paper money—but one can put up with this if, in between, are pieces of prose as pure as the one we have quoted.

And there are many others. Cobbett had an extraordinarily keen eye for a bit of country, when he goes north he notices the difference between north and south. He had a way of judging a district by the number of churches. Where in the south, in a fertile valley, he comes on a church every two miles or so, then he thinks the land was good, and must have supported a large population in the Middle Ages when the churches were built. In the north, from Morpeth to Alnwick, he remarks that the land is poor, scarcely any trees, “the farms enormously extensive ; only two churches, I think, in the whole twenty miles.” Cobbett made the following comparison ; Northumberland, with an area of 1871 square miles, had 88 parishes, while Suffolk, with 1512 square miles, had 510, and how rules for one part of the country could not be applied to another.

WHEAT

Then he is distressed not to find many birds in Lincolnshire. He says, "We heard a little twittering from one thrush ; but, at that very moment, if we had been as near to just such a wood in Surrey, or Hampshire, or Sussex, or Kent, we should have heard ten thousand birds singing altogether, and the thrushes continuing their song till twenty minutes after sunset."

Cobbett tells an amusing lark tale, which we have never seen enacted ourselves. He watched a gentleman lark circling upwards and singing gloriously—then from close by, straight up to him, went the lady lark and obviously gave him a lecture, because the poor songster stopped and flew down to earth. Cobbett suggests that the lady said to her husband, "Yes, my boy, we all know that you have got a very nice voice, but singing won't feed the family"—but then larks sing long before any family comes.

Though Cobbett loved old churches, and the delights of the countryside, his main concern was agriculture, and the condition of the labourers. For example, in his ride to Huntingdon, in 1822, he notes that he did not see any wheat drilled, but that they still persisted in sowing broadcast (Fig. 84), and that so badly that some parts of the field looked as if the seed had been "flung along them with a shovel, while other parts contained only here and there a blade."

At Burghclere, Hants, Cobbett saw a crop of wheat planted in the Tullian manner, in rows, on ridges, at wide intervals, and ploughed, or hoed, in between all the summer. The crop equalled 28 bushels to the acre. Another wheat crop was dibbled in between rows of turnips, in November, four rows on a ridge, with 18 inches between each two rows, and a 5-foot interval between the outside rows. So in Cobbett's time wheat was still sewn broadcast, dibbled, and drilled. Again in the Cotswolds he found ploughing done by oxen. Fig. 100, from J. F. Herring's picture, "Seed-time," dated 1854, shows the land being ploughed

FAIRS

with a swing plough—then rolled, and a man behind sowing broadcast.

There is an interesting note on the journey to the north of England in 1832. When Cobbett was at Hexham he remarked that “there appears to be no such thing as barns, but merely a place to take in a stack at a time, and thrash it out by a machine.” Unfortunately Cobbett does not describe the machine, but we shall be doing so a little later.

In the Woodforde Diary we can watch the prices rising during the War. In Cobbett, after it, we hear of disastrous falls. At Chertsey, Surrey, in 1822, prices were less than a third of those of 1813—cows fetched £3 as against £15. Again in 1826 Cobbett went to the great fairs at Weyhill and Appleshaw, where horses, cheese, hops, corn, and 200,000 sheep were offered for sale. Ewes sold there in 1812 for 55s. to 72s., but in 1826 for only 25s. Cobbett remarks, more than once, on the great use of these markets to the small local craftsman in the old days, who, having made things, could offer them in the market directly to the purchaser.

Cobbett gives details of the labourers' wages—how in 1822 they were reduced to 6s. a week, and he met a farmer who said they must all be ruined unless they could have another “good war.” Cobbett points out that Arthur Young, in 1771, allowed for a labourer, his wife, and three children, a sum which would have been equal to 13s. 1d. in 1826, instead of which he only got 8s.

There were perambulating labourers. The mowers, who were English, moved ahead of the Irish haymakers. One of their grievances was that they had to pay 5d. a quart for their beer.

Cobbett seems to have worked hard to help matters, and brought out his book on Cottage Economy—this, he claims, introduced the art of straw-plaiting into England. Certainly, until a few years ago, the cottagers in our part of the country used to plait straw, and sell it to the Luton

CRAFTS

hat manufacturers. Cobbett notes in 1826 that gloves were manufactured at Worcester which "cannot be carried on by fire or by wind or by water, and which is, therefore, carried on by the hands of human beings." The work was done by the people in their cottages and helped them very much.

Cobbett was pleasantly surprised to see a woman, near Westborough Green, in Sussex, "bleaching her home-spun and home-woven linen." He realized that if the countryside is to be healthy, farming must have its attendant trades, because they help to build up a healthy corporate life. To grow foodstuffs only, and import all your implements from factories in the towns, means a lop-sided life in both country and town.

On the other hand, at Witney, the blankets used to be made of yarn spun in the Cotswold villages, but Cobbett found that factories had been started and five of these did what thirty smaller people had done before.

Again, when Cobbett was a youth there was a cottage industry of carding and spinning wool in the Avon Valley, but this had gone when he went there on his rides. The factories in his time were not all worked by steam—he tells of woollen cloth mills all down the valley at Avening, Glos—some worked by steam, but others by water.

Still, people were trying to improve the condition of the labourer. Cobbett found allotments at Tutbury, Glos, let by a farmer to his labourers at £1 per annum per rood or $\frac{1}{4}$ acre, and he thought this was a fair rent, and that it would help the labourers, as we know it has. It was really a revival of the Common Fields, and gave men the chance to dig in the earth.

All the old crafts did not die at once. The village smith was a good tradesman, and in between shoeing horses helped the farmers to mend the machinery which they had began to use, when it broke down. The country builder drove a good trade, as he still does to-day, but he had to be a good all-round tradesman, and be prepared to build you

SENSIBLE FELLOWS

a house, or make you a coffin if necessary. The village wheelwright was a great artist, there is no other word, because he built the waggons. If any of our readers want to know the mysteries of this craft they have only to read "The Wheelwright Shop" by Sturt. In Fig. 95 we have illustrated various types of waggons (spelled with two g's, please) and we shall deal with this later.

It was in 1822 that Cobbett thundered against the New Turnpike Act, which sought to fit very wide wheels to the waggons, so that the tyres could be used to roll down the surface of the roads. It was an ingenious idea of the townsmen, but quite hopeless, because the moment the waggon went off the hard road on to the farm track it was foundered. The Act as well made chalk and lime subject to turnpike duty, and this hit the farmers of clay lands who needed lime to dress it.

One effect of the hard times was that emigration was stimulated. Cobbett remarks, in 1830, that it was "not the aged, the halt, the ailing," that were going, but the "sensible fellows" with a little money, "carpenters, wheelwrights, millwrights, smiths and bricklayers." Four hundred went from Norfolk when he was there, and they were, of course, worth their weight in gold to America. From Sheffield and district we sent knives, forks, scythes and sickles to America, but our export trade was beginning to be hampered by the tariff, passed by the U.S.A. in 1816, charging a duty on imports.

In the last paragraph is all the history of agriculture in the nineteenth century. The "sensible fellows" emigrated, and our export trade improved. The country was sacrificed to the town—the Wen had to be fed. The sickles which were exported were paid for by food for the operatives, and agriculture was left to itself, unless there happened to be a war on. To-day the countryside is in forlorn ruin, and weeds grow where once corn rustled in the wind; there are derelict farms with grass growing in their yards; we import food, yet pay men and keep

TRUCK SYSTEM

them in unemployment. The grown-ups tolerate a madder world than any a boy or girl could imagine.

Cobbett remarks on the truck or tommy system in 1830. This prevailed in the iron country of which Wolverhampton was a central point. He thought the term arose from the army, where the bread was called tommy. What the system amounted to was that the employers paid their men in commodities instead of money, and as they calculated the wages in terms of the retail prices of the goods, and bought them wholesale, they got the shop-keeper's profit for themselves. The truck system was prohibited by the Truck Act of 1831.

Cobbett found that when he went to the north in 1832 the Durham miners lived well. Their wages were 24s. a week, with house, fuel and doctoring free. As Cobbett said, "Theirs is not a life of ease to be sure, but it is not a life of hunger." They were very much better off than the unfortunate agricultural labourer.

Unfortunately Cobbett was not interested in mechanical matters. In 1830 he found that boats went up the Humber and the Ouse, to within a few miles of Leeds. He went back to Barton "by the steamboat," that is all—we should have liked a page of description. Again at North Shields, in 1832, where he found that the working people seemed to be very well off, their dwellings solid and clean, and their furniture good, he notes as well that "they have begun to make a rail-way from Carlisle to Newcastle; and I saw them at work at it as I came along"—and no more than that of the "rail-way."

That is all we need say of Cobbett, but we strongly recommend our readers to read his "Rural Rides"—it gives one side of the picture which cannot be neglected. As well there is the man and his life. The early days at Farnham; the father teaching his boys in the evenings; the son's travels, and adventures, and his great courage. Turn back to our description of Newgate, and think of two years there with felons, and

MACHINERY

remember that Cobbett came out unbroken. It is a splendid record.

Having gained some impressions of the life of the countryside in the early nineteenth century from Cobbett, we can now turn to the practice of agriculture, and give some details of the implements and machinery with which it was carried on. In the two words, implements and machinery, you have nearly the whole story. At the beginning of the century nearly all the implements were home-made, by local workmen, but as time went on these were replaced by machinery made in factories in the towns, and imported into the countryside, so that life there became duller as it became less varied.

If we start with the oldest of all the implements, the plough, this at an early date attracted the attention of the industrialists. Woodforde notes in his Diary, how, in 1786, he went over Mr. Ransom's new iron foundry at Norwich, and that it was "very curious indeed." Ransom introduced the chilled plough share, and by about 1825 the complete iron plough had made its appearance.

Still the townspeople did not have it all their own way, and the wooden plough held its own on heavy land; Fig. 11 was still in use when we drew it in 1919. This was more than could be said of the delightful plough we have shown in Fig. 85. We discovered this, in bits, in an orchard of a farm at Hemsby, while we were on holiday in Norfolk, and with the assistance of an old ploughman propped it up once more into a semblance of life so that we could draw it. The village laughed at the mad artist, but the old ploughman was rather touched. He held the one handle while he talked to us of his craft, and would have agreed with A. G. Street's panegyric of ploughing in "Farmers' Glory." He told us as well that he thought the plough dated from about 1840, and that it was called a Skyles plough, because it had been made by three brothers of that name who worked close by. They had their own smithy, foundry and wood-working shop.




FIG. 86.—Bell's Reaping Machine (1826), now in Science Museum, London.

REAPERS

Now look at Fig. 85, and decide for yourselves if they were three fools or three wise men. So far as we are concerned, we think they were artists, and we dedicate Fig. 85 to their memory, and we hope that if they are now ploughmakers in the Elysian Fields they may come to know this and give us an amused chuckle.

Following the ploughing came cultivating, harrowing and rolling, to prepare the land for sowing. It is obvious that you could not sow seed in clods.

Many more drills followed Tull's, which we illustrated in Chapter I, but, as we have seen from Cobbett, seed was still sown as well either broadcast or dibbled.

When we come to reaping, the inventors got to work at an early date, and a very natural thing happened. Their first idea was that you could not possibly take the reaping machine into a lovely field of corn, with the horse in front, and let the corn be trampled down before it could be cut, so the machine came first, and was pushed by the horses like a mowing machine. You can see at the Science Museum, London, one of the first of these reaping machines, made in 1826 by the Rev. Patrick Bell of Forfarshire, which we have shown in Fig. 86. How the unfortunate horses managed to push the cumbersome machine along over ridge and furrow we cannot imagine, but they did, and many were made and used.

Fig. 87 explains the mechanism of Bell's reaper, and it is worth consideration because it incorporated some very good ideas. The man in Fig. 86 walking on the near side of the machine was able, by means of a handle, to disconnect C from B in Fig. 87, and so stop the whole working. In the same way, by means of the cord shown, he could raise or lower the revolving frame in front to suit the height of the corn which it pressed down on to the knives. Perhaps the most ingenious idea was the pair of bevel gears at L, Fig. 87. Either of these could be slid on to M, to turn the circular shafts at the side of the sloping apron in front, on to which the corn fell when it was cut—the shafts

McCORMICK




FIG. 87.—The Mechanical Part of Bell's Reaping Machine.

were connected at the foot by a chain, and travelling bands on the apron threw the corn to the near or off side as desired. This was a real triumph. The Rev. Patrick must have been cheered when he thought of this. His machine could go up and down a field, and not round and round, if so desired.

James Smith of Deanston had experimented (before Bell) with the machine before horse type of reaper, which rotated a cheese shaped cutter with a knife on its lower edge.

The first real advance was made by Cyrus H. McCormick, who patented his reaper, as Fig. 88, in U.S.A. in 1834. McCormick's brain-wave came in realizing that if he could only arrange his cutting knives on one side of the horse, then the machine could be *drawn* with greater comfort. The mechanism is shown in Fig. 88, and it is simplicity itself, as all real brain-waves are. A pulley at the side of the one road driving wheel was connected by a band to another pulley over turning the circular wooden frame. The blades of this were slightly twisted so that the corn was gradually bent down. The bevelled gears turned a small cranked shaft, which gave the reciprocating motion to the cutting knife, working it backwards and forwards



FIG. 88.—McCormick's first Reaping Machine (1834).
(From a model in Science Museum, London.)


SCYTHES

like a hair clipper. McCormick's machine was a reaper only, and not a binder, and the cut corn had to be raked off and then tied up into sheaves, and stacked in stooks. The man with the rake had a tiring job, as he had to sidle along backwards, or tread on the corn as he raked it off. To get over this trouble a seat was built upon the machine, so that the raker could sit at his work—this was done in 1847, and a reaper of this type won a prize at the London Exhibition of 1851. With the McCormick reaper a pathway had to be cut all round the field first, with a scythe, to make a passage for the machine, and then round and round a diminishing square it went, driving the rabbits into an always smaller space, until they had to bolt and run the gauntlet of all the boys and dogs in the neighbourhood.

We once saw, and it is proof of our nearly incredible antiquity, a field of wheat all cut by scythe. The head man started off on the left, and cut a swathe straight ahead of him, progressing with long rhythmical strokes. When he was safely in advance, the next followed, and so on until six were stretched across in a slowly moving echelon, to the accompaniment of the most beautiful sound of the tubular straws being cut by the sharp steel. A scene as idyllic as that pictured by Hephaistos on the shield he wrought for Achilles, where the corn was cut by sickles, and the sheaf binders followed with twisted bands of straw, meanwhile a feast was made ready beneath an oak. Our reapers needed lashings of beer, and hunks of bread and cheese, with perhaps a little cold bacon, and a raw onion as savoury.

The next step to be considered is threshing. In Vol. II we illustrated the barns in which the harvest was garnered, and the flails which were used to thresh out the corn from the ear. Quite early in the eighteenth century the inventors got to work and tried to produce mechanical threshers, and by the early nineteenth century these were coming into general use. Judging by a model at the Science Museum, which we have drawn in Fig. 89, and

THRESHING



MAN STOOD IN WELL (A)
 & FED CORN INTO (B)
 ON TO TOP OF BEATERS
 REVOLVING INSIDE
 WIRE SCREEN OR
 CONCAVE BACK OF WHICH
 IS SHOWN AT (C): GRAIN REMOVED
 AT FRONT & L. SIDE: STRAW AT BACK.

FIG. 89.—Model of Horse-power Thresher (1851).
 (Science Museum, London)

which was exhibited at the 1851 Exhibition, the inventors had not made any very great progress by then, and the early threshers were the simplest contrivances.

With the flail the corn was laid out on the threshing floor, and the grain knocked out of the ears by the blows of the swingel. In the early threshers the rapidly revolving blades of the beater, shown in Fig. 90, took the place of the swingel, and the real advance came with the provision of the circular screen, or "concave," which acted as a sieve and separated the grain from the straw. This machine was worked by horse power, and its capacity is stated to have been 60 bushels per hour. It must be remembered that it only did the threshing, and this sifting of the grain from the straw—it did not, as modern threshers do, include the winnowing.

To understand winnowing, we need to go back a little.

WINNOWING

In our books on Ancient Greece we described how the Greeks, after oxen had trodden out the corn, threw the chaff and grain up, so that the wind carried the lighter chaff away and left the heavier grain in a long shaped heap. This operation continued down through all the hundreds of years, excepting that the place of the wind was taken by the primitive fan we have illustrated in Fig. 91. One amusing detail

of this method is that in throwing the grain along in front of the draught made by the fan the heaviest and best grains went farther than the poor ones, and so these, being at the tail, were called "tailings," as they still are.

One could not expect the nineteenth-century inventors to put up for long with such a simple apparatus as Fig. 91, and they very speedily invented a series of winnowing and sifting machines which got rid of the chaff, dust and weed seeds. Up till the 1851 Exhibition these had not been combined with the thresher, as they are now.

When we come to milling we have seen on p. 81 that the steam engine was applied at a very early date to mills, as was the use of cast-iron rollers, instead of the old mill




FIG. 90.—The Mechanical Principle of Thresher, Fig. 89.

WINDMILLS




FIG. 91.—Winnowing Fan.
(*Science Museum, London*)

stones of the windmills. Some of the windmills continued to hold their own, as a few of them do even to-day.

When Cobbett was at Ipswich he counted seventeen windmills on the hills around the town, and their bodies were painted white and their sails black.

If any of our readers wish to keep their French from getting rusty, they can read "*Lettres de Mon Moulin*," by Alphonse Daudet. Perhaps the nicest of the letters, dated from an old windmill overlooking the village of Fontvielle, in Provence, by the author of "*Tartarin de Tarascon*," and which was published in a Paris newspaper, is the one called "*Le Secret de Maître Cornille*." The tale deals with the losing fight of the old miller against the new steam-mill. He implores his neighbours, "*N'allez pas là-bas, disait-il; ces brigands-là, pour faire le pain, se servent de la vapeur, qui est une invention du diable, tandis que moi je travaille avec le mistral et la tramontane, qui sont la respiration du bon Dieu . . .*"—but read for yourselves and find out his secret.

CARTS




FIG. 92.—Evolution of the Tumbril and Waggon.

We have illustrated the various types of windmills in Vols. I and II. Steam roller mills will hardly lend themselves to illustrations, but models can be seen at the Science Museum, London. We strongly recommend our readers who are interested to go there and see the Agricultural Section. It is the best one we know, and the Handbook on Agricultural Implements and Machinery,

TUMBRILS




FIG. 93.—An East Anglian Tumbrel.
(Drawn near Halstead, Essex.)

which can be bought there for 2*s.*, mentions, and illustrates, many other types and variations for which we cannot find space.

Now we can consider the farmer's means of transport ; the tumbrel that took the dung to the fields, and the waggon which carried the harvest home. Here is a subject which is nearly as old as man himself. Long before he was a farmer, he may have tied two poles together, as Fig. 92, and found that he could pull a more cumbersome load in this way than he could carry on his shoulders. When he had domesticated the horse, he could be put into the shafts, and you get the slide-car of Antrim, Ireland ;

WAGGONS

and wheels added made the Irish wheel car. Obviously this is the line of ancestry of the tumbril, or dung cart, as Fig. 93. Arranged to tip up as shown, it is one of the most useful implements on the farm. We discovered the example we have drawn near Halstead, in Essex, and as it had wooden axles (to-day these are made of hardened iron, bedded and bolted into the wooden axle-bed) it must be of very considerable age. Its wheels were 4 feet, 10 inches diameter—from the pummel or bumpers at the back to the front of the shafts was 13 feet 7 inches—the bottom frame-work was 3 feet 10 inches across the front, and 4 feet at the back, which helped the clearance of the load as it was shot out. The design of a tumbril was a nice exercise in the art of balance. If the weight is thrown too far forward on the ridge tie, or chain over the horse, it is as bad as if it is too far back, so that it pulls up on the wantie or belly-band. The old wheelwrights had to bear all these details in mind.

The waggon is nearly as old as the land over which it trundles. One of the earliest examples must be the one which was discovered in the Viking Ship at Oseberg; but with it was buried a sledge, and this seems to have been the ancestor of the waggon. A northern people would soon have discovered that the sledge slid over the snow better than dragging poles, and then, in the summer, wheels would have made the sledge go better still. Readers who are interested in the subject are advised to read Dr. Cyril Fox's article in "Antiquity," which we note in our Authorities.

Here in England for centuries the waggon took the corn to market, and gaily painted (red lead for the wheels, and yellow or prussian blue for the body), with its fine team of horses, showed what manner of man the farmer was, and if he wanted to move house then the waggon was the moving van. And the last journey of all was taken in it—washed, and dressed with evergreens, the waggon carried the farmer in his coffin to the churchyard. In more ways

WHEELWRIGHTS






FIG. 94.—The Under-Framing and Carriages of A, Fig. 95.


than one the waggon was a very moving thing, and has played its part well in Anglo-Saxon history. It went to America with the emigrants, and under the "covered waggon" the hardy frontiersman slung his plough—one covered the ground, the other broke it.

We referred in Vol. II to "The Wheelwright's Shop," and should like to do so again, because in this book is given the whole art and mystery of the wheelwright's trade as it used to be carried on. The wheelwright was the master craftsman of the countryside, the coach-builders generally working in the towns. Consider the difficulty of making a wheel by hand. To start with the face of the wheel had to be concave or dished in design. This was done because when the waggon went bumping over the ridges the whole weight of its load might be delivered as a thrust on the inside of the stock (nave or hub). Had the wheel been made flat, the weight of such a blow would have knocked all the spokes out, so the wheel was dished. Consider the difficulties this entailed. The stocks were of elm, and in the early days chipped out by hand with an axe, because they had not got lathes to do it. The spokes,

WAGGON AT TRING HERTS. DRAWN 1919
 BODY 12' 0" LONG - FRONT WHEELS 3' 9" DIAM.
 BACK WHEELS 4' 9" DIAM.



WAGGON AT HALSTEAD ESSEX (1932)
 BODY 11' 9" FRONT WHEELS 3' 11" DIAM. BACK 5' 1".



WAGGON AT TRING (1920)
 BODY 12' x 3' 9"
 FRONT WHEELS 4' 0" DIAM.
 BACK WHEELS 4' 11" DIAM.

G.H.B.Q.


FIG. 95.—Various Types of Waggon.

“ SUMMERS ”

made of heart of oak, and cleft, not sawn, were tenoned into the stock in a staggered fashion, one forward, one back, so as not to weaken the stock, and as the spokes not only radiated but leaned out a little, cutting the mortises called for judgment. Then there was the further complication of the felloes, or rims, of ash, elm or beech ; these were made in sections and dowelled together and had to be mortised to take the spokes, which were always arranged in pairs, but owing to the dishing of the wheels the spoke at the bottom was vertical, and the one over leaned out, and the felloes had to be fitted together to make a rim and yet pick up all the spoke tenons. Then the tyres, which by reason of the dishing of the wheels were not like narrow widths of a cylinder, but had to be slightly conoid in shape.

Another refinement of waggon building was the fitting of lengthways floorboards, as Fig. 94. The floor of a waggon is supported by the “ sides ” outside, and the “ summers ” inside, which act as joists. As these run longitudinally the simplest method of flooring would have been to nail the floorboards across these, but it would not have been so good, because shovelling out a load across the grain of the floorboards would have worn and splintered them. So oak keys were driven through the summers from side to side and kept down about 1 inch below them, and the floorboards fitted between lengthways. Mr. Sturt says in his book that in Surrey this thoroughly practical method was given up about 1884 for the cheaper, and nastier, cross-flooring.

All these details and many things beside are discussed in Sturt's book, and when reading this look at Will Hammond's and George Cook's photographs, and think of them as great artists, because that is what they were. They and their master were playing a losing game, which they have now lost, and passed on—the machine was too much for them—and in losing them we have lost something as well. Men who with oak, ash and elm, a few tools and



C.H.B.Q.

BERKSHIRE WAGGON (DRAWN 1933) BODY 12'6" LONG: FRONT WHEELS 4'6" DIAM.
BACK WHEELS 5'5": TRACK OVERALL 5'7": VERMILION WHEELS: YELLOW BODY.

FIG. 96.—A Waggon from the Vale of the White Horse.

STURT

that most wonderful tool of all, the human hand, could make a waggon are a loss. It is saddening to think that you would hardly find a man in England to-day, unless you happened on a very old man, who could do their work. There are many though who, if asked to do so with such a simple apparatus, would sit down and weep. When a waggon was finished in Sturt's shop the fact was celebrated by a wayzgoose, or supper, held in the local inn, with songs and merriment.

Fig. 95 shows various types of waggons which we have drawn from time to time. A, though not of very interesting shape, was one of the most beautifully made waggons we have ever come across, and the waggon chamfering, which had the practical purpose of reducing weight, was superb. For example, look at the strouters or struts on the sides. Its under-framing is shown in Fig. 94. B, Fig. 95, might be nearly as interesting in shape as the old Berkshire waggon, Fig. 96, because it is of the waisted variety, but the waist is concealed by the sides being taken across it, with a hole cut in to take the wheel on the lock. The front ladder and movable front are unusual. It was said to be about sixty years old. C, Fig. 95, is a Wiltshire type which had found its way to Tring.

A and C, Fig. 95, were broken up for scrap-iron and firewood soon after we drew them.

Some of these drawings date from 1919-20, when we were engaged in a campaign to try and get some specimens saved, with other implements, in an open-air museum. Our campaign naturally did not come to anything—people are not really interested—but here is a letter from Thomas Hardy, dated April 7th, 1921, who was an architect before he became a novelist and poet, and whose help we had solicited:

“The commendable interest you take, as is shown by the letter you send me, in old agricultural implements as valuable relics of the past, I entirely reciprocate, and were I younger I might assist you in steps towards the preserva-




FIG. 97.—The Wheelwright's Shop at Bockley, Sussex.
After a painting by P. W. Cole, R.B.A., A.R.C.A. (Lond.).




Fig. 98.—The Timber Carriage. (Drawn at Potter's End, Herts, 1933.)




FIG. 99.—The Timber Truck, Neb or Bob. (Drawn at Berkhamsted, Herts.).

THOMAS HARDY

tion of typical examples. But I am quite unable for one reason and another to join actively in such a movement. Letters to the papers invariably bring an overwhelming correspondence, which I cannot cope with at my age. I trust that you will be able to enlist the sympathies of more active lovers of such antiquities before it is too late to do anything towards saving them.

“The farm waggon, of which you send a sketch [this was C, Fig. 95] is a fairly good specimen; but the old ones left hereabout—at any rate till lately—are more graceful, the curve being very marked, and the floral designs painted on the front and tail-board very ingenious. This latter feature has, however, almost disappeared under a coat of plain paint.” We have never discovered a waggon with floral designs.

This was before we had drawn the old Berkshire waggon (Fig. 96) in 1933, and we think this would have earned Hardy's commendation. We discovered it late in the autumn of 1932, when we were motoring through Tom Brown's country, the Vale of the White Horse, Berkshire. The wide wheels with the double strakes, locking felloe to felloe, were seen in the gloom of a cart-shed by the road. The ancient Cowley we possess was stopped with a shriek of its brakes, and we tip-toed into the shed and found Fig. 96. It was a wonderful moment, because—let there be no mistake about it—we were in the presence of as fine a piece of evidence of the ingenuity of man as well could be—a wooden ship and a waggon such as this are two of the most beautiful things ever made by man, and this type of waggon is so ship-like. It is of the waisted variety, as was the Kent and Sussex type we illustrated in Fig. 118, Vol. II, and the floor rises up towards the front. Now think how you would like to make this in such a workshop as Fig. 97, without anything to help you except your brain, hands and a few tools. The Berkshire waggon may still exist (we drew it in the spring of 1933), so we send out another plea. Cannot we somehow or other start an open-air



Fig. 100 Ploughing (with a Wooden Plough), Rolling and Broadcast Sowing, c. 1850.

(*Unbound and Unpaginated*, London.)

Fig. 1. 1. *Unbound*



FIG. 101. A Catholic Town in 1840



FIG. 102.—The same Town in 1840.

GATES




FIG. 103.—A Cornish Field-Gate.
8 feet wide by 4 feet high.

museum, like the Skansen, near Stockholm, where the pleasant old things of the countryside could be preserved. It is not well for us that they should all be destroyed. The average weight of a waggon was about 18 cwt., and it carried a 3-ton load. In 1772 Young noted the cost of a waggon at £20 to £25, and a tumbril £10 to £12. By 1870 a waggon cost £42.

The wheelwright's work started in the woods; here he bought his timber, and he had to buy with judgment. Naturally curved trunks would cut into the curved timbers which were used in waggon building, and you did not buy your oak and elm in the same woods, because oak likes a heavy soil, and elm grows on gravel. Having bought your timber, you carted it home and cut it up over a pit, with a top sawyer and a bottom sawyer, and then it was stacked in the yard to season, at least a year for each inch in thickness—laid down almost like port to mature, and used with the same judgment and gratitude.

All this meant work for other people besides the wheelwright—his timber had to be carried. Fig. 98 shows the timber carriage which was, and is still, used. In form it

HORSES




FIG. 104—The Five-barred Gate.

much resembles the frame of the farm waggon, without the body on it—in fact, this timber carriage is really the basis on which many carriage and coach forms have been built up; a few boards laid across it, and one edgeways up against each standard and you had a very useful waggon. The carriages could be used as well for carrying hop-poles to the hop-gardens, and for a variety of other purposes. When the carriage is used in the woods it is brought up as close to the side of the log as is possible, then larch poles are placed on wheels as shown. These are held in position by a chain taken through the pillow, under the felloe, round over the larch pole and the tyre under the felloe and then hooked as shown. The other ends of the chains are passed under the log and over it, and back over the carriage to the horses on the other side, who then pull on the chains and roll the log up the poles until it rests on the carriage, butt end always foremost. The moment the pull of the horses is put on the chain the tops of the poles are locked to the wheels by the methods of fixing the chains there; a very simple but ingenious arrangement. The carriage is low built and wide, as it need be to prevent overturning.

But some logs are so awkwardly placed that the carriage cannot be brought alongside them, and then in our part of the country the truck, neb, or bob, as Fig. 99, is used. We cannot say anything of this amazing contrivance, or

TRUCKS

how many centuries have gone to its evolution, but here it is still in use. The truck is backed over the butt end of the log, which is raised as described on the drawing. Two horses are used on the road, driven tandem, so that the total length with log is about 37 feet, and to see a truck like this on the road alongside a Green Line bus is to see old and new together in a startling fashion. Figs. 103 and 104 show field gates; these used to be locally made and, like the waggons, the patterns varied in the different localities. A good gate is not at all an easy thing to design; you lose the simplicity which is necessary and produce something which looks as if it should be seen in front of a villa unless you are very careful.

Here we must finish our sections on the countryside and the work of the farmer, and we are conscious that we have done it badly. Still there may be something in it which will stir the imagination of the boys and girls for whom we write. Remember the rejoinder of Alexander to Dinocrates, that, "as an infant is nourished by the milk of its mother, depending thereon for its progress to maturity, so a city depends on the fertility of the country surrounding it for its riches." From the attic in which this is being written we look out on an awakening world; the blackthorn is in full flower, with the cherry and plum, and the bees are hard at work on the arabis and aubretia. The thorn has put out its leaves, but the other trees only show tender flushes of colour through which their branches can be seen. A glossy starling has perched on the bare ash opposite our window and, having parted company with the flock, has set up housekeeping with another on the chimney top—the spring is here.

This miraculous place, this English countryside, is worth knowing and preserving and loving—we commend it to English town-dwelling boys and girls. Adrian Bell's and A. G. Street's books will help us to understand it, and we must not forget "Joseph and His Brethren."

CHAPTER VII

NINETEENTH-CENTURY BUILDING

WHEN we come to building at the beginning of the nineteenth century we find a very different state of affairs from that which had obtained at the beginning of the eighteenth. When Queen Anne was on the throne there was one central stream still steadily flowing from its sources in Jones and Wren. One hundred years on, the stream had divided up into many rivulets and had lost its force and direction. It was possible in building to be Greek or Goth, Roman, Chinese or Egyptian—fashion had taken the place of tradition.

We will deal with the "Goths" first, because in the end they triumphed over the "Greeks" and sacked their citadels.

We have seen (p. 48) how early the first Gothic revival started; Battey Langley published his book in 1742, and in it set out to restore and improve Gothic architecture. Horace Walpole was certainly no fool, and yet he attempted the impossible in building a castle.

In the second Gothic revival of the nineteenth century the full tide of romanticism set in, and flowered into the poetry of Sir Walter Scott, which preceded the beginning of the *Waverley Novels* in 1814. The ferment in men's minds which produced the French Revolution was reflected in their buildings—the rules of Classical Architecture were thrown on one side for what was thought to be the more natural inspiration of Gothic. Picturesqueness was demanded, so castles and abbeys were explored. Their lovely ruins, seen perhaps by night, with a pale moon silvered against the gloom, and showing through the web of a rose



FIG. 105. —Midday Traffic in Parliament Street (1820)

By E. Faint & H. Monette




Fig. 106 Interior of the 'Reduced Amnities' Bank of England

(See *John Smith, J. R. S., J. R. S., J. R. S., J. R. S., J. R. S.*)

ASHRIDGE

window, fired the clients and their architects. So they set out to recreate castles and abbeys, forgetting entirely that you cannot *design* castles and abbeys, but that these must grow out of quite definite practical requirements and plans.

In our book on Anglo-Saxon England we showed how the timber forts on the tops of the mounts, as shown in the Bayeux Tapestry, developed into the Shell Keep, as at Berkhamstead. In Vol. I. of this series the square keep of Hedingham was followed by the polygonal one at Orford, in Suffolk, and then the fortified walls of the Edwardian castles in Wales gradually developed into the more comfortable quarters at Bodiam. Again, in Vol. I. we showed how the conventual buildings of the Benedictines, Cistercians or Carthusians developed around their cloistered needs. The original builders of both castles and abbeys put plan and practical purposes first, and built around these beautifully; they did not set out to construct picturesqueness; they ornamented construction instead of constructing ornament; the nineteenth-century Gothicists did not follow their good example. Take Ashridge, Herts, the subject of our sketches Figs. 107 and 111. This was designed by James Wyatt (1746-1813), who was afterwards called the Destroyer by Augustus Welby Pugin. This was because of the work Wyatt did when "restoring" Salisbury Cathedral in 1789, when he took out thirteenth-century glass like that of the Five Sisters at York. This was hardly a good preparation for the work carried out at Ashridge from 1806-13, and which was finished by Wyatt's nephew. We have chosen Ashridge because we used to go there in the old days when it was still a house, and not a college as it is now. Look at the exterior view, Fig. 107, and it is just a muddle. Had it been a real castle, abbey or house you would have been able to pick out its plan or skeleton at once. There is no recognizable make or shape about Ashridge. It is like a snowman, built up by sticking on lumps instead of having good bones inside it. Internally it was much the same;




FIG. 107.—Ashridge Park, Hertfordshire.

(James Wyatt, *Architect*, 1806-13.)

BECKFORD

you entered, by the door shown in the distance in Fig. III, into an entrance hall with a timbered roof, which was much too high for its length and width, and looked through a double-arcaded screen, carrying the bedroom passages, into the staircase hall shown in our sketch. All this magnificence led up to a smallish ante-room, with the dining-room on one side and the state drawing-rooms on the other. The staircase hall, about 40 feet square, rises up some 90 feet odd, so that it is a "Gothick" well, made up of bits, and without any pride of race or ancestry behind it. No real Gothic staircase was ever like this one.

Here is a tale which illustrates the early nineteenth-century outlook, and how cheerfully they destroyed to make way for their own work. We were shown a nice eighteenth-century barometer in a mahogany wall case and told that this was all that remained of the furniture of the house which preceded Ashridge. When the new house was ready all the old furniture was piled up in the park and a lovely bonfire made of it, and all the village watched the conflagration, including the parson of Little Gaddesden, and then suddenly the weather glass, untouched by the flames, slithered down off the pile to his feet, and he whipped it up and put it under his cloak, and many years later it came back to Ashridge and was treasured as an "antique."

Wyatt was the architect of the sham abbey which Beckford built at Fonthill in 1795.

The next names in importance in the Gothic revival were the Pugins, father and son. The elder Pugin came to London in 1798, and was employed by Nash. He had a drawing school and published "Specimens of Gothic Architecture, 1821-3." His son, Augustus Welby Northmore Pugin (1812-52), followed in his father's footsteps, and as a boy of fourteen was measuring up Rochester Castle and nearly lost his life by the collapse of trenches which he had excavated. Augustus Welby became a Roman Catholic in 1834, and one of his works which

PUGIN

Londoners can study is the Roman Catholic cathedral in Southwark. He also assisted Barry with the designs of the Houses of Parliament, in Westminster, begun in 1840, and clothed the classic type of plan with the Gothic detail one sees there now.

Pugin published his "Contrasts," or a parallel between the architecture of the fifteenth and nineteenth centuries, in 1836. Figs. 101 and 102, reproduced from one of the original plates, shows one of the contrasts. One of his last works (before he died in 1852) was the arrangement of the Mediæval Court of the Great Exhibition of 1851. In an illustrated "cyclopædia" published in 1852 one of the exhibits in the Mediæval Court, an oak niche, is noted as "the great peculiarity of this niche consists in its being designed after the old principle, to suit the material in which it has been executed." This was very much more than could be said of many of the exhibits. Fig. 126 shows a table designed by the Duchess of Sutherland, and made for her by G. J. Morant. It is described as being of elegant design and the finest workmanship. The swans were painted white, and the lilies and bulrushes partly gilt and partly white. We hope her Grace was a better duchess than designer.

Pugin was the pioneer of the later Gothic revival, which came about as a response to the movement which originated at Oxford when Keble preached a sermon on National Apostasy on July 14th, 1833. Under Keble and Pusey the movement quickened the life of the English Church. Henceforward Greek churches, like Inwood's at St. Pancras, were thought of as pagan and became unfashionable, and the many new churches which were built in the middle and later part of the nineteenth century had to be Gothic, and they were not very much nearer the truth than Ashridge, which we have illustrated. The best summing up of the later Gothic revival we know was contained in a letter written to us by the late R. Norman Shaw, R.A., in 1910: "It was always supposed that 'Gothic' was to



FIG. 108. View of Brighton looking to the Pavilion and Sea, 1830

By John Bury, Brighton



FIG. 100.—Wedgwood and Byerley's Pottery Emporium, York Street, St. James's Square, c. 1800




FIG. 110.—A fine Shop in Artillery Row, Houndsditch, London, of the latter half of the eighteenth century.




FIG. III.—Ashridge Park, Hertfordshire.
Staircase Hall.

(James Wyatt, Architect, 1806-13.)

REGENT STREET

develop, and there was any amount of tall talk as to what it was to do—but it didn't do anything. It was like a cut flower—pretty enough to look at—but fading away before your eyes—and if we don't take care, the English Renaissance that we now have will do the same—so unlike the French—they went on all the last century doing work that was founded on their old work, and magnificent work it was—and this was the result of gentle development, new features and arrangements growing from the old stock. In fact their Architecture was alive—ours dead—a mighty difference—and arising of course from their having a School—and we have none.” Norman Shaw was an old man in 1910, and had retired after a distinguished career as an architect in the nineteenth century. We remember that it was a little saddening at the time to receive the letter and realize how the high hopes had faded. The “castle,” “abbey,” “cathedral” and “church” builders had discovered that architecture is not a “cut flower” which can be used for decorative purposes and put in any pot—but a plant that only flowers if it is rooted in reality.

Still the Gothic people did not have it all their own way, and the old classical tradition lingered on side by side with the Gothic until well on in the nineteenth century. The Prince of Wales became Regent in 1811, and George III. did not die until 1820. It was during the Regency that Regent Street, London, was designed by John Nash, and a very noble piece of town planning it was. Starting at Regent's Park with the villas there, it finished at Carlton House, where the Regent lived, and where Carlton House Terrace and the Duke of York's column were built when Carlton House itself was pulled down (1827-29). The Regent's Park villas remain, but Regent Street has gone, and in 1933 a beginning was made in the destruction of Carlton House Terrace, which it is hoped will not continue. Nash's architecture was not in itself superb—there is the well-known quip,




FIG. 112.—House at Kennington Oval, South London. (Now demolished.)

BANK OF ENGLAND

“ But is not our Nash, too, a very great master ;

He finds us all brick and he leaves us all plaster,”—

it was the fact that Regent Street was part of a well-ordered scheme which made it such a distinguished and well-mannered street. Now all the buildings are up and down—there is no plan—all shout at you as it were, and the street is just a medley of poor architectural forms. The old Regent Street was better than the new, and here we should like to tell of the Bath buns which could be bought there when we were young. It may be that our appetites have changed with the passing years, but we remember the ones we used to eat there as incomparably better than their unworthy successors ; it is sad to think we shall never eat another, never feast our eyes on their yellow sweetness, never surreptitiously lick our fingers after the eating !

But to revert to architecture. During this time many houses were built ; the Napoleonic wars were at an end and much building was done. The plastered houses were made gay with paint and balconies were added in delicate Greek designs. In Fig. 36B we show the quiet interior of one of these nice stucco squares, and from the tailpieces (pp. 183, 196) you can see how charming were these neo-Greek interiors ; they are taken from Moses delicate little engravings called “ Modern Costume,” 1825.

Another name to be mentioned honourably is that of Sir John Soane. He was born in 1753, entered the office of George Dance in 1768, won the R.A. Gold Medal 1776, travelled in Italy 1778–80 and, coming home, was from 1788 architect to the Bank of England, London, for forty-five years. Soane’s screen walls to the Bank building still remain, and Fig. 106 shows one of his interiors there. This is curiously modern in design—all the architectural fripperies have gone by the board ; except for the little columns in the cupola light there are not any orders with their entablatures, and the effect is got by simply ornamented geometrical shapes. Soane was a very sound



FIG. 11. Houses in Brunswick Square, Hove, Sussex.

BRIGHTON

constructor, and his vaults were made up of fireproof tiles, not lath and plaster. His work did not please his contemporaries, who were outraged by its modernity. The house which he built for himself in Lincoln's Inn Fields, London, and which is now the Soane Museum, should be visited because the furniture is as he left it. Soane installed a small pipe high-pressure steam-heating system in his own house in 1831, but had used steam heating at Tyringham, Bucks, as early as 1797. Here is an interesting point: the long hours which were worked at this time in the new factories are often noted as being inhuman, but these were not unusual. Soane's office hours were seven to seven in the summer, and eight to eight in the winter.

Fig. 112 shows one of the suburban houses which began to be built early in the nineteenth century, and what could be more pleasant than this one which used to stand at Kennington Oval? One likes to think of a nice young couple setting up house in it. We remember it when going to the Oval in the old days, but even then it had fallen on evil times and looked unkempt. When the house was built Kennington and Camberwell were countrified to the business man, and he lived there and drove into the City. Now these neighbourhoods are forlorn wildernesses; many of the old houses remain, but they are unkempt and uncared for. On some of the front gardens cheap shops have been built; in others a few sooty shrubs remain, and gates hang awry and creak dismally.

Many very pleasant Regency houses and shops remain at Brighton—quite enough to make one sad that the town was developed so badly during the nineteenth century. Had the Regent's tradition of building been carried on and developed it might be quite one of the pleasantest towns in England.

Fig. 113 shows one or two of the houses in Brunswick Square, Hove, Sussex, and here the Ionic order from the Erechtheum, Athens, which we saw in our book on Classical Greece, on one house has been pleasantly varied




FIG. 114.—In the Park (1825). The North Lodge, Stanhope Gate, Hyde Park, London.

(*Decimus Burton, Architect, 1800–1881.*)




FIG. 115.—East Front of the Pavilion, Brighton.

John Nash, Esq. R.S.A.



FIG. 116. —A Factoryscape in the Potteries.



FIG. 117 Back-to-Back House in the North
of England




FIG. 118 One-Roomed House for Five,
Offaly, Dublin, Ireland

THE PAVILION

with plain pilasters on the next. Decimus Burton's Hyde Park lodges, as Fig. 114, carry on the Greek tradition.

Again, what could be more pleasant or conducive to good business than the old shops we illustrate in Figs. 109, 110? The modern multiple stores are the great offenders—they come into the country towns and buy, perhaps, a nice old Georgian house, and tear out half of its front. Then up goes an enormous name plate, and if they can contrive that this goes half across the first-floor windows, then this is done. Under and behind an enormous sheet of plate glass cart-loads of provisions are displayed for sale, and as an amusement park for all the flies in the neighbourhood. They seem to advertise quantity, but not quality.

It was at Brighton that the Regent built the Pavilion, between the years of 1784 and 1820. Starting as a respectable farm-house, it was continually being altered and enlarged until it came to its present form. Holland, the architect of Carlton House in London, made it into a quite nice and ordinary house from whence the Regent could enjoy the sea breezes and lead the fashion in going to the seaside. Repton prepared designs, and published them in 1808, and these seem to have given ideas to Nash, who gave the Pavilion its present exotic form. Cobbett was in Brighton in 1822, and this is how he describes the building: "Where you see the thing from a distance, you think you see a parcel of cradle-spits [one is shown in Fig. 133] of various dimensions, sticking up out of the mouths of so many enormous squat decanters. Take a square box, the sides of which are three feet and a half, and the height a foot and a half. Take a large Norfolk turnip, cut off the green of the leaves, leave the stalks 9 inches long, tie these round with a string 3 inches from the top, and put the turnip on the middle of the top of the box. Then take four turnips of half the size, treat them in the same way, and put them on the corners of the box. Then take a considerable number of bulbs of the crown-imperial,

A KREMLIN




FIG. 119.—Housing in a Slum Area.

the narcissus, the hyacinth, the tulip, the crocus, and others ; let the leaves of each have sprouted to about an inch, more or less according to the size of the bulb ; put all these, pretty promiscuously, but pretty thickly, on the top of the box.

Then stand off and

look at your architecture. There! That's 'a Kremlin'!"

Naturally enough Cobbett thought the Pavilion was a vain thing, and, knowing as he did the unfortunate condition of the agricultural labourer at the time, he was enraged that money should have been wasted in such a way. Still from our point of view the Regent's seaside palace is very interesting, and one can hardly understand the Regency Period unless a visit is paid to Brighton to see it. On a grey day it is very unreal, but in sunlight, or at night when it is floodlit and seen by itself behind the silhouette of trees which cut off the rest of the town, the east front, as Fig. 115, becomes a fairy palace, and one sees what the old Regent was aiming at.

Inside, the State apartments are very fine with their riotous decorations in silver, scarlet, gold and writhing dragons, all in the Chinese manner. The frontispiece shows a banquet in progress and will give some idea of the colour.

Fig. 108, from a very interesting old print of Brighton, shows the first view of the town which the traveller from London had, with the Pavilion as its central feature.

But enough of kings' palaces. The time has come to write of other things ; so far we have been concerned with beauty, now we must search for ugliness, and we shall not have to go very far. In the nineteenth century people seem




FIG. 120.—A Family Party in 1806.

TOWN-PLANNING

to have lost all their architectural good manners. Until then even the simplest buildings, the cottages, stables and sheds, were pleasantly simple and unpretentious, and you could live in and with them. There was no need to have a Society for the Preservation of Rural England. Since the Industrial Revolution the very reverse has come to be the case, and building has been unplanned and marked by pretentious shoddiness. It was not till 1909 that John Burns brought in his Town Planning Bill to try and persuade people that it was a good idea to plan a town before you built it.

Let us take Fig. 3 for an example. If you happened to find your way to Berkhamstead and wandered around the little town, as a stranger you would be able to trace its history since the day that William the Conqueror accepted the submission of the English there. The place was vulgarized in the nineteenth century; there have been hideous suburban developments, and multiple shops spoil the High Street. Still the town is a microcosm, a little world of its own, and recognizable as such.

Now let us take an Automobile Association map and select one of those areas which are hatched in grey as places to be avoided if you are motoring for pleasure. The hatching is symbolical, and the warning necessary. These industrial towns are grey beyond belief, pleasure has flown away, and you are apt to lose your way because the place has been developed without any plan—it is, in fact, without form and void. There may be a church, but there are more likely to be many chapels where people can voice their dissent. There will hardly be a market square; there is no need for one, because the products of the factories are sold overseas and paid for by imported foodstuffs. So the town has no centre, and as it has no plan you will find factories, houses, shops, chapels, cemeteries all in one inextricable jumble. Around the town will be the later suburban developments. Miles of dreary roads and houses; a growth which has spread across the fields like a fungus,

SLUMS

but always cut off from the country by a tin-can zone where the urban rubbish is shot. If you can imagine yourself as having come from Mars with a seeing eye, and seeing for the first time, the first question which would arise would surely be: What were the conditions of life which produced so much ugliness? If a man is to be judged by his




FIG. 121.—Early Nineteenth-Century Chair.

works, how are we to judge these early Industrialists? They acquired money, but not much else.

If our books have served any useful purpose at all, it will be found in the fact that throughout them all we have stressed the fact that life and things must be planned; that you cannot *design* buildings. These must grow naturally out of the practical requirements of people, and the buildings are like the people. Take any period you like and study the people and their ways, and you will find that their buildings fit them like gloves.

All the king's horses, and men, and architects, and town planners, and Acts of Parliament must fail unless the conditions of life are kindly and pleasant.

All this leads up to the slums, which remain as a source of embarrassment to the industrial towns, because, to give them what credit we can, they are doing their best to remedy matters. Fig. 117 shows a court in a slum area

BACK TO BACK




FIG. 122.—Early Nineteenth-Century Chair.
About 1806.

in an industrial town in the North of England, which shall be nameless, and the photograph was taken in February, 1933. It shows typical back - to - back houses, built perhaps 100 years ago. Back to back means that the houses are only one room deep, so at the back of the houses shown on each

side of the court in Fig. 117 comes another house stuck on to it. Each house is about 11 feet wide, and 11 feet 6 inches from front to back. There is no back garden or yard, and the only chance of light and sun is the one window on to the court. There is only one room and the staircase on each floor, and the staircase opens into each room and is not cut off by a passage. Each room may have its family (see Fig. 118), and there are others in the cellars to which the outer stairs lead down. It is only a year or so since the Thames rose very rapidly and, overflowing the Embankment, drowned many people living in cellars at Westminster, within a few hundred yards of the Houses of Parliament.

There are no conveniences in the houses—never a larder, for example. The one water-tap is shown in the court over the pails (Fig. 117), and water has to be fetched

GARDEN CITIES

from this for all the families, no matter what the weather is like. The doors on each side of the tap and pails are the closets, and there is none in the houses. The smaller door just to the right of the water-tap served for the removal of the sewage from the closets. The only sink is the channel in the paving of the court, and the dust-bins stand there to aid the general frowstiness.




Fig. 119 shows a block plan of the area, and a cross

FIG. 123.—Early Nineteenth-Century Chair.
About 1810.

marks the position of the court shown in Fig. 117. There are twenty-eight houses in the island, and including half the area of the surrounding streets that gives 127 houses to the acre. The new garden cities aim at not more than twelve. Here is an interesting point: we think the final solution of the slum problem will be found in crowding far more than 127 houses on to the acre, and for this reason. The slum dweller is such a long-tailed town mouse that if you take him into the country, where the mice have short tails, he is unhappy. He misses the noise and the excitement, and to walk along a country lane at night, without any lamps, reduces him to panic fear, especially if an owl screeches; so the transported slum-dweller wants to go back to the friendly town. Then he is so poor that he

FLATS




FIG. 124.—Chair, about 1820.

cannot afford the pence for fares to reach his work. As well, garden cities are far too expensive. Spreading the houses over such a wide area of ground means costly roads, paths, sewers, gas, water and electric light mains, and every individual house has to heat its own water, cook, and so on. Instead of spoiling the country, we think it would be better to take the trees and grass into the towns.

Don't rebuild the slums; blow them up with dynamite, then build great towers of dwellings and surround them with gardens. Let the flats have hot water and heating laid on, and all the conveniences.

A boy or girl reading this book may become a great town-planner; they may even build Jerusalem in England's green and pleasant land. It would be a great work.

Here is an instance of town life recounted to us by Mrs. George Trevelyan, who carries on the noble work of her mother in providing play centres for town children.

A grandmother, pushing a pram with a boy baby sitting in it, arrived at the Foundling Hospital one afternoon in a high state of excitement and asked if she could come in. On being told yes she explained that, having been born in the country, she had been telling her grandchild about



FIG. 125 Model Houses for the Labouring Classes, Exhibited by Prince Albert at the Exhibition of 1851.




FIG. 126 Table and Bookcase, 1851

By G. J. Meunier




FIG. 127.—Piano in Papier-mâché Case




FIG. 128. Cabinet by W. Tamer
Furniture at the Great Exhibition, 1851.



FIG. 129.—Brass Inlay in Rosewood on Top-rail of FIG. 131.

grass. Someone had told her that there was grass in the grounds of the Foundling; might the infant be allowed to sit on it? Permission being graciously given, the infant sat on the grass. This true tale sounds improbable; there are parks in London, but then they may be a mile away, and people who have the leisure to push a pram for that mile are scarce in slums. So it is possible that if the gods decide that you shall be born and bred in Fig. 117 grass remains one of the mysteries.

Though many back-to-back slum houses still remain to-day, desperate efforts are being made to clear them away. A few years ago one of the northern towns had 25,000 such houses, which they have now reduced to 2500. Unfortunately the slum represents valuable property, showing a good return on your money. So they have been acquired by people who have invested their savings in this way, or by speculators whose idea was to buy cheap and let dear, and these people represent the vested interests.

Before a slum can be cleared away the municipality has to gather all this information together and prepare a scheme for rebuilding; the Ministry of Health sends down an inspector, who holds an inquiry and hears all the evidence and objections. All this adds to cost, and sometimes the new buildings are too expensive for the old inhabitants, who just move on to another slum. It is all very difficult and complicated and hopeless; everybody wishes the slums to disappear, yet they persist.

Sir Edwin Chadwick (1800–1890) was a pioneer in the attempt to improve the conditions of the working classes. In 1832 he was appointed Assistant Commissioner for an




FIG. 130.—The Doctor's Visit, 1821. (After Cruikshank.)



FIG. 131.—Rosewood Piano of Six Octaves (1820) made by Thomas Hoskison.

(Bethnal Green Museum, London)

inquiry into the working of the Poor Laws ; in 1833 into factory life ; in 1834 was Secretary of the Poor Law Board ; in 1838 carried out investigations into the sanitary condition of London. All this led up to his "Survey into the Sanitary Conditions of the Labouring Classes of Great Britain" and the appointment of Medical Officers of Health. While Chadwick and his colleagues were making this survey "it was frequently declared by the inmates that they had never for many years witnessed the approach or presence of persons of that condition near them," and Chadwick declared that "more filth, worse physical suffering and moral disorder than Howard describes as affecting

PRINCE ALBERT




FIG. 132.—Papier-Mâché Bed. English, about 1850.
(Given to the Bethnal Green Museum, London, by H.M. Queen Mary)

the prisoners, are to be found among the cellar population of the working people of Liverpool, Manchester or Leeds.” Again, Chadwick found that in Bath in 1837 small-pox carried off 300 slum dwellers, “but scarcely one gentleman and only two or three tradesmen.”

When Chadwick died he left a large sum of money in trust for delivering lectures on the promotion of sanitary science, and these are still given.

Another pioneer in the cause was Prince Albert, the

RANGES




FIG. 133.—Roasting Range, the Pavilion, Brighton.
(Nash, Architect, 1820.)

husband of Queen Victoria, and the great-grandfather of our present King. Readers of Lytton Strachey's "Queen Victoria" will remember his appreciation of the character of the Prince Consort, and the interest which he took in science and industry, and Strachey points out the great

FURNITURE

difficulties which the Prince encountered when he first suggested the idea of a Great Exhibition to be held in London in 1851; how these were overcome and the idea turned into a triumphant success. The interest to us at the moment is that the Prince's own exhibit was the model houses for the labouring classes, of which we show the original engraving in Fig. 125, built near the south entrance to the Exhibition. The model house consisted of four dwellings—two up and two downstairs. Each dwelling contained a general sitting-room and kitchen, two small bedrooms (one for boys, and the other girls) and a large bedroom for the parents and babies, a scullery and a decent water-closet. All the rooms had cupboards, the building was fireproof, and each had its own water supply. The Prince was assisted by Mr. Roberts, the architect. The cost was estimated at £440 to £480 for the block of four, and the rental at 3*s.* 6*d.* to 4*s.* a week each.

After the Exhibition a similar block was built at the entrance to Kennington Park, in South London, and can still be seen there. Strachey in his book raises the interesting point of what might have happened in England if the Prince had not been cut off in his prime. This patient German, with his high sense of duty and his love for orderliness, gaining in experience and reputation as the years passed, might have come to such a position of authority that he would have been able to overcome the inertia and lack of planning which is so noticeable a characteristic of the Englishman. Had the Consort lived the cellar dwellings of Fig. 117 might not have disgraced us at the present day.

FURNITURE.—We can now leave slums and consider the furniture of the early nineteenth century, which hitherto has received scant attention. It cannot of course compare with the eighteenth-century masterpieces of Chippendale, Hepplewhite and Sheraton; still it has a great interest of its own and was well made.

Take the family party scene of 1806 shown in Fig. 120;

CHAIRS

the polished steel grate and marble mantelpiece are quite simple and nice, and the glass over has Sphinx heads on its pilasters, with an admixture of Greek ornament. Napoleon's campaign in Egypt had advertised




FIG. 134.—Thomas Robinson's Range (1780).

that country, and the sphinx became a popular decorative feature; you can see it again in the patterned borders on the walls. The chairs and sofa in Fig. 120 are in black with gold lines, and these colours are repeated in the carpet.

Another chair of the same type is shown in Fig. 122; again black and gold is used, but with little added red touches. It is a little bit too architectural for a chair, which should be so suave in its lines that it looks as if it had been shaped and not built. Figs. 123 and 124 are amusing examples of what we call "cow-hocked" chairs—that is, the type where the hind legs incline together at the back and are not so wide across the bottom as they are at the top. By the way, when drawing a chair see if this is so, because it adds complications to a difficult subject. Both these chairs were made in beech grained to look like rosewood, which was now the fashionable wood.

Fig. 129 shows the brass inlay in the top rail of Fig. 124, with a Greek flavour in the design.

Brass inlays again appear on the rosewood piano (Fig. 131). The veneered borders with the grain of the wood applied crossways are pleasant, and the whole design is a successful treatment of a difficult subject. The bedroom in Fig. 130 is quite a homely room. Fig. 132 shows a bed which is an amazing piece of work. In the 'forties a fashion sprang up of japanned papier mâché, and



FIG. 135.—Early Nineteenth-Century Carron Range.

generally with a black ground on which were painted vividly-coloured flowers, and to heighten the general gaiety of the effect mother-of-pearl was inlaid as well. This treatment was applied to tea-trays, chairs and, as we have seen, beds. Fig. 132 must be seen to be believed, and fortunately this is possible by going to the Bethnal Green Museum. The canopy at the back is 8 feet high, and the fringe at the top is in green wool, and the cords and tassels in green and gold. The rep curtains are green bordered with green and gold. The bed is 6 feet 10 inches long and 4 feet 8 inches wide.

With this bed we come to an end of the history of English furniture. Chairs, tables and the rest of the household gear have been made and used since, but they are in a different category altogether. Made before 1851, as they approach old age they are felt to have earned a certain reverence, and so can be cherished as antiques ;

COOKING




FIG. 136.—The Bodley Range, A.D. 1802.

after 1851, and even before their coverings have been worn out, they become second-hand and are mocked at in the sale-rooms, and pass to the lodging-houses and apartments.

Figs. 126-128 show some of the furniture which was exhibited at the Great Exhibition of 1851, and so that there may be no deception we have reproduced the original engravings. What can be said for it? It carries on no tradition, but jumbles up all the styles. The Exhibition was a glorification of the machine, and the furniture was thrown in. In the same way the people who bought it and used it in their homes had been so busy acquiring wealth by the use of the machine that they had little time left for anything else. Their furniture had to have an atmosphere of richness about it and look as if the host of the party were really and truly affluent—not much else mattered.

COOKING.—To study this subject in a really regal way we will return to the Pavilion at Brighton, which we have already illustrated in Figs. 1 and 115.

Between the banqueting room (Fig. 1) and the kitchen

KITCHENS

comes the table deckers' room, and its nice name explains its use.

The kitchen in the Pavilion is a fine place, 42 feet by 38 feet, with a lantern light in the ceiling supported by four iron columns disguised as palm trees, and provided with copper leaves at the top. On one side comes the great roasting range, as Fig. 133. This has a beautiful copper canopy over it to carry off the steam and smells into a flue in the chimney. There are other canopies as well over the marble pastry-making slabs at the sides, with dutch tiles at the back. The joints or birds to be roasted were put on to the spits as shown, and these, being placed in the grooves on the hinged arms, were turned by chains passing round pulley-wheels on the ends of the spits; the chains at the upper ends passed over wooden pulley-wheels which are attached to the horizontal spindle, turned by bevel gears from a smoke vane in the chimney. This was, or still is, turned by the rising heat of the flue. On the other side of the kitchen is a hot plate. This has a furnace at one end, and a flue passes from this horizontally under the hot plate until it is taken up vertically in the wall behind, and here dampers are arranged to regulate the draught. Providing the vertical flue was high enough, sufficient draught would be made to draw the fire and heat along under the hot plate. This hot plate has every appearance of being as old as the range, and saucepans would have been heated over circular holes in the hot plate for making sauces. There are coppers in the adjoining vegetable kitchen, with the original covers engraved "P. R.," for the Prince Regent. The oven, or ovens, have disappeared in alterations which have been carried out in this part of the building, and this is a pity, as we should have been able to find out whether the Regent had introduced one of the new kitchen ranges which were being used at this time. There would certainly have been a brick oven for bread, but a range would have made a useful addition.

The earliest description of a range we have come across

ICE HOUSES




FIG. 137.—An Ice House.

is the specification of the range patented by Thomas Robinson on October 21st, 1780. This says: "One side of the fire is the oven, and the other side is made to wind up with a cheek. The top bar in front is made to fall down occasionally to a level with the second bar. The moving cheek is made with a socket in it to receive a swinging trivet. The oven is made of cast iron, nearly square in front, the door hung with hinges and fastened with a handle and a turnbuckle, and the oven is provided with fillets for the shelves to rest upon. The oven must be enclosed with bricks and mortar." The old roasting ranges, as Fig. 133, had the cheeks which could be wound up to reduce the size of the fire, so what Robinson did was to add the oven at the side, which made the fitting much more useful and suitable for the smaller houses which were springing up in the suburbs of London and the industrial towns. We show this range in Fig. 134.

The Robinson range developed into the nineteenth-century open range, with a boiler added on the opposite

FOG

side to the oven, as Fig. 135. The setting of the oven was improved. In the Robinson range, Fig. 134, this was just set on brickwork, and the fire came against one side. In Fig. 135 the oven inside had a circular back, and in setting it the bottom of the oven was kept level with the fire bars, and a space was left under for hot air. A space was left as well on the left side and back of the oven into which this heated air could pass up from the bottom space out of the grating at A, Fig. 135. The oven was heated by the fire on its right-hand side, and conducting plates were cast on this to assist the passage of the hot air around the oven.

The range of bars to hold the fire had a sliding cheek to reduce its size, and a trivet to take the kettle. The boiler was returned around the back to get part of it near the fire ; it had to be filled by hand, and if this was forgotten then the boiler burnt out and was useless. Notwithstanding the hot-air chamber around the oven, it got much hotter on one side than the other, and to get over this its shelf was made to turn on a pivot, so that the food to be cooked could be turned to the heat. It was this open range which devoured coals and poured out the smoke that made the nineteenth-century London fogs. Fortunately for us we are beginning to forget what these were like. The late Sir Frederick Treves, a distinguished doctor of those days, estimated that in a fog in London a square mile of air contained 6 tons of soot, and killed people "not by scores and hundreds, but by thousands"; as well that "the lungs of an adult dweller in big cities are dingy thunder-cloud blue in colour, due absolutely to dirt and soot in the atmosphere." Fig. 135 was one of the principal causes of all this.

The next step seems to have come about by trying to combine an oven with the hot plate ; the latter had shown that you could conduct heat in horizontal flues if you had a sufficiently high vertical chimney to create a draught. This is what the Bodley Range, as Fig. 136, which was

OVENS

patented on February 27th, 1802, aimed at. This seems to have been the first range or kitchener with a closed top. The fire was open in front, and could be used for roasting. The oven appears to have a fire-brick between it and the fire, so there was less danger of scorching, but the flue on the other three sides of the oven led to more equal heating. Still there was no provision as yet for diverting the oven heat so that this could come from the top for cooking meat, and the bottom for pastry. The flue, however, not only heated the oven, but the hot plate over it, so that the top of the range could be used for boiling. To do all this the fire-box had to be kept full up, and the coal consumption was as much as twelve to fifteen scuttles a day. All the kitcheners seem to have descended from the Bodley range.

It was Count Rumford (1753-1814) who invented the water-jacketed roasting pan, which kept down the temperature of the fat under the joint in the oven and so prevented it from spluttering over and being burnt, with unpleasant and smelly results. Rumford as well has a "roaster" to his credit; this consisted of an oven in the form of a cylinder placed within another, the space between the two being the flue, with the furnace at the bottom and the chimney at the top. The roaster appears to have been a scientific toy which, though it pointed the way, did not come into general use.

Passing from heat to cold, Fig. 137 shows how ice was provided for cooling drinks and making ices in the early nineteenth century. The example shown still remains, and will remain until man or an earthquake destroys it, in the park of Ashridge, Herts, which we illustrate in Fig. 107, and it appears to be of the same date as the house (1806-13). This ice house is one more illustration of the cleverness with which the old people got over their difficulties, and the self-help which they practised. They could not make ice, so in the winter they cut it off the ponds and lakes and stored it underground as shown—first a layer of straw,

LIGHTING

then one of ice, and so on. Buried in the deep blackness of the vault, cut off from the outer air by the three doors in the entrance passage, and further insulated by being buried underground, the ice kept itself frozen until it was wanted in the summer. Please notice the ingenious arrangement by which, with sloping doors, a pulley-wheel was arranged in the brick vault of the passage, so that it could be used to haul up and lower ice in the ice house itself. While we were measuring in the passage one of the authors was nosing about with the one electric torch, and became interested in various stalactite forms on the ceiling; the other author, prone on tummy, with head over the edge, was attempting to judge the depth of vault by dropping pebbles into it, when the first, discovering that the stalactites were really bats, fled shrieking with the light and, banging the outer door to keep the bats in, left the second in velvet-black darkness. All this to sound a note of warning: when measuring an ice house take a bat-lover for an assistant.

LIGHTING.—In country houses people still had to depend on candles for lighting the reception rooms, with all the trouble of snuffing the candles and cleaning the candlesticks. Lamps of the cruzie type, as shown in Fig. 30, were used in the kitchen and offices, and burning as they did animal and fish oils, or the contents of the frying-pan after the frying, they must have been smelly contraptions. Good colza oil lamps seem to have come in about 1836, and paraffin was first used for lighting about 1853. Boulton and Watt were the first to use gas to illuminate their works in 1803, and by 1810 it was being used for lighting the streets. There is a good tale told that when it was installed in the House of Commons members were seen going round feeling the pipes to see if they were hot. They were afraid the flame continued down the pipes.

GAS COOKING.—We cannot discover when gas cooking was first introduced, but gas cookers were exhibited at the 1851 Exhibition.

DATING BUILDINGS

And now, having come to the end of the space allotted for early nineteenth-century building and furnishing, may we make a suggestion? If our readers will familiarize themselves with the general characteristics of buildings so that they can date them, they can then apply such knowledge to the town or district in which they live. There may be an old castle, as in Fig. 3, with the remains of the township which grew up around it in the Middle Ages. The mills may be there which were mentioned in Domesday, and a school of 1541 show the Tudor interest in education. Almost certainly there will be pleasant Stuart and Georgian houses, and Regency ones like those we have illustrated in this book. Industrial and Suburban developments can be noted, and the nearest Grid lines will bring the survey up to date.

In this way the town will come to life and form the background of history, because history can be shown by bricks and mortar, as well as found in the printed pages of books.



Lady with child and cradle.

By Henry Moses, 1825

CHAPTER VIII

NINETEENTH-CENTURY CLOTHING

THE clothing trade was destined to be one of the chief instruments of the commercial expansion of the nineteenth century. Great industrial centres were to spring up in Lancashire and Yorkshire, and the materials woven on the looms there were sent all over the world. These were paid for either by the importation of raw materials or foodstuffs for the population of the industrial towns.

There was nothing very revolutionary about the period, and the inventors contented themselves with perfecting the ideas of Kay, Hargreaves, Arkwright, Crompton and Cartwright, of whom we wrote in Chapter III. Improvements were made in detail, and one of the most important of these was the introduction of the Jacquard apparatus, which made the weaving of elaborate patterns very much simpler than it had been.

If we turn back to Fig. 47, of the hand loom, we shall find that patterns were possible by introducing colours in the weft. If a black thread were used, for example, and this was passed under and over the warp threads, like darning, you got a pattern, and this could be varied by going under three and over one, and so on. This was, and still is, the only way to achieve pattern, the interlacing of different coloured threads. In all textile designing the patterns should be built up on squares representing crossing threads.

We saw how in Fig. 47 the warp threads were lifted or lowered so that the shuttle could be passed through the shed by being attached to loops in the healds, and how




FIG. 138.—Power Loom (1851)
(Science Museum, London)




FIG. 139.—Original Singer Sewing Machine
(1854).
(Science Museum, London)




FIG. 140.—Spinning, Reeling and Boiling the Yarn in Northern Ireland, 1791

B. W. Hoare.




FIG. 141.—Power Loom Weaving, c. 1835.

By Sir E. Baines

JACQUARD




FIG. 142.—Upsetting the Charlies, 1821.

these were operated by being connected to treadles. So complicated patterns meant more healds and more treadles, and the work was consequently very skilled. This did not suit nineteenth-century ideas at all; they wanted mass production. The Jacquard apparatus was a step in this direction. Figs. 51 and 148 explain this.

Jacquard seems to have made a commercial success in France, in 1804, of inventions of Falcon in 1728, and Vaucanson in 1745, and it was introduced into this country early in the nineteenth century. Fig. 148 explains the principle. The Jacquard apparatus could be applied to the hand-loom where it was retained, or used in conjunction with the power loom.

On p. 72 we described how the power loom was invented by Cartwright in 1785. This was improved in detail, not principle, and Fig. 138 shows how far the designers had got by 1851. At first sight it appears a very complicated bit of machinery, but after a little study it will be found to be only a mechanical version of Fig. 47. The machine, competing against the human hand, asks for and has to take endless trouble. We explain the mechanical principle in Fig. 149.

LOOM

Comparing Fig. 138 with the hand loom, Fig. 47, and Kay's flying shuttle, Fig. 53, we can see how the various parts of these were incorporated in the power loom. On Fig. 138, starting from the back, the warp threads can be seen at A, the healds at B, and heald shafts at C; the batten is seen at D, with the reed at E, and the shed at F, with the shuttle just entering it. G shows the picker, which




FIG. 143.—Boxing. (After Cruikshank.)




FIG. 144.—Fencing. (After Cruikshank.)



FIG. 145.—Fly-Fishing in 1831. (After James Pollard.)
(The Gade, Water End, Herts.)



FIG. 146.—The Dance.
(After Cruikshank.)

throws the shuttle out of its box through the shed by means of the picking stick H and strap connections, and the cloth when woven passes on to the cloth beam I. The principle is just the same as the hand loom plus Kay's shuttle. For pattern work a Jacquard apparatus was fixed over this.

SEWING MACHINES.

—It was not to be expected that sewing—one of the oldest of the arts—would escape the attention of the inventors. The history of sewing goes back into the remotest antiquity. There is, in a case on the left-hand gallery as you enter,

in the Prehistoric Room at the British Museum a small cardboard box, the contents of which we illustrated in Fig. 54 of our book on the Old Stone Age. It contains the apparatus for making the bone needles which men then used for sewing skins together. First an awl was made which punched a hole through which the sinew could be passed; next came a kind of crotchet needle, which pulled it through, and then a needle with a pierced eye through which the sinew could be threaded; the needle started life then as an awl, and the principle of sewing was established in Solutrean times. Steel needles were probably




FIG. 147.—The Quadrille, 1821. (After Cruikshank).

POWER LOOM




FIG. 148.—The Mechanical Principle of the Jacquard Apparatus.

introduced into England in the sixteenth century, and with them most beautiful work was done at the rate of about thirty stitches a minute. The inventors thought this was much too slow, and at the end of the eighteenth




FIG. 149.—The Mechanical Principle of the Power Loom on Fig. 138.

TEXTILES

century they got to work. Elias Howe, in 1845, designed the first lock-stitch machine using a threaded needle and shuttle. If you take your mother's machine (with her permission) and turn it by hand very slowly you will find that the needle pauses in its stroke, which causes a loop to form in the cotton, and the threaded shuttle goes through this, and then the needle pursues its course and pulls the thread tight.



FIG 150.—Pelisse, Mantelet, 1803.

It was in 1851 that I. M. Singer patented his first sewing machine, which is now at the Science Museum, London, and which we illustrate in Fig. 139. It is still in working order, and if any of our readers go to the Museum we suggest that they ask Mr. E. J. Taylor, the chief attendant in the Textile Gallery, to open the case so that the noise of this early machine can be properly appreciated; at the same time Mr. Taylor might be persuaded to give a demonstration on the power loom (Fig. 138). Here we should like to return thanks to him for his kind assistance in elucidating the mysteries of his textile machinery.

DRESS.—We can now turn to the dress which was made of the materials woven on the looms and find out how it reflected the spirit of the times, and this is at once



FIG. 151.—The Tailor, 1821.
(After Cruikshank.)

apparent. At the very end of the eighteenth century, when "Romantic" houses like Ashridge were being built, as Fig. 107, the people had to have "Romantic" clothes. The women wore large hats, with flowing curls, and loose frills at the neck. And here is an interesting point which mystifies one author, but is quite feasible to the other. One would have imagined that the position of women's waists was settled when women were designed; but this was not the case in the

nineteenth century; sometimes waists went up, sometimes they went down. As the dress became less formal the waist-line rose, heels were flatter, and less stiff silk and more muslin, calico and chintz was worn. Fine embroidery, though, was used to decorate the materials.

Between 1804 and 1808 a modified classical dress was worn, and the waist-line rose to under the arms (see the first lady in Fig. 155). The hair was cut short and dressed in small ringlets, or frizzed, or worn with a straight fringe on the forehead. Sometimes real flowers were worn in the hair, and the bonnets were modelled on Grecian helmets.

In the eighteenth century pockets were worn under the skirts, outside the petticoats; in the beginning of the nineteenth, women carried bags which they called

HAIR-DRESSING

"indispensables." Parasols, sometimes hinged, as Fig. 155, had been carried since the last quarter of the eighteenth century. The poke bonnet seems to have developed from the helmet shape; it was small in 1815, enormous by 1827, and survived until 1860. Hats also were very large and over-trimmed in 1828, and were parodied by Cruikshank, together with tiny waists (see second lady, Fig. 155).



FIG. 152.—Walking Dress, 1821.

From about 1808 the waist-line (in women) gradually dropped, until in 1820 to 1830 it had reached the lowest level, but it was very tight, and the skirts very full.

We must confess that we are very interested in this waist-line problem. What did it reflect? Was it economical, political or psychological? Here is a subject beyond two poor artists and far more suitable for the real scholar.



FIG. 153.—The Riders, 1821.

Hair had become long again by 1821, and was worn high with fantastic bows and curls. High tortoise-shell combs can be noted in 1830 fashion plates. In 1836 hair was plaited in wickerwork fashion on the crown of the head and flowers inserted for the evening. Sleeves to the wrist had been worn for day wear since 1804, and they grew larger as the waist-line

CRINOLINE



FIG. 154.—Young Man, 1821.
(After Cruikshank.)

dropped, and became enormous in 1830. By 1841 they were tight again in the upper arm; the bodice was pointed, the waist still small, and the skirt full.

In 1845 the hair was worn with a simple middle parting and side bunches of curls, as third lady, Fig. 155. Shoes throughout the first half of the century were of thin leather, often of slipper shape, with little if anything which would be called a heel to-day.

The full skirt question is important. If you go to the museums and study the early nineteenth-century dresses you will find that they are all on the small side. The women were tiny, and that was all right

when they were young and fairy-like, but it was all wrong when they became middle-aged and portly. We regret to have to use the latter word, but in the cause of historical research it must be employed. The full skirt remained until 1854, when it became fuller still by the use of the crinoline introduced from Paris. Made first of stiff horse-hair and then of steel hoops, it was spoken of as a hygienic contrivance which enabled the skirt to be so large that the waist, by comparison, seemed small, and that without the undue compression which had been used till then. It was




Fig. 155.—Costume in the First Half of the Nineteenth Century.

a contrivance which brought comfort to the middle-aged and kept them in the fashion, and as the young girl can wear anything and look nice, everybody was happy. To sum up, you can say that simplicity was the keynote of the early part of the century, with extravagance at the end of the Regent's time, regaining a measure of simplicity by 1850 under good Queen Victoria. The three groups



in Fig. 155 show these three periods. FIG. 156.—The Parson and His Wife, 1821.
(After Cruikshank.)

So far as men were concerned, their waist-line does not seem to have troubled them. In the late eighteenth century knee-breeches had descended to mid-calf for daily use, and shoes were tied instead of buckled, and by 1816 pantaloons of stockinette to ankle, with black silk socks and pumps, were worn for the evening. The broad-brimmed Napoleonic hats took the place of the three-cornered ones, and in the early nineteenth century the crowns of these rose and, though varying in shape, the top-hat arrived. Men wore their own hair, cut short, and their faces were clean-shaven. Their collars stood up on each side of their faces, and they wore black cravats.

In 1825 broadcloth great-coats were used for travelling, without capes, and in this year Charles Macintosh introduced waterproofing, and soon after mackintoshes came into use for wet weather. By 1825 breeches had become

WHISKERS



FIG. 157.—Riding Dress, 1832.

trousers, fastened with straps under the instep, and by 1830 black ones were worn in the evening, though knee breeches and *chapeau bras* continued in use for Court and the opera.

By 1830 the tops of men's sleeves were very full, and gathered and pleated at the armhole. The coat, with high collar and spreading lapels, was worn well open to show the satin

waistcoat, tight at the waist, over wide-topped trousers, diminishing down to small ankles, as first man in Fig. 155. The coats were usually of coloured cloth, cut away with tails, and the trousers of white or coloured nankeen. Low shoes were worn until 1825, with riding boots to the knee for walking.

By 1841 the cravats were still dark, and covered the shirt front and collar, with a white slip between cravat and waistcoat, as second man, Fig. 155.


Whiskers began to be worn, and by 1855 moustaches were allowed to grow. These, the sign of ferocity, had hitherto been regarded as a privilege of the military. Trousers became tight, and sleeves as well. The skirted frock-coat was usual, although these,



FIG. 158.—Dressing-Gown, 1839.

BETHNAL GREEN

with military frogging, had been worn as early as 1825; the coat had a stand-up collar. We should like to give our readers another reminder here, that fine collections of early nineteenth-century clothes can be seen at the Victoria and Albert, the Bethnal Green, the Geffrye and the London Museums, in London.



A Card Party.

By Henry Moses, 1825

CHAPTER IX

THE SUBSIDIARY TRADES

TRANSPORT was certainly the most important of the subsidiary trades in England in the nineteenth century. It was to alter the face of the countryside and impinge on its life in a hundred different ways. At the beginning of the century the roads were coming into their own once more ; then these were to be forgotten and again have a later renaissance when the motor-car came along. Roads are pleasant things, and what more delightful occupation is there on a winter's evening than to take out your maps and trace one's journeys on the roads of England ? And they vary—the Roman road, which thrusts its purposeful way over the countryside, and the winding lanes between the villages, which started as the tracks between the common fields.

There is no greater tribute to the Roman genius than the road system which the Romans laid out when they came to Britain, and which we still use. Imagine the difficulties of foreseeing exactly the line on which trade and inter-town communication would follow, to look ahead nearly 2000 years. The Romans were great planners.

We have seen in what state Celia Fiennes found the roads in the seventeenth century. They were improved by the Turnpike Trusts of the eighteenth century, and then at the end of the eighteenth and the beginning of the nineteenth Macadam and Telford got to work. They dug down to the foundations of the Roman roads, cleared out the pot-holes and brought the main roads into fine condition, so that the mail-coaches could run at an average and unheard of speed of eight miles an hour, with bursts of eleven to twelve.



FIG. 150 —A small Merry-go-round in a Village, c. 1810.

B. W. H. P. sc.



FIG. 160 - Children dancing in the grounds of a Country House,
c. 1820.



FIG. 161 The Smithfield Horse Show, c. 1825

This weekly market is mentioned by FitzStephen in the twelfth century, so had been held regularly for 200 years.




FIG 162.—Royal Mail Coach (1820) at the Science Museum, London.

MACADAM

But the good macadam road was a very different thing from those we have now. Boys and girls who read this book will hardly remember the roads which were general when their parents were young. The surface was worn off by the iron tyres of the wheels—because rubber was not used as it is now—and laid on the top of the road in a good solid layer of dust. By May all the hedgerows along the roads were white; if you bicycled in breeches and stockings there was a pattern of dirt on your legs where the dust had blown through. The first motors raced along and left behind them uncurling serpentine clouds of dust, and the people you passed by fled or, holding handkerchiefs over their noses, glared at you with their eyes. The horse is the only sufferer by the tarred roads, and we have forgotten what dust and mud can be like.

The bridge-builders continued their work, and the Menai Bridge was designed by Thomas Telford in 1819, and opened in 1826. The engineers could have had very little data to guide them as to the stresses set up by a living load, but they were plucky and inspired and achieved the factors of safety. This is especially true of some of the earliest railway viaducts—nobody had ever run a train over a bridge before (Fig. 73).

VEHICLES.—When we come to vehicles pride of place must be given to the Mail Coach (Fig. 32), and Fig. 162 shows an actual example which can be seen at the Science Museum, in London. This dates from about 1820, or the heyday of coaching. The front wheels are 38 inches diameter, back wheels 48 inches, with a wheel-base of 6 feet 6 inches. The under-framing is much the same as the timber carriage, Fig. 98, with a pole or perch between the front and back axles. On this under-carriage the coach body is fixed by springs. The coach carried four persons inside, the driver and one passenger beside him, and four others on the seat behind, with the guard over the boot with his blunderbuss just in front of him



FIG. 103 — Steam Omnibus, Coach and Waggon, c. 1835.




FIG. 104 — Gurney's Steam Coach, London to Bath, c. 1835.



FIG. 105. Early Train drawn by the primitive "Novelty" Locomotive, with Omnibus and owners' Coaches.




FIG. 106.—The "North Star" and Train of early Carriages.



FIG. 107.—Steam Omnibus, Edinburgh to Leith, c. 1860.

TOM BROWN

for the highwaymen. The coach was drawn by four horses.

The best description we know of a coach ride is the one in "Tom Brown's Schooldays," which, though it was published in 1857, deals with the period when Tom first went to Rugby, about 1837—that is, just at the end of the great coaching period, when the railways were beginning to drive the coaches off the road. Tom comes up from the Vale the day before with his father, and they stay the night at the Peacock Inn, Islington, so as to catch the Tally-ho for Leicester. Tom has beef-steak with oyster sauce for supper, and drinks brown stout. As the coach leaves Islington at 3 a.m., Tom is called at 2.30, and has a three-hours' drive, on the top, before dawn. Just as we have forgotten dust, we cannot remember now how cold it could be driving in an open carriage. But the Tally-ho is a tip-top goer and averages ten miles an hour, and Tom experiences the thrill, which we all do, of driving along at night when the world is asleep. Then the dawn comes, and the world wakes up and the road comes to life, and appetite as well, but this is stayed by a twenty-minutes' halt at an inn famous for its breakfasts. Pigeon pie, ham, cold boiled beef, kidneys, steak, bacon and eggs, buttered toast and muffins is the fare offered to Tom.

Fig. 168 shows the first omnibus introduced into England by G. Shillibeer, a coach-builder. Two started to run on July 4th, 1829, between Paddington and the Bank, in London, and the fare was 1s. Each omnibus carried twenty-two passengers inside and was drawn by three horses.

This led to the introduction of a steam omnibus. In *The Times* of April 25th, 1833, an account was given of one that started running then from Paddington to the Bank. It was stated that "there can be no possibility of explosion," and "the guide, who sits in front, has complete control, and can arrest its progress instantaneously." Starting at six miles an hour, when it cleared the crowd

OMNIBUS




FIG. 168.—Shillibeer's Omnibus, 1829.
(Model in Science Museum, London)

“the velocity was increased to the rate of ten miles an hour.” The authorities, however, refused to license “the Enterprise Steam Coach,” so it died the death. This was built by Hancock, but Gurney designed one to run between London and Bath (Fig. 164). We wonder if the varied steam vehicles of Fig. 163 ever ran.

We illustrated a post-chaise, perch-phaeton and a gig in Vol. II., and the two first, with the Victorian landau, were suspended by springs over an under-framing like the timber carriage. It was the brougham, as Fig. 170, which introduced the new principle of building a rigid body and attaching the springs and wheels to this, without the connecting pole or perch. The specimen at the Science Museum is the original built for Lord Chancellor Brougham by Messrs. Robinson and Cook in 1838. It created a great sensation then and remained in use until the motor-car age.

Joseph Hansom, the architect, designed his cab in 1834, but this did not resemble the hansom which became very popular during the nineteenth century.



FIG. 166. Market Day outside the Old "Red Lion" at Greenwich.

By Francis Reynolds.

LOCOMOTIVES

Unfortunately we can only deal with beginnings, but space must be found for the hobby horse, as Fig. 176, introduced into England from France in 1818, when it was described as a "Pedestrian Curricule." Hobby horses became all the rage, and there are old prints of the period showing the schools where you could learn to ride them. Round and round the riders go before their admiring friends, and some of the greatly daring ones actually lift both legs off the ground, and so experience the thrill of balancing in a spread-eagled fashion. This discovery that it was possible to balance yourself and progress on two wheels led to the early bicycle of 1839, as Fig. 177. This was designed by Kirkpatrick Macmillan, a blacksmith of Courthill, Dumfriesshire, and the propulsion by treadles and cranks is very ingenious. It was really in advance of the "boneshaker" of 1868, but, on the other hand, you could not have turned at all sharply without fouling your feet against the wheel. Probably to go straight ahead was quite thrilling enough. Any readers who are interested should go to the Science Museum, where there is a fine collection of early cycles, all dated, so that their development can be traced.

RAILWAY LOCOMOTIVES.—Actually there were railways long before there were locomotives. A print of 1754 shows stone from the quarries at Bath being transported in low trucks whose wheels run on rails. This was long before man invented the locomotive, which derived its name from *locus*, place, and *motio*, motion, because it performed the miracle of moving itself from place to place. Hitherto man had never been able to make anything which moved itself. His ships depended on the wind, and his coaches on the horse. Watt's steam engine puffed and grunted but stayed put, which was perhaps just as well.

Puffing Billys and the Rockets of a little later must have been bad to meet on the road, but imagination refuses to conceive what a Watt's locomotive would have been like. We often watch the behemoth at the Science

TREVITHICK




FIG. 170.—The Original Brougham (1838).
(*Science Museum, London*)

Museum in action ; the great beams rock, the gears grind round, and it really does puff and grunt. Originally working at a very low pressure of 4 or 5 lb. per square inch, owing to the risk of explosion with the badly-made boilers of the time, it is not at all lively (Fig. 171).

It was Richard Trevithick (1771–1833) who altered all this by introducing a boiler which worked to a pressure of over 100 lb., and once this was done movement was suggested. Trevithick, who was the son of a Cornish mine manager, was born at Camborne, in Cornwall, so that during his boyhood he was to be much in touch with things mechanical. In 1797, when he was twenty-six, he had made the model of a road locomotive which can be seen at the Science Museum, London, and we illustrate this in Fig. 172. That it is only a model makes no difference to the fact that it was and is a locomotive possessing the power to move itself. True it only ran around Trevithick's table, but that does not matter ; imagine what your own feelings would have been had you been Trevithick.

The next step was the completion, on Christmas Eve,




FIG. 171 —Boulton and Watt's Rotative Engine (1797).

(Science Museum, London.)




FIG. 172 —Trevithick's Road Locomotive

Model, c. 1800

(Science Museum, London.)




FIG. 173.—Davidson's, 1842, the first to run on a railway.




FIG. 174.—Farmer's Model Electric Train, 1847, from the inventor's reconstruction for the Chicago Fair, 1893.




FIG. 175.—Cotton's Electro-magnetic Locomotive, 1846.
Early Electro-magnetic Locomotives.

CATCH-ME-WHO-CAN

1801, of a steam carriage to run on the roads, and the Dictionary of National Biography says that this carriage conveyed the first load of passengers ever moved by the force of steam. We should say that this was rather a risky statement. Cugnot had experimented with a traction engine in 1770, and a model of his machine is preserved at the Conservatoire des Arts et Métiers, Paris. There is another model of Murdoch's locomotive in the Birmingham Art Gallery; this dates from 1781-86, and Oliver Evans's was at work in Philadelphia.

Whether these moved passengers or not we do not know, but Trevithick's did, and was known as the "Puffing Devil"; unfortunately it was burnt out while Trevithick and his friends were in an inn celebrating the success of this first run. 1803 saw another steam carriage, and then in February, 1804, Trevithick produced the first railway locomotive. This hauled 10 tons of iron and seventy men, in five waggons, at nearly five miles an hour for nine and a half miles over the rails used by the horse trams in the mines at Penydarran, near Merthyr Tydvil, South Wales.

Trevithick must have been possessed of humour, because in 1808 he brought a new locomotive to London, hired some land near Euston, put up a circular track and fenced it in, and charged 1s. a head for joy-rides at fifteen miles an hour (see Fig. 178).

The engine was called "Catch-me-who-can" and was backed to beat any horse running at Newmarket.

It will be well for any young Trevithick who may read these pages to take stock of the state of affairs which is revealed by the recital of achievement and dates which we have given above. Had the people had eyes to see, from the very moment at which Trevithick made his little model run round the table they might have foreseen the possibilities of his invention; had they had imagination they might have realized the enormous importance of the invention and the changes it was to make, not only in running around our little island, but in crossing the

HOBBY HORSE




FIG. 176.—The Hobby Horse (1818).
(*Science Museum, London*)

continents of the Old and New Worlds. This iron horse was destined to drive all the other horses off the road. Surveyors had to go before it, spy out the land, scheme the gradients and make ready the way. The descendants of the navvies who had made the canals had a bigger task than their forebears and followed on the trail to dig and embank, and when the rails could not be taken over the mountains they had to tunnel through them. The engineers made the bridges, the iron-founders the rails, the builders the stations. New towns were to arise, and old ones which were passed by dwindled away. Man could peddle his goods over a continually expanding area, and trade and industry were to be revolutionized. The very character of the country was altered because men lost the road sense, and towns became a congeries of houses grouped around railway stations. All this was hidden from the riders in "Catch-me-who-can."




FIG. 177 —Trevithick's 'Catch-me-who-can' on the Site of Euston Square, London (1806).

By Thomas Rowlandson.




FIG. 178 —A G.W.R. Locomotive, c. 1845, of the earlier Broad Gauge Type, which ran (with eight wheels) till 1892.

By J. C. Bourne.




FIG. 179. A Train of Farm Animals near Bath, c. 1840

STEPHENSON

Trevithick seems to have exercised his inventive genius as well on steam-boats, dredgers and threshers. Any problem attracted him, and then about 1816 he went to Peru, made a fortune there, lost it in a revolution, and came back some years later to find that others had benefited by his work. Blenkinsop and Hedley had followed in his tracks with colliery locomotives, and then George Stephenson (1781-1848) appeared on the scene. He had been appointed engine-wright at the Killingworth Colliery in 1812, and began his experiments in 1813, and completed his first engine in 1814. This work led to him being appointed, in 1822, engineer to the Stockton and Darlington Railway, which had started the year before and was the first public steam railway to be made in the world; but it was only employed for carrying goods. A new Act of Parliament was obtained in 1823, authorizing the railway to carry passengers as well, but railways as we understand them had not yet come into being. The Liverpool and Manchester Railway was authorized in 1826, and when it was approaching completion in 1829 the directors, wishing to be quite sure that they were on the right side, appointed Messrs. Rastrick and Walker to visit all existing railways and report on the respective merits of locomotives or stationary engines drawing the trains by cables! Their report was rather in favour of the latter method of traction. The directors, however, very wisely determined to have a competition, and offered a prize of £500 for the best locomotive, and this led to the Rainhill trials, nine miles from Liverpool, on October 6th, 1829, at which the "Rocket" won the prize, and the "also rans" were the "Novelty," "Sans Pareil" and others. The locomotive had at last come into its own, thirty-two years since Trevithick's little model, Fig. 172, had run round the table and settled the principles. The world went railway mad. The "Best Friend" made its first trip in the U.S.A. on January 15th, 1831.

To return to the subject of our sketch, Trevithick on

BICYCLE




FIG. 180.—Macmillan Bicycle (1839).
(*Science Museum, London*)

his return was not able to take his place again. Whether he had lost courage or the spark of his genius had died out we cannot say, but he died in poverty and was buried in a grave for poor persons at the parish church of Dartford, in Kent, in 1833. He does not seem to have been esteemed in his own time, but the wheel has turned full circle and in 1933 the centenary of his death was commemorated by an exhibition of his work at the Science Museum in London, and the Bishop of Rochester conducted a memorial service at the Dartford church where he lies buried. Hence our warning to young Trevithicks of to-day: it takes time to knock ideas into the heads of Englishmen; the inventors may not be esteemed, and somebody else will make the money, but the wheel turns, and in a hundred years you are honoured and bishops praise you as a famous man.

But what is still more pleasant is that the celebrations of his fellow-countrymen were forestalled by the action of




FIG. 127. View of Whampoa, Canton River, China, showing on the right the East Indiaman *Helderloo*, of 1,315 tons, built in 1816 and broken up in 1834.

STEAMBOATS

two American gentlemen, F. R. Low, the President of the American Society of Mechanical Engineers, New York, and the Editor of *Power*, and R. C. Beadle, the Assistant President of International Combustion Engineering Corporation, New York, and editor of *Combustion*, who caused a tablet to be erected in the church at Dartford, setting out the facts we have given, in July, 1924.

STEAMBOATS.—While the locomotive engineers were at work others were experimenting with the application of the steam engine to water transport. The first practical steamboat seems to have been the *Charlotte Dundas*, made by Symington in 1801 for use on the Forth and Clyde Canal. In 1815 steamers appeared on the Thames. Then they began to be used for coasting and cross-Channel work, and gradually the voyages became longer. The Peninsular Steam Navigation Company was founded in 1837, and they bought the wooden paddle steamer, the *William Fawcett*, as Fig. 182, which had been built in 1829, and started running between Falmouth and Gibraltar, calling at ports between. In 1840 they extended their line to Egypt, later India and the Far East, and became the Peninsular & Oriental Steam Navigation Co.

It was not till 1838 that steamers began to sail regularly across the Atlantic. The paddle steamer *Sirius* began then, and took nineteen days, and ninety-four passengers. She was 178 feet long by 25.6 feet broad by 18 feet deep.

To go back to the *William Fawcett*, the length on deck was 74.3 feet, breadth 15.1 feet, and depth 8.4 feet. In fact, she could not have been very much bigger than the "penny steamers" which used to run on the Thames when we were children. These were paddle steamboats, with a funnel so arranged that it could be lowered when going under a bridge. The steamers had their own bridges, on which the captain walked and looked very nautical. The mate threw the mooring ropes to the men on the piers, and they attended to the gangways. Below decks were the engineers and engines, all working visibly and distilling

SAILING SHIPS

an excellent odour into the air—something compounded of water, oil and steam, which was redolent to us of the ocean. It was a wonderful trip to zigzag down the Thames from Chelsea to Greenwich—let no one say they have seen London if they have not seen it from the Thames—and then below bridges, in the Pool, were real sea-going boats with the brine dripping off them. The dull dogs who rule London can never have been children, or they would at once fall in with Mr. A. P. Herbert's suggestions and reinstate the steamers.

Our penny steamers were well enough for the Thames, but we should hardly have liked to cross the Bay of Biscay in them, or for that matter the *William Fawcett*, as Fig. 182. Nevertheless, we hear that later one Thames steamer was sold to someone in the Balkans and they managed to make the voyage out to there.

The *Great Britain* was the first screw steamer to cross the Atlantic, and this she did in fifteen days in 1845. She was as well the first large ship to be built of iron. The Americans, with their magnificent inland waterways, were ahead of us in steamship design. Robert Fulton's first successful steamer, the *Clermont*, was running on the Hudson in 1807, and Stevens had preceded him with a screw-driven boat.

SAILING SHIPS.—This heading seems a little out of place, coming after steamships. One might have imagined that immediately the steamer was invented the sailing ship would have been abandoned; but this was not the case. There was some sentiment in the contest; a sailing ship is one of the most beautiful things invented by man, and so long as it did not spell absolute ruin there were men who would send them sailing for the love of it. In the first part of the nineteenth century it was the ambition of the captain to become the owner of a ship, and then, if successful, others would be bought and a small line or fleet founded. Captain John Willis, who gave the order for building the *Cutty Sark*, as Fig. 186, came of just such stock. His father had

CUTTY SARK




FIG. 182.—The First P. & O., the *William Fawcett* (1829).
(Model in Science Museum, London.)

started as a captain and built ships out of his savings, and the son, John, had sailed his father's ships until he succeeded to the business. So the salt of the sea was in his blood, and when he built the *Cutty* as late as 1869, it was as a sailing ship. The designer was Hercules Linton, who had just started ship-building with a partner called Scott. The *Cutty's* length is 212 feet 6 inches, breadth 36 feet, depth 21 feet, and she turned out to be a wonderful ship. That is one of the extraordinary things about ship-building—you can build two ships to the same plans and specification, and one will sail much better than the other. Given a good wind the *Cutty* could outsail most of the steamers of her day; they had to be content with eleven to twelve knots, while the *Cutty* was capable of seventeen to seventeen and a half knots, and on several occasions did 363 miles in the twenty-four hours. Such performances, however, could not have been obtained unless the man in command had been a fine seaman.

In course of time the machine won, and the *Cutty* fell on evil days and was sold to the Portuguese; they re-rigged

her as a barquentine and painted false ports on her sides, as shown in the drawing of her bows in Fig. 184. Time passed, and then it happened that the *Cutty* sailed into Falmouth Harbour round about 1922, and though she did not know it Falmouth was to be for a time a haven of refuge for her. Captain Wilfred Dowman, a retired master mariner, lived in a house overlooking Falmouth Harbour, and he and Mrs. Dowman determined to buy the *Cutty* and preserve her as an example of superb ship-building. She was thoroughly overhauled and found to be as sound as when she was built in 1869, and then she was re-rigged as shown in the small drawing in Fig. 184. This, by the way, gives very little idea of the ship's beauty.

Perhaps the best thing to do would be to read Mr. Lubbock's book, "The Log of the *Cutty Sark*," to get an idea of what she did, and imagine her with all her sails set racing home under Captain Woodget's command from Sydney in sixty-seven days.

However, the *Cutty Sark* has made one more voyage—her last—to start a fresh and very individual career of usefulness, and rest for good at the mouth of the Thames, her home river in the days of her great voyages. She has now been appointed a sister ship to the famous old H.M.S. *Worcester*, which has for many years trained young officers for the merchant navy off Greenhithe. But the *Worcester* has now undertaken the training of cadets for civil aviation, and it is they who will be trained on the *Cutty Sark*; freshly painted and fitted, and manned by *Worcester* cadets, she was towed round from Falmouth under the command of Commander Steele, V.C., R.N., the Captain-Superintendent of the *Worcester*, and very fittingly Captain Dowman's son was on board. So she will henceforth link the agelong tradition of sail of which she was one of the greatest exponents, with the newest method, of those who are destined to pass quickly over the waters instead of through them. Is it not a fitting fate for this lovely creation of man's hands and skill, and will not those who read these



FIG. 183. The *Joseph Conrad*, a barque of 680 tons, built probably about 1830. She traded between Liverpool and New Orleans, and was making voyage to India for a second time.

EMIGRATION

lines go down to admire her as she lies at her anchored rest, with the ships of all nations passing up and down ?

We include three coloured plates of sailing ships ; one is of vessels in the Canton River, China, with the East India-man *Waterloo* (Fig. 181) with her elaborate stern. She was of earlier type like the vessels of Nelson's day, and had a short life—let us hope it was a merry one ! The *Joseph Cunard* (Fig. 183) was a barque, that is, she had no square sails or yards on the mizzen-mast. She was only half the size of the *Waterloo* or two-thirds of *Cutty*, but crossed the Atlantic to New Orleans and later sailed to India.

The third plate (Fig. 187) we are glad to include, as it shows from a water-colour a fully-rigged tea clipper under full sail. The *Spindrift* was built on the Clyde in 1867 and wrecked two years after, in the year the *Cutty Sark* came into being. We have not been able to ascertain her tonnage, but it might have been about 1000.

It is one of the most remarkable things in the history of navigation, this rise of the clipper ships both sides of the Atlantic ; at its last hour the sailing vessel attained its perfection of design and made its fastest passages forty years after steamers started regular ocean runs.

To mention just a few other famous clippers there were the *Ariel*, *Taeping* and *Serica*, which had a famous race from China in 1866, and made the passage in ninety-nine days. Then there was the *Thermopylæ*, and *Sir Lancelot*, of 886 tons, with a crew of thirty and a canvas spread of over an acre. One of these ships sailed 1000 miles in three days, and the *Taeping* and her fellows averaged thirteen knots over long periods.

It was a magnificent swan-song, but it could not last. The Suez Canal was opened in the *Cutty's* birth year, and as steamers increased in size, with more reliable and speedier engines of triple expansion type, the economic scales were too heavily weighted against the windjammer, and the future of carrying traffic, cargo and passenger, passed for good to the engineer.

EMIGRATION.—There were great developments in transport during the nineteenth century because of emigration. We have seen (p. 122) how Cobbett remarked, the “sensible fellows,” with a little money, who packed up their traps and went Westward Ho—400 from Norfolk in 1830, and this was going on all over the northern part of Europe.

Wherever the steam engine and industrialism went it meant a great dislocation of existing conditions and a break in the traditions of life, and the land was full of enmities and strife. Let us try and imagine the frame of mind of one of the “sensible fellows” of 1830 in Norfolk; perhaps he was a hand-loom weaver from Norwich who found his occupation gone, or a ploughwright who could no longer make ploughs like Fig. 85, or one of those men who had lost their holdings through the enclosures. Then letters began to find their way back from America, and tales were told in the inn of this great New World where land could be had for the asking, and men were free and the pursuit of happiness possible.

To help us into the frame of mind of the nineteenth-century emigrants let us take an atlas to give us an idea of the size of America, which it is so easy to forget. Take a pair of compasses and place one leg round about Boston, and stretch the other across the continent to Vancouver Island; now take the compasses and place one leg on Brest, in the west of Brittany, and you will find the other spans to the east of the Caspian Sea. In this vast area were all the animal, vegetable and mineral riches which man desires, and they were to be had for the asking.

The growth of the United States can be seen by looking up the dates of the constitution of the various States. Here is a list. The government of the original thirteen on the Eastern Seaboard was ratified round about 1787-88 and 1789. Then followed Kentucky (1792), Tennessee (1796), Ohio (1803), Louisiana (1812), Indianapolis (1816), Mississippi (1817), Illinois (1818), Alabama (1819), Missouri (1821). Then Arkansas became a State in 1836, Michigan 1837,




FIG. 184 The U. S. Mail Steamship *Humboldt*, built at New York, 1850

From Bowditch's "The Sea: Its History & Romance" (Hutton & Co.)

By permission




FIG. 185 Embarking in Pleasure Steamer near Golden Gate, San Francisco




FIG. 186.—The *Cutty Sark* (1869) 921 tons, in Falmouth Harbour, from under Her own Bows.

PILGRIM FATHERS

Florida and Texas 1845, Iowa 1846, Wisconsin 1848, and California 1850. That is to say that by the time of our Great Exhibition in 1851 roughly only one-half of the country was settled in States, and in the remainder the hardy pioneer and frontiersman were pushing out into the wilderness.

This peaceful penetration of a great continent is one of the miracles of history. Coming back from America on a great liner a few years ago we passed a schooner going to the fishing on the Newfoundland Banks—the merest cockleshell of a boat—and the men waved to us, and we waved back and thought at the time of the hardihood of the small crew, and then of all the other crews that have sailed across in every variety of ship, with all their possessions and full of hope—sensible if you like, and very courageous. A fine stock.

Which brings us to our next point—the influence all this movement was to have on the Old World, because it stands to reason that you cannot found a new world and expect the old one to remain the same. It is a sound mechanical law that if you exert a force in one direction, a reaction is set up in another.

Let us now follow our “sensible fellows” to America in 1830—the carpenters, wheelwrights, millwrights, smiths and bricklayers. When they arrived people were beginning to be interested in the Pacific coast as a place for settlement, and the Oregon Trail, a great unmade road 2000 miles long, from Independence to Oregon City, was being worn smooth by the waggon-wheels of the immigrants, and our sensible fellows, if they went this way, would have been pioneers, because thousands followed them. Nothing like it has ever been seen before—nothing like it can ever happen again. Where our friends went we cannot say, but wherever it was—the Pacific Coast or one of the frontier States—they would have found that they were in a land without any traditions. At home, before the coming of Industrialism, there had been no reason to do



FIG. 187. The Tea Clipper *Spindrift*, built at Glasgow 1867, wrecked on Dungeness 1869.

PILGRIM MOTHERS

a thing very quickly; if you built a waggon you did it as well as you could and made it to last 100 years. Mass production would have been ridiculous in a village or country town. But when he got to the States man was pigmy when compared with the countryside. It was not a question of 100 men doing the work of 100 men, but 100 men confronted with the possibilities of employment for thousands. It was a virgin country; all you had to do was to walk in and help yourself with two hands and wish you had twenty. So all the old traditions were cast on one side and every possibility was explored for saving labour. A perfectly proper thing to do.

Then there were the women to be considered, and though we hear much of the Pilgrim Fathers, not so much is said of the Pilgrim Mothers, yet they exercised an enormous influence. No race of women ever played a greater part in history than the wives and mothers who followed the trail in the covered waggon, and bred a new race and did all the chores at the same time. Had they stayed at home and lived in such a house as we have described in Chapter II they would have found their joy in running their houses as we have described; but in a new world this was not possible, and so the ingenuity of their menfolk went to providing them with every labour-saving appliance that would ease their unremitting toil. Labour-saving was necessary in the New World, where the frontier was always ahead, but it was a fatal doctrine for the over-populated Old World, and it may even be that, now the frontier of the New World has been reached, they too may have to consider whether Quantity is better than Quality.

ELECTRICITY.—The last name that we shall mention in this book is that of Michael Faraday (1791–1867), who in 1831, by his discovery of electro-magnetic induction, brought electricity into use. Faraday was a blacksmith's son, who ended his school life at thirteen and began work by selling newspapers. His opportunity came when, after attending lectures by Sir Humphrey Davy, he called on

FARADAY

the lecturer with his notes, and as a result was appointed a laboratory assistant at the Royal Institution at 25s. a week.

There is hardly a modern development in electrical engineering which cannot be traced back to Faraday. Many men followed in his footsteps ; Joseph Henry, an American, nearly anticipated Faraday's discovery. Lord Kelvin was the pioneer of submarine telegraphy ; James Clerk Maxwell put the discoveries into mathematical form ; Charles Wheatstone's experiments led to the electric telegraph ; David Edward Hughes invented the microphone ; Joseph Wilson Swan the incandescent filament lamp ; and Thomas Alva Edison is another name in the brilliant band—and the end is not yet. The latest development of Faraday's discovery is the distribution of electric power by means of the Grid in England, and it may be the most important.

Through the kindness of Mr. J. H. R. Body and the Newcomen Society we give some particulars of early electro-magnetic engines, from an interesting paper read by him recently before the Society. William Sturgeon evolved the electro-magnet in 1825 and seven years later he designed a machine in which a central shaft carrying two horizontal permanent bar magnets was made to revolve between four vertical electro-magnets energised with current from a battery. A reproduction of this machine is in the Science Museum. Soon after Davenport, in America, made a rudimentary electric locomotive which is really more like an electric merry-go-round. A little later Robert Davidson, of Aberdeen, made an electric locomotive which actually ran at four miles per hour on a stretch of the Edinburgh and Glasgow railway (Fig. 173), electro-magnetic engines were also designed in America by Cotton in 1846 and Farmer in 1847 (Figs. 174, 175). All these ingenious machines failed in competition with steam from the weight and cost of the batteries which supplied their power ; electric traction did not really become practicable

THE "WAYSIDE INN"

until the invention and application of the dynamo, but these early experiments are of intense interest as precursors of the enormous present day developments in electric traction on rail and road.

Watt's steam engine gathered men together because they had to go where the power was, and so the industrial towns came into being; electric energy, if it can be distributed cheaply, may take men back to the village and the countryside.

This brings us to our **CONCLUSION**. What hope is there for boys and girls of fourteen to eighteen who may read this book and wish to find interesting and useful work to do?

Whether we like it or not, the world *to-day* is still accepting the American tradition of mass-production and labour-saving which came about owing to the conditions we described on p. 216. Some while ago we were talking to a Japanese gentleman, and asked him why in his country they were abandoning their own charming ways of making things and following Western fashions. "Oh," he said, "we must have lifts and things; we must all be like America."

This is a question of primary importance. We had an extraordinarily interesting trip to America in 1928 to inspect factories. We got as far west as Detroit, the home of mass production. Everybody was prosperous—dollar bills were as evident as leaves in the autumn—yet it all seemed unreal to us, this monstrous factory development, and we were happier motoring through New England and dining at the "Wayside Inn."

If mass production is to continue there are fearful dangers ahead. Carried to its logical conclusion, it means entirely automatic plants and very little work for anybody, and a dull grey world, with the "dole" for consolation.

Again, there is the argument that all these things must be accepted because of our export trade; but nowadays all the nations are sellers, not buyers. That

SPENDING

wise old man Johnson, when he was travelling in Scotland with Boswell, told him, in 1773: "Depend upon it, this rage of trade will destroy itself. You and I shall not see it; but the time will come when there will be an end of it. Trade is like gaming. If a whole company are gamesters, play must cease; for there is nothing to be won. When all nations are traders, there is nothing to be gained by trade, and it will stop first where it is brought to the greatest perfection. Then the proprietors of land will be the great men." This hardly means that all export trade will cease, but it is possible that imports will be restricted to those things which we cannot produce ourselves.

It may be thought by our readers that we detest machinery. This is not the case at all; we are very interested in it. It is the products of machinery which are so generally detestable. We speak with some experience, because one of the authors, when young, spent a year in a carpenter's shop where all the work was done by hand. Anybody who has spent a long summer's day rip-sawing 2-inch deals or jack-planing English oak is in the mood to accept the assistance of the machine—but it is a dangerous master. In its place the machine is a useful servant, and if work can be so organized with its aid that men can find an interest in their work, well and good. Given cheap electric power, the small tradesman of the village might come to life again and restore the balance of life there. How is this to be done?

The remedy is in the hands of our readers, who in a few years will be men and women, running the world themselves. Trade and industry cannot be changed by Acts of Parliament, but they can be stimulated and altered by Demand.

Let us assume that in ten years' time every man and woman has been so trained that they can appreciate good work, are prepared to do it themselves, and expect and demand it in return. Take the case of women, who really run the world. They are the great spenders, not spend-

SAVING

thrifts. The married woman decides what food the family shall eat, guided somewhat by her husband's grumbles; she has a distinct say in house-building, as any architect with an experience of clients' wives knows, and the woman decides what clothes she and her children will wear, and drives her husband to his tailor when he becomes too tramp-like.

Supposing all the women in ten years' time forswore prettiness and went in for really good stuff; interested themselves in finding out if their food were wholesome and not adulterated, bought home-grown produce in preference to foreign, established markets and did their own marketing. Supposing they interested themselves in town-planning and slum clearance and seeing that their houses were well built. Supposing they demanded that their clothes should be well made and no one sweated in their manufacture. Supposing they forget prices, because prices are only relative and an index of an exchange of commodities. If all this happened, then their own and other people's children would not have to look very long for interesting work to do.

It is not very much to ask; only that they should apply to all their household spending the same rules which obtain when they buy their own dresses. A woman may have to buy her dresses off the peg (if she is a stock size), but she really hates it, and if at a party she meets a fellow-woman in the fellow dress there may be bloodshed or hysterics—and this is a perfectly proper feeling. Nature hates repetition and charmingly varies her products, making no two things alike. Let woman, the great spender, turn over a new leaf and amend her ways and all will be well with the world once more.

N.B.—We have continued the tale in Vol. IV of this series which deals with Everyday Things from 1851 to present time.

INDEX

The numerals indicated in black type refer to the illustrations, which are referred to under their **figure-numbers**.

- Acacia tree, 113
 Adam, Robert, 50, 62, 76
 Agriculture, 3, 9, 11, 24, 109, 113, 116, 119, 124, 134
 Ague, 85
 Albert, Prince, 172
 Almerico, 44
 America, 214, 219
 Antrim, 134
 Aqueduct, **71**, 77
 Arkwright, 70
 Ashridge Park, **107**, **111**, 149
 Ayot St. Lawrence, **43-5**, 60

 Back-to-back houses, **117**, **119**
 Bailiff, **82**
 Bakewell, 22
 Baking, 32
 Balloons, 79
 Bank of England, **106**
 Barbers, 84
 Bath, 88
 Bath buns, 156
 Baths, 88
 Bay windows, 52
 Bayeux tapestry, 13, 149
 Bazalgette, Sir J., 105
 Beckford, 151
 Bed, **36**, **172**
 Bedford Row, 91
 Belhus, 48
 Bell, Adrian, 147
 Bell's Reaper, **86**, **87**, 126
 Belton House, 40
 Berkhamstead, **3**, 3, 164
 "Best Friend," the, 207
 Bethnal Green Museum, 197
 Bicycle, **177**, 203
 Blankets, 121
 Bleeding, 85
 Blenkinsop, 207
 Bonnet, 74
 Bookcase, **126**
 Boston tea-party, 107
 Boswell, 34, 220
 Botley, 113
 Boulton, 80
 Boulton and Watt's rotative engine, **171**
 Boxing, **143**
 Bramah, 97
 Bread, 32, 108
 Brettingham, Matthew, 22
 Brewing, 28
 Bridges, **74**, 79, 80, 200
 Bridgewater, Duke of, 77
 Brighton, **108**, 161
 Brindley, 77
 Brougham, **170**
 Brown, "Capability," 49
 Buonaparte, 107
 Burghclere, 119
 Burlington, 43
 Burton, Decimus, 161
 Butter, 34

 Cabinet, **128**
 Calash, 73
 Campbell, Colin, 43
 Canals, **71**, **72**, **73**, 77
 Candles, 37
 Carding, **46**
 Carlton House Terrace, 154
 Carts, 9, 92, 134
 Cartwright, 72
 Castles, 149
 "Catch-me-who-can," **178**, 205
 Cattle rearing, 19, 22
 Cellar dwellings, 166
 Cesspools, 91
 Chadwick, 169
 Chairs, **121-124**
 Chaises, 78
 Chambers, Sir Wm., 49
 "Charles," **142**
 Chelsea Embankment, 106
 Chinese design, 49
 Cholera, **80**
 Churches, **44**, **45**
 Churn, **28**
 Cisterns, **76**, 93
 Clipper ships, **186**, **187**, 210, 213
 Closets, water, **77**, 96
 Clothing, 63, 184

INDEX

- Coaches, **32, 78, 162, 193, 200**
 Cobbett, 7, 19, 23, 111, 162
 Coke of Holkham, 22, 46
 Common Fields, 3
 Cooking, 30, **133-136, 177**
 Corn Law, 111
 Costume, v. Dress
 Cotswolds, 5, 119
 Country Life, 3, 11, 109, 116, 119, 134
 Cowpox, 83
 Cravats, 195
 Crinoline, 194
 Criminals, v. Prisoners
 Crompton, 71
 Cruzie, **30**
 Cugnot, 205
Cutty Sark, **184, 210**
- Dance, George, 52
 Dancing, **146, 147, 160**
 Dartford, 208
 Davidson, Robert, 218
 Dentistry, 85
 Diary, Woodforde, 9, 24, 73, 83
 Dibbling, **17, 25**
 Digesters, 31
 Diseases, 9, 84
 Diviners, 90
 "Doctor's Visit," the, **130**
 Dog madness, 86
 Dole, 110
 Doultons, 91
 Drainage systems, **78, 79, 100**
 Drains, 87, 91, 97
 Dress, **36, 58, 59, 60, 61, 62, 63, 64, 65, 65A, 66, 73-6, 150, 152, 153, 154, 155, 156, 157, 158, 191**
 Drills, 12, **15, 16**
 Dust, 200
 Dwellings, workmen's, **125, 174**
- Electric traction, **173-5, 218**
 Electricity, 217
 Electro-magnetic engines, **174, 218**
 Emigration, 122, 213
 Empire State Building, 102
 Enclosure Acts, 20, 24, 110
 Engineering, 77
 Evelyn, John, 31
 Executions, 58
 Exhibition, Great, 152, 174
- Factory System, 80
 Factoryscape, **116**
- Fairs, 120
 Falmouth, 212
 Family Party, **120**
 Faraday, 217
 Fares, coach, 78
 "Farmers' Glory," 124
 Farming, 3, **17A, 20, 25, 109**
 Farnham, 111
 Fencing, **144**
 Fever, 55, 84
 Fields, 3
 Fiennes, Celia, 7, 8, 40, 77, 89, 198
 Fire of London, 40
 Fireplaces, 48, 52
 Fish diet, 28
 Fishing, **145**
 Flail, 130
 Flaxman, 51
 Fleet, the, 91
 Flogging, 9, 113
 Fogs, 180
 Folding Sheep, 20
 Fonthill, 151
 Food, 27, 28
 Foundry, 124
 Four-course system, 21
 Furniture, **121-124, 126-132**
- Game Laws, 19
 Gaol Fever, 53, 84
 Garden Cities, 167
 Garderobes, 89
 Gas, 182
 Gates, **103, 104**
 Geese, 116
 Geffrye museum, 197
 Gibbs, James, 46
 Girdle, **27**
 Glove-making, 121
 Gothic Revival, 148, 154
 "Gothick," 49, 151
 "Great Britain," the, 210
 Grecian Dress, 74
 Greek style, building in, 60
 Grid lines, 183
- Hairdressing, 193
 Hampton Court, 40
 Hansom, 202
 Hardy, Thomas, 143
 Hargreaves, **55, 65, 68**
 Harington, Sir John, 96
 Harvest, 26
 Hats, 193

INDEX

- Haymakers, 120
 Healds, 66
 Heating, steam, 158
 Hedley, 207
 Hellyer, Stevens, 96
 Herbert, A. P., 210
 Hexham, 120
 Hobby-horse, **176**, 203
 Hoeing, 12
 Holkham, 22, **34**, **36A**, 40
 Hot plates, 178
 Hours, working, 104
 Houses, **33**, **112**, **113**, **114**, 158, 165
Humboldt, U.S. steamship, **185**
 Hunter, John, 84
 Hydrophobia, 86

 Ice houses, **137**, 181
 Icknield Way, 78
 Idle-back, **24**
 Implement, 8
 Industrial Revolution, 2, 83
 Industrial Towns, 164
 Industrialism, 10, 213
 Inns, 79, **169**, 201
 Interiors, **36A**, B, 43, 46, **120**, 183, 197
 Inoculation, 83

 Jacquard apparatus, **148**, 184
 Jam, 33
 Jefferson, 107, 113
 Jenner, 83
 Jesty, 84
 Johnson, Samuel, 220
 Jones, Inigo, 39
Joseph Cunard barque, 182
 Journeys, 78, 201

 Kay, John, 63, 68
 Kedleston, 46
 Kent, W., 44
 Kew Gardens, 112
 Kettle, **24**, 31
 Kitchen, **20**, **21**
 Knee-breeches, 195

 Labourers, farm, 115, 120
 Labour-saving, 217
 Lamps, 37
 Langley, Batty, 48
 Lark story, 119
 "Leather-legged chap," **83**
 Leverton, 51
 Lighting, 37, 182

 Linen, 121
 Locomotives, electric, **173-5**, 218
 Locomotives, steam, **165**, **166**, **172**, **178**, **179**, 203
 Locust tree, 113
 Lodges, Hyde Park, **114**
 London, 7
 London Museum, 197
 Looms, **47**, **51**, 63, 66, 72, **138**, **141**, **149**, 184

 Macadam, 108
 Machinery, 220
 Mackintosh, 195
 Macmillan, 203
 Mail coach, **32**, **162**
 Manufactures, 8
 Markets, 4, 81, **169**
 Mass production, 217
 McCormick, Cyrus, 127
 Mead, 29
 Meals, 28
 Meat-eating, 28
 Measure, **29**
 Medicine, 83
 Menai Bridge, 200
 Mereworth, 44
 Merry-go-round, **159**
 Milkman, **81**
 Mills, steam, 80, 131
 Miners, 123
 Mistley Church, Essex, 62, 76
 Monmouth St., Soho, **79A**
 Moustaches, 196
 Mowers, 120

 Nash, 154
 Navvies, 78
 Needles, 188
 Newgate, **38**, **39**, **40**, **42**, 52, 113
 New River Co., 93
 North Shields, 123
 "North Star," **166**
 Northumberland Avenue, 106

 Omnibus, **167**, **168**, 201
 Organ, **14**
 Oseberg, 135
 Osterley House, 96
 Ovens, **26**, 32

 Pack-horses, 7, 77
 Paddle steamers, **186**, 209
 Palladian style, **33C-F**, **36A**, 43-6
 Pan, Frying, **25**

INDEX

- Papier maché, **127, 132**, 175
 Parasols, 193
 Parliament Street (1829), **105**
 Pasteur, 86
 Pedlar, **17A**
 Pavilion, Brighton, **1, 108, 115, 133**, 178
 "Pedestrian Curricule," 203
 "Peter Porcupine," 112
 Piano, **127, 131**
 Picking stick, 188
 Pigs, 36
 Pilgrim Fathers, 214; Mothers, 214
 Planning, 164
 Ploughing, 6, 13, 25
 Ploughs, **10, 11, 12, 13, 85, 100**, 124
 Plumbers, 101, 104
 Poke bonnets, 193
 Poor Laws, 171
 Port wine, 29, 85
 Power, *v.* Steam; Loom, 72, **138, 141, 149**, 185
 Prices, 28, 109, 120, 145
 Prisoners, 55, 57, 58
 Prisons, 53
 Puddings, 33
 Pugins, the, 151
 Pumps, 93
 Punishment, 9, 59
 Putney Bridge, 106

 Quadrille, **147**

 Railways, 123, 203, 205
 Rainhill Trials, 207
 Ranges, 31, **133-6**, 179
 Ransome, 124
 Rattle, 5
 Reaping, **86, 87, 88**, 126
 "Red Lion," Greenwich, **169**
 Red Lion Square, 91, 93
 Reed, 186
 Refrigeration, 181
 Regency style, **36B**, 112-4, 158, 162
 Regent, the, 154, 161
 Regent Street, 156
 Rents, 27
 Repton, 161
 Revett, N., architect, 60-2
 Riding dress, **157**
 Roads, 6, 78, 198
 "Rocket, The," 207
 Rolling, **100**
 Rooms, **118, 120, 130**

 Rotation Club, 27
 Rotten boroughs, 114
 Rumford, Count, 181
 "Rural Rides," 111

 Sailing ships, **181-2, 186-7**, 210
 St. Pancras Church, 152
 Salisbury Cathedral, 149
 Sanitation, 53, 87
 Saucepan, 33
 Scoop, 7
 Screw steamers, 210
 Scurvy, 84
 Scythes, 129
 Sea bathing, 86
 "Seed Time," 119
 Serge trade, 81
 Sessions House, **41**
 Sewage disposal, 89
 Sewers, 91
 Sewing machine, **139**, 188
 Shaw, Norman, 101, 152
 Shed, 67
 Shillibeer's omnibus, **168**, 201
 Shoes, 74, 194
 Shops, **30A, 30B, 109, 110**
 Shuttles, **52, 53, 54**, 68
 Sickles, **18**, 26
 Silchester, 1
 Singer, I. M., 191
 "Sirius," the, 209
 Skansen, 145
 Skating, **65A**
 Skim milk, 36
 Skirts, 194
 Slide car, 134
 Slums, **79A**, 83, 104, **119**, 165
 Small-pox, 83, 172
 Smelting, 80
 Smith, 4
 Smithfield Horse Show, **161**
 Snuffers, 37
 Soane, 156
 Socrates, 113
 Souse, 36
 Sowing, 11, **84, 100**
Spindrift, clipper, **187**
 Spinning, **48, 49, 50, 55, 56, 57, 140**
 Spinning jenny, **49, 55**, 65, 69
 Spinning machine, **50, 56**
 Spinning wheel, 65
 Squire and parson, 38
 Stage-coach, **32**
 Staircases, **35, 37**, 43, 46
 Steamboats, 123, **185, 186**, 209

INDEX

- Steam coaches, **163, 164**, 202, 205
 Steam engine, 82
 Steam omnibus, **163, 167**
 Steam power, 80
 Stephenson, George, 207
 Stoves, 31
 Strand, the, 7
 Straw plaiting, 120
 Strawberry Hill, **37, 43**
 Street, A. G., 147
 Stuart, "Athenian," 59
 Suburbs, **22**
 Surgeons, 84
 Sweeps, 34

 Table, **126**
 Table-ware, 29
 Tailings, 131
 Tailor, **151**
 Taxes, 85, 114
 Tea, 29
 Telford, 198
 Textiles, pre-factory, 8
 Threshing, 27, **89, 90**, 120, 129
 Tijou, Jean, 40
 Tillage, 11
 Timber carriage, **98**, 146
 Timber truck, **99**, 146
 Tips, 28, 30
 Tithes, 27
 "Tom Brown's Schooldays," 201
 Town-planning, 82, 164
 Towns, 3, **101, 102**, 164, 183
 Townshend, 21
 Trade Cards, **80A, 80B**
 Traffic, **105**
 Trains, **165, 166, 180**
 Trams, 205
 Transport, 77, 134, 198
 Traps, drain, 97
 Travelling, 7, 78, 198
 Trenchers, **19, 29**
 Trevithick, 204
 Trevithick's model, **172**
 Trough, **6**
 Trousers, 196
 Truck System, 123
 Tull, Jethro, 3, 10, 20, 116
 Tumbrils, **92, 93**
 Turnips, 20, 26
 Turnpikes, 122, 198
 Turnspit, **20, 23**
 Typhoid, 101
 Typhus, 85

 Vaccination, 83
 Vails, 28, 30
 Valve closets, **77, 96**
 Valves, ball, 93
 Vehicles (i. coaches, omnibus, steam, etc.), 78, 198
 Viaduct, **73**
 Victoria Embankment, 106
 Viking ship, 135
 Village amusements, **159, 160**
 Villas, **112**

 Wages, 25, 30, 109, 120, 123
 Waggon, **31, 92, 94, 95, 96**, 135, **163**
 Waistline, 193
 Wallpapers, 50
 Walpole, Horace, 148
 Warp, 66
 Washing, 33
 Washington, George, 23
 Waste or Common, 4
 Water frames, 70
 Water mills, 120
 Water pipes, 93
 Water supply, 90, 92, 166
 "Waterloo," East Indiaman, **181**
 Watt, James, 10, 80, 203
 Weaving, **47, 51**, 63, 66, **149**, 184
 Wedgwood, 51
 Well winch, **75**
 Wells, 92
 Westminster, 104
 Wheat, 27, 109, 119
 Wheels, 136
 Wheelwright, **97**, 136
 Whiskers, 196
 "William Fawcett," the, **183**
 Windmills, 132
 Window tax, 85
 Winnowing, **91**, 130
 Witney, 121
 Woodforde Diary, 9, 24, 73, 83, 109
 Woodforde, James, 24, 27, 78, 109
 Woodforde, Nancy, 29, 33
 Woodget, Capt., 212
 Woodlands, 116
 Woodwork, 43
 Wren, 40
 Wyatt, James, 149

 Young, Arthur, 23, 25, 120

A Selected List of BATSFORD BOOKS

relating to

*Architecture, Fine and
Decorative Art, Interior
Decoration, Gardens, Social
History, Crafts, Applied
Science, Engineering, etc.*



Published by B. T. BATSFORD LTD

Bookseller, and Publishers by Appointment to H.M. The Queen

15 North Audley Street, Mayfair
London, W.1

CONTENTS

	<i>Page</i>
THE BRITISH HERITAGE, PILGRIMS' FACE OF BRITAIN & NEW CENTURY LIBRARIES	3-5
BOOKS ON ENGLAND	3-11
HISTORIC COSTUME	12
SOCIAL HISTORY	8-13
HISTORIC ARCHITECTURE	14-21
HISTORIES OF ARCHITECTURE	14-17
CLASSIC ARCHITECTURE AND THE ORDERS	14-17
RENAISSANCE ARCHITECTURE	14-17
MEDIEVAL ARCHITECTURE	14-17
ARCHITECTURAL DRAWING	11, 13
GARDENS	5, 17, 19
CHURCH ART	16-19
MODERN ARCHITECTURE AND DESIGN	19, 21
THE MODERN HOME	21, 22
PERIOD FURNITURE AND DECORATION	19-22
BOOKS FOR COLLECTORS	18-25
FINE AND DECORATIVE ART	22-23
HISTORIC ART	24-26
DESIGN AND ORNAMENT	25-27
MANUALS ON DRAWING, COMPOSITION, ETC.	26-29
ART ANATOMY	28-29
LETTERING	29
ARTS AND CRAFTS	30-31
NEEDLEWORK AND EMBROIDERY	30-31
INDEX	32

NOTE.—This list comprises over 200 books on the subjects shown above from Batsford's main catalogue, in which are listed some 650 odd titles. It is intended to form a representative selection for the use of readers, but those interested in any particular subject should obtain the main catalogue (which will be sent post free on request), that comprises a much wider range of titles under every head. Fully illustrated prospectuses of most books can also be sent on request. Patrons are reminded that Batsford's new premises are at 15 North Audley Street, London, W.1, one minute from Oxford Street, on the main thoroughfare leading to Grosvenor Square, three minutes' walk from either Bond Street or Marble Arch Stations on the Central London Railway; there an immense stock of books, old and new, English and foreign, with prints, pictures, etc., can be inspected at leisure in the large and beautifully-fitted showrooms and gallery. *Telephone Mayfair 6118; Accounts and Production, Mayfair 4337. Cables: Batsfordia, London. Telegrams: Batsford, Audley, London.*

A full index of the books contained in this list, arranged alphabetically under the names of authors, is given on page 32.

THE BRITISH HERITAGE SERIES

Numerous other volumes in the British Heritage Series are in active preparation or projected; particulars will be gladly placed at the disposal of any interested, together with illustrated prospectuses of any or all of the above volumes, on application to the Publishers.

THE OLD TOWNS OF ENGLAND

By CLIVE ROUSE, F.S.A. A careful and informative Review of their Types and History, Features and Industries, including Cathedral Cities, Spas and Resorts, Market Towns, Scholastic and Church Centres, Sea Ports, etc. Illustrated by some 120 fine photographs of general views and fine public and private buildings, picturesque corners and byways, aerial views, and including sketches, old prints, etc. With coloured Frontispiece by W. SIDNEY CAUSER and decorative jacket in colour by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE ENGLISH CASTLE

By HUGH BRAUN, F.S.A., A.R.I.B.A. An original and thorough review of the origin, evolution and vicissitudes of mediæval fortresses, with accounts of military engines, famous sieges, etc. Illustrated by some 125 fine photographs of general and air views, features and details of the outstanding examples in England and Wales. Including also a series of reconstructions, sketches, old manuscripts, pictures, etc., and Foreword by HILAIRE BELLOC. With coloured Frontispiece and decorative jacket in colour by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE SEAS AND SHORES OF ENGLAND

By EDMUND VALE, Author of "Things that are Seen," "The World of Wales," etc. With a Foreword by Sir ARTHUR QUILLER-ROUCH ("Q"). A bright, racy account of the varied English and Welsh coastline, its Cliffs and Coves, Estuaries and Ports, Inlets and Harbours, including the Solway, the Irish Sea and St. George's Channel, the Severn Sea, the Atlantic, the English Channel and the North Sea. Illustrated by some 130 fine photographs of coast and sea scenes, etc. With coloured Frontispiece by P. SHEPPARD and decorative coloured jacket by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE SPIRIT OF IRELAND

By LYNN DOYLE, Author of "Ballybullion," and short stories of Irish Life. A bright, witty yet informative review of Dublin, the South East Corner, Grasslands and County Towns, Cork and Kerry, Limerick and Clare, Galway and the North-West, Derry and Antrim, Belfast, etc. Illustrated by 138 superb unpublished Photographs of coast and mountains, islands, rivers, antiquities, cottages, towns, life in fairs, gatherings, sport, etc., forming an unrivalled pictorial survey. With 3 colour pictures by PAUL HENRY and HUMBERT CRAIG, and pen drawings, map and decorative jacket in colour by BRIAN COOK. Second edition. Demy 8vo, cloth, gilt. 7s. 6d. net.

THE ENGLISH COUNTRY HOUSE

By RALPH DUTTON, Author of "English County Homes Open to the Public." An historical and social review, tracing design and evolution from the Conquest to Victorian times, including Interior Decoration and Gardens. Illustrated by 130 fine Photographs, largely taken expressly for the work, by WILL F. TAYLOR, and others, of Mediæval, Elizabethan, Stuart, Georgian, Classic and Neo-Gothic examples throughout the country in their charming settings. With coloured Frontispiece by ALGERNON NEWTON. Numerous Plans, End Papers of Old Views, and decorative coloured jacket by BRIAN COOK. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE ENGLISH ABBEY: ITS LIFE AND WORK IN THE MIDDLE AGES.

By FRED H. CROSSLEY, F.S.A., author of "English Church Monuments," etc. With a Foreword by the Rt. Hon. W. Ormsby-Gore, P.C., M.P., First Commissioner of Works. An informative yet vivid review of Origins and Orders, the Working Staff of the Convent, the Buildings, Daily Round and Processions, Administration, Building Methods, and Social Reactions. With 138 Illustrations from Photographs by the Author, and others of Interior and Exterior views, features, etc., and sketches by BRIAN COOK. Including also List of Abbeys, Map and Plans, 2 coloured plates from contemporary MSS., and 1 by T. GIRTIN. With gay coloured jacket by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE PARISH CHURCHES OF ENGLAND

By the Rev. J. C. CON, LL.D. Edited, with an additional three Chapters, by CHARLES BRAOLEY FORD, author of "The Landscape of England." With a Foreword by the VERY REV. W. R. INGE, D.D., late Dean of St. Paul's. With Chapters on the Life and Services, the Evolution of Plan, Structural Design, Fittings and Furniture, and Local Varieties of Style. Including 135 fine Photographic Illustrations of Exteriors and Interiors, Features in stone, wood and metal, a special series of Plans and Drawings. With a coloured Frontispiece by HUGH O'NEILL, glossary, and gay decorative coloured Wrapper by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE CATHEDRALS OF ENGLAND

By HARRY BATSFORD, Hon. A.R.I.B.A. and CHARLES FRY, with a Foreword by HUGH WALPOLE. With a rapid but comprehensive Introduction, followed by a short, clear, description of each cathedral, its situation, history and architecture. Including 133 Illustrations from new photographs, a superb series, far in advance of anything yet produced, a colour Frontispiece from an old drawing by F. MACKENZIE, a complete series of uniform Scale Plans, Glossary, and some 30 Line Sketches and gay decorative coloured jacket by BRIAN COOK. The book is ideal for the tourist; untechnical but informative, superbly produced and illustrated. Second Edition, revised. Demy 8vo, cloth, lettered. 7s. 6d. net.

ENGLISH VILLAGES AND HAMLETS

By the Hon. HUMPHREY PAKINGTON, F.R.I.B.A., President of the Architectural Association, Author of "How Men Build," etc., with a Foreword by E. V. KNOX ("Evoc"), Editor of *Punch*. A popular Pictorial Survey in 130 fine new Photographic Illustrations of unspoilt varied examples from some 30 English counties, in stone, brick, plaster, half-timber and cob, including many full-page unpublished Views, also 4 coloured Plates and 25 Pen Drawings specially made by SYDNEY R. JONES, Maps, and gay decorative coloured wrapper by BRIAN COOK. Second Edition, with an Historical Introduction by G. N. YOUNG. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE SPIRIT OF LONDON

By PAUL COHEN-PORTEIM, author of "England the Unknown Isle," "While Time Stood Still," etc., with a Foreword by RAYMOND MORTIMER. A series of original and brightly written chapters on Through the Centuries; Streets and their Life; Green London; Amusements and Night Life; Traditional London; and other subjects, with 144 splendid photographic illustrations of many London scenes and life, including a colour Frontispiece by W. SIDNEY CAUSER, pictorial endpapers, and gay decorative coloured jacket by BRIAN COOK. Demy 8vo, cloth, lettered 7s. 6d. net.

An extremely thorough and well-balanced survey of London as a living entity by one of its greatest cosmopolitan admirers. Indispensable to the Londoner, and invaluable to every provincial and overseas visitor.

THE FACE OF SCOTLAND

A Pictorial Review of its Scenery: Hills, Glens, Lochs, Coast, Islands, Moors, etc., with Old Buildings, Castles, Churches, etc. Including a brief review of Topography, History and Characteristics. By HARRY BATSFORD and CHARLES FRY, with a Foreword by JOHN BUCHAN, C.H., M.P. With 130 splendid illustrations, from specially selected Photographs, many hitherto unpublished, a Frontispiece in colour from a Water-colour by W. RUSSELL FLINT, R.A., and numerous Line Drawings in the text and gay decorative coloured Wrapper by BRIAN COOK. Second Edition revised. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE HEART OF SCOTLAND

By GEORGE BLAKE, author of "Shipbuilders," "Rest and Be Thankful," etc., with a Foreword by ERIC LINKLATER. A companion and complement to "The Face of Scotland." An able and vigorous account of the Land and its People, including a review of Highland Places, the True Lowlands, Black Country, a Tale of Four Cities, the Kirk and the People, the Fireside Clime, Sport, Institutions, Legends and Realities. Containing some 130 superb Photographic Illustrations of Scenery and Life, Mountains, Cities, Towns, Cottages, Sport, etc. With a coloured Frontispiece by KEITH HENDERSON, numerous Drawings, Map, and a gay decorative coloured wrapper by BRIAN COOK. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE HEART OF ENGLAND

By IVOR BROWN, author of "I Commit to the Flames," "Master Sanguine," "Brown Studies," etc. An able witty Review, written with penetrating and sympathetic insight, on many aspects of present-day Life and Work, including Chapters on Seaport and Seaside; the Downs and the Moors; Country Matters; Markets and Mills; The Suburb; The Week-End; The Young Idea; Recreation. With some 130 new and attractive Photographic Illustrations of many varied types of Country and Town, Life, Work and Play, a coloured Frontispiece by W. SIDNEY CAUSER, and a gay decorative coloured Jacket by BRIAN COOK. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE OLD INNS OF ENGLAND

By A. E. RICHARDSON, F.S.A., with a Foreword by Sir E. LUTYENS, R.A. A comprehensive survey of one of the most attractive features of English Life. With a letterpress full of knowledge and robust humour. Illustrated by 130 fine new Photographs of inns, medieval and later, in stone or timber, and in addition pictorial endpapers, and 20 Line Drawings and gay decorative coloured wrapper by BRIAN COOK. An indispensable possession to the tourist. Second impression. Demy 8vo, cloth, lettered. 7s. 6d. net.

THE COUNTRYMAN'S ENGLAND

By DOROTHY HARTLEY, author of "Here's England," "The Old Book," etc. An illustrated sketch of the various types of English country, the people, and their occupations. Arranged under: Mountain and Moorland; Garden and Orchard Country; The Undulating Farmlands; Hill and Downland; Fens and Levels; Coast and Estuaries. With a superb series of about 130 Photographic Illustrations of Scenery, Farmsteads, Fieldwork, Country Crafts and Occupations, etc. Including many miniature Sketches by the author, coloured Frontispiece by JOHN NASH, and gay decorative, coloured jacket by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

GARDENS IN THE MAKING

By WALTER H. GODFREY. A simple Guide to the Planning of a Garden. With upwards of 70 Illustrations of Plans, Views, and various Garden Accessories. Crown 8vo, cloth. 7s. 6d. net.

THE "FACE OF BRITAIN" SERIES I.

THE HIGHLANDS OF SCOTLAND

By HUGH QUIGLEY, author of "The Trentino and the Tyrol," etc. A graphic account of the Cairngorms, the Lower Grampians, the Far North-West, the West Coast, the Inner and Outer Hebrides and the Glencoe district. Illustrated by some 130 fine photographs of mountains, lochs, seascapes, rivers, glens, woods, etc., by ROBERT M. ADAM. With coloured pastel Frontispiece by W. DOUGLAS McLEOD, Maps, etc., and decorative coloured wrapper by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE "FACE OF BRITAIN" SERIES II

ENGLISH DOWNLAND

By H. J. MASSINGHAM, Author of "Wold Without End," "Downland Man," etc. A comprehensive review of the features, distinctive characteristics, antiquities, villages, etc., of the Chalk Country in England, including the Wiltshire Mass, the Berkshire Ridges, the Chilterns, the North and South Downs, etc. Illustrated by some 130 fine photographs of general views, hill-scenes, panoramas, farms and fieldwork, cottages and churches, barrows, cromlechs, etc. With colour Frontispiece and decorative colour jacket by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE NEW CENTURY ILLUSTRATED LIBRARY, I MOTOR RACING AND RECORD BREAKING

By the well-known Record-holding Racer, CAPTAIN G. E. EYSTON, Author of "Flat Out," etc., and BARRÉ LYNDON, Author of "Circuit Dust," etc. An historical account of achievements and thrills in many countries, and the influence of racing on car design. With 110 vivid Photographic Illustrations of track and road racing in Europe and America, hill-climbing, risks and personalities, etc. Including a colour Frontispiece by GORDON CROSBY, novel coloured photographic jacket, etc. Demy 8vo, cloth, lettered, 7s. 6d. net.

Other Volumes are in preparation; particulars will be announced later.

THE NEW CENTURY LIBRARY, VOLUME II THE WAR OF THE GUNS

Experiences of a Battery Signaller on the Climax of the Western Front, 1917-19. By AUBREY WADE. With an Introduction by EDMUND BLUNDEN, Author of "Undertones of War," etc. A graphic and vividly written first-hand account of the last desperate fighting round Ypres, Messines, Passchendaele, the Cambrai front, the German break-through, Villers-Bretonneux, and the final advance. Illustrated by some 120 fine photographs, English and German, of trench fighting, artillery work, etc., forming a unique record in pen and picture of the intensest phase of the Great War. With Maps, coloured Frontispiece by SIR WILLIAM ORPEN, R.A., and decorative jacket by BRIAN COOK. Demy 8vo, cloth, lettered, 7s. 6d. net.

THE ENGLISH AT HOME

A graphic pictorial record from photographs specially taken by BILL BRANDT. With an Introduction by RAYMOND MORTIMER. Comprising 64 full-page photogravure plates of typical scenes and Characters at Work and Play in Town and Country. Including Racing, Betting, Mining, Children rich and poor, Drinking, Bathing, Cricket, Selling, Travelling, City Life, Suburbs, a Garden Party, Teas high and low, Schools, Games, Sport, etc. A remarkable original and fascinating review of the full-flowing stream of life and work in modern England. Crown 4to, decorative boards, cloth back, 3s. net.

A Revelation in modern publishing, THE PILGRIMS' LIBRARY.
A miniature Pocket Encyclopædia of National Varied Attractiveness.

THE BEAUTY OF BRITAIN

A new composite picture of the English, Welsh and Scottish countryside, under 14 divisions by various writers, with an Introduction by J. B. PRIESTLEY. Including the Coast, and Wales, by EDMUND VALE; the West Country by EDMUND BARBER; the Chalk Country by A. G. STREET; the Central Midlands by SIR W. BEACH THOMAS; Scotland, Lowlands and Highlands, by GEORGE BLAKE; and articles by other well-known writers. With 256 pages of Text, 130 splendid Photographic Pictures of the finest and fairest scenes of the country, a Frontispiece in colour by JOHN CONSTABLE, R.A., and a decorative coloured jacket by FRED TAYLOR, R.I. Crown 8vo, cloth, lettered, 5s. net.

THE LEGACY OF ENGLAND

An Illustrated Survey of the Works of Man in the English Country: Farm, Village, Country House, Town, Church, Inn, Sport. With Introduction by EDMUND BLUNDEN and contributions by ADRIAN BELL, C. BRADLEY FORD, G. M. YOUNG, G. A. BIRMINGHAM, IVOR BROWN and BERNARD DARWIN. 256 pages, illustrated by 130 splendid Photographs of fine varied examples from all parts. With colour Frontispiece by J. M. W. TURNER, and decorative jacket in colour. Crown 8vo, cloth, lettered. 5s. net.

NATURE IN BRITAIN

A Pictorial Review of our native wild Fauna and Flora, including Animals, Birds, Fishes and Water Life, Insects, Trees and Shrubs, and Flowers. With Introduction by HENRY WILLIAMSON, and contributions by FRANCE PITT, SETON GORDON, E. G. BOULENGER, C. BUSHBY, R. ST. BARBE BAKER and R. GATHORNE-HARDY. With 120 fine photographs of animal, bird, water insect, plant and tree life, colour frontispiece and decorative colour jacket by BRIAN COOK. Crown 8vo, cloth, lettered, 5s. net.

THE BOOK OF SPEED

With 165 superb Illustrations in photogravure. Including: The Quest of Speed by STEPHEN KING-HALL; The Dawn of Flight by COL. ETHERTON; Speed in the Air by G. DE HAVILLAND; "400 Miles an Hour!" by FLIGHT-LT. G. H. STAINFORTH; Motor Record Breaking by G. E. T. EYSTON; "What It Feels Like!" by SIR MALCOM CAMPBELL; Speed-Boats by H. SCOTT-PAINE; Motor-Cycle Racing by JAMES GUTHRIE; Speed by Rail by CECIL J. ALLEN; The Ocean Routes by SIR A. ROSTRON; Speed in Warfare by Maj.-Gen. FULLER; The Non-Stop Run by the Driver of the "Flying Scotsman." Second Edition, revised and enlarged, with a Review of "The Pace in 1935" by BARRETT LYNDON, and fresh illustrations. Cr. 4to, cloth, lettered, with new Frontispiece and coloured photographic wrapper. 5s. net.

DINNER BUILDING

A Book of entertaining and practical instruction in the Noble Arts of Cooking and Eating. Written by W. TEIGNMOUTH SHORE. With an Introduction by GILBERT FRANKAU. A series of 42 bright, stimulating but practical Talks on such subjects as The Perfect Dinner, Sandwichery, Remnant Days, Cabbages and Things, incorporating hundreds of fresh recipes of all kinds. Cheaper reissue. Fcap 8vo, cloth, lettered. 2s. net.

ROUND THE WORLD IN FOLK TALES

A Regional Treatment. By RACHEL M. FLEMING. 16 Tales from Iceland, Mexico, Africa, Australia, etc., told in a fresh, easy style. With 17 Illustrations from Prints, Drawings, and Photographs. 8vo, boards, 2s. net. Cloth, 3s. net.

A fine series of exceptional Colour Records: BATSFORD'S "ART AND LIFE IN COLOUR" LIBRARY

In two sizes: (I) Quarto, (II) Small Folio. (I) comprises TROPICAL BUTTERFLIES; RARE SHELLS; THE YEAR'S WORK AND PLAY; IN MASTERPIECES OF FLEMISH ILLUMINATION; to be followed by TYPICAL MINERALS and ALPINE FLOWERS. Each contains 12 superb facsimile colour plates, reproduced regardless of expense, forming veritable works of art. With brief Introduction and text. Stiff covers, 5s. 6d. per volume.

II. PAINTING OF THE FAR EAST, chiefly Chinese, with some Japanese examples; TROPICAL FISHES and MARINE GROWTHS, the LANDSCAPES OF SWITZERLAND from views of a century ago. With brief introduction and text. Stiff covers 7s. 6d. net per volume.

These two sister series constitute an endeavour to represent some of the finest works of Nature and Art by the highest achievements of modern reproductive processes. No trouble or cost has been stinted to obtain most artistic facsimile results, which will appeal to all for their beauty and intrinsic interest. Copies in portfolio can be supplied for framing if wished. The introductions on BUTTERFLIES, SHELLS and FISHES are by Professor JULIAN HUXLEY, F.S.A. of the London Zoo; that of the volume on ILLUMINATION by Mr. FRANCIS KELLY, the writer on costume; and to the volume on PAINTING OF THE FAR EAST by Mr. LAURENCE BINYON, late Keeper of Prints at the British Museum, the well-known authority on Oriental Art.

A NEW VOLUME IN THE "ENGLISH LIFE" SERIES
THE MEDIEVAL STYLES OF THE ENGLISH PARISH CHURCH

By F. E. HOWARD, joint author of "English Church Woodwork," etc. A careful and informative account of the Evolution of Design, Features and Detail from early pre-Conquest days to the sixteenth century, including chapters on each Transitional Phase and on Methods of Studying a Parish Church. With some 160 illustrations from photographs of exterior and interior views, arcades, capitals, towers and spires, doorways, windows, carving, etc. With plans, mouldings, and decorative jacket. Large 8vo, cloth, lettered, 12s. 6d. net.

THE "ENGLISH LIFE" SERIES
THE ENGLISH COUNTRYSIDE

By ERNEST C. PULBROOK. A Review of some of its Aspects, Features, and Attractions. With 126 Illustrations from Photographs, and a Pencil Frontispiece by A. E. NEWCOMBE. New and cheaper impression. Large 8vo, cloth, gilt. 10s. 6d. net.

ENGLISH COUNTRY LIFE AND WORK

An Account of some Past Aspects and Present Features. By ERNEST C. PULBROOK. Containing about 200 pages on Farmers, Old and New—Field-Work—Cottage Folk—The Village Craftsman—Religious Life, etc. With about 200 artistic Illustrations from special Photographs. A New and cheaper reissue. Large 8vo, cloth, gilt. 12s. 6d. net.

OLD ENGLISH HOUSEHOLD LIFE

Some Account of Cottage Objects and Country Folk. By GERTRUDE Jekyll. Consisting of 17 sections on the Fireplace, Candlelight, the Hearth, the Kitchen, Old Furniture, Home Industries, Cottage Buildings, Itinerants, Mills, Churchyards, etc. With 277 Illustrations from Photographs and Old Prints and Drawings. New and cheaper reissue. Large thick 8vo, cloth, gilt. 12s. 6d. net.

An appealing novel series at cheap price:

BATSFORD'S PICTORIAL GUIDES TO HISTORIC CITIES OF NORTHERN EUROPE.

I. STOCKHOLM. II. COPENHAGEN. III. AMSTERDAM. IV.
HAMBURG.

Their Layout, Highways, Byways and Waterways, Distinctive Buildings, Life, Work and Play, presented in a series of some 100 attractive modern photographs, full-page and smaller, specially taken by Geoffrey Gilbert. With brief Introduction, Tourist Information and full informative captions. Square 8vo, in decorative two-colour stiff covers specially designed by E. McKnight Kauffer. 2s. 6d. net per volume.

THE GOOD NEW DAYS

Things that Boys and Girls Should Know. By MARJORIE and C. H. B. QUENNEL, Authors of "Everyday Things in England," "The Everyday Life" Series, etc. Demy 8vo, with coloured jacket. 6s. net.

A Series of bright informative talks about the fundamental factors of English Citizenship, present-day conditions and problems, and including comparisons with the past, in Agriculture, Towns and Suburbs, Trade and Finance, Production, Legislation, Leisure, Taxation, National Debt and Imprisonment, Armaments, etc., With historical summaries. Illustrated by numerous plans, diagrams, reproductions of old prints and up-to-date photographs, showing comparatively, power machines, farming, old villages, steamships, slums and ultra-modern flats, recent developments of social life, etc.

A striking and original book, which in an informal way provides a course in Civics, and will be found of remarkable value to all interested in the past and future of their own country.

"ESSENTIALS OF LIFE" SERIES

By Lieut.-Colonel F. S. BRERETON, C.B.E. Bright, informative reviews of the Indispensable Things of Human Life. Each with 80 pages of text, and about 100 illustrations in Line and Half-tone from Photographs, Drawings, Old Prints, etc., of Old and Modern Developments. Large crown 8vo, cloth, lettered. Cheaper reissue. 2s. 6d. net each.

CLOTHING: An Account of its Types and Manufacture. Contents: Materials—Spinning—Weaving—The Sewing Machine—A Morden Factory—Furs and Rubber—Leather and Tanning—Boots—Hats—Glove-making—Dyeing and Cleaning—Pins—Needles—Buttons, etc.

TRAVEL: An Account of its Methods in Past and Present. Contents: Early Roads and Trading Routes—Coaching—The Steam Engine—Steamships and Railways—The Bicycle—The Petrol Engine—Air Travel—Postman—Wire or Wireless. With illustrations of Coaches, Engines, Balloons, Aircraft, Ships, Steamers, etc.

THE XVIIITH CENTURY IN LONDON

An Account of its Social Life and Arts. By E. BERESFORD CHANCELLOR. Containing 280 pages, with 192 illustrations, printed in sepia, from Prints and Drawings by Contemporary artists. With a Frontispiece in colour. Cheaper reissue. Crown 4to, cloth, gilt. 15s. net.

A Companion and Sequel to the above

LIFE IN REGENCY AND EARLY VICTORIAN TIMES

An Account of Social Life in the days of Brummel and D'Orsay. By E. BERESFORD CHANCELLOR. A Series of Chapters on the time of Brummel and D'Orsay, 1800-1843. With numerous illustrations from Rare Prints and Original Drawings. Cheaper reissue. Large 8vo, cloth, gilt. 12s. 6d. net.

LIFE AND WORK OF THE ENGLISH PEOPLE THROUGH THE CENTURIES

A Pictorial Record from Contemporary Sources. By DOROTHY HARTLEY and MARGARET M. FITHOI, B.A. (Lond.). Each volume is devoted to a century and contains about 150 pictures on 48 Plates, of Household Life, Industries, Building, Farming, Warfare, Transport, Children, Church Life, Gardens, etc. With an Introduction, Descriptive Notes, Chart, Analytical Index, Music, etc. Large (royal) 8vo, boards, lettered, or in portfolio with flaps, 3s. net, or in cloth, 3s. 6d. net per volume. Volumes I and II (Early Middle Ages), III and IV (Later Middle Ages), and V and VI (Renaissance) are also together in cloth, 6s. net each, and volumes I, II and III (Middle Ages), and IV, V and VI (Renaissance) are also in cloth at 9s. net each. A few copies of volumes II and III (Later Middle Ages), and volumes IV and V (Early and Middle Renaissance), can also be obtained together in cloth at 5s. net each.

The Series has now been completed as follows:

- | | |
|----------------------------|----------------------------|
| I. SAXON TIMES TO 1300 | IV. THE SIXTEENTH CENTURY |
| II. THE FOURTEENTH CENTURY | V. THE SEVENTEENTH CENTURY |
| III. THE FIFTEENTH CENTURY | VI. THE EIGHTEENTH CENTURY |

MEDIEVAL COSTUME AND LIFE

An Historic and Practical Review. By DOROTHY HARTLEY. Containing 22 full-page Plates from Photographs of living Male and Female Figures in specially made Costumes from Medieval MSS., 20 Plates in Line from the Author's Drawings of practical Construction, Detail, Sketches, etc., and 40 Plates of some 200 Reproductions from Contemporary Manuscripts of scenes of Medieval life and work. Including full historical and descriptive text, with directions for the practical cutting out and making of many costumes illustrated. Large royal 8vo, cloth. 12s. net.

A SHORT HISTORY OF COSTUME AND ARMOUR, CHIEFLY IN ENGLAND, 1066-1800

By F. M. KELLY and RANDOLPH SCHWABE, Principal of the Slade School of Fine Art. Royal 8vo, cloth, gilt. 25s. net. Or in 2 volumes:

- I. THE MIDDLE AGES, 1066-1485. With Sections on Civilian Dress, "Shirts," "Shapes," Houppelandes and Burgundian Modes Armour. Illustrated by 4 Plates in colours and gold, over 100 special Pen Drawings by RANDOLPH SCHWABE from original sources and 32 Photographic Plates of over 70 reproductions. Royal 8vo, cloth, gilt. 13s. net.
- II. THE RENAISSANCE, 1485-1800. With Sections on Puff and Slashes, The Spanish Trend, "Cavalier" and French Modes, the Heyday and Decline of Powder, Armour, etc. Illustrated by 5 Plates (3 double) in colours and gold, over 100 special Pen Drawings by RANDOLPH SCHWABE from original sources, 36 Photographic Plates of 58 Reproductions. Royal 8vo, cloth, gilt. 13s. net.

HISTORICAL COSTUME

A Chronicle of Fashion in Western Europe, 1490-1790. By FRANCIS M. KELLY and RANDOLPH SCHWABE. Containing the chief characteristics of Dress in each century. Illustrated by some hundreds of full-page and text Sketches from original sources by RANDOLPH SCHWABE of typical groups, figures and details. Including 7 Plates specially reproduced in colour, and 70 Photographic reproductions of Pictures, Portraits, Scenes, etc. Second Edition revised and enlarged. Large royal 8vo, cloth, gilt, 25s. net.

The Quennell Series of Books on Social Life and History

In their volume the authors have approached history from a new angle and in the process have revolutionised the teaching of it. In their hands it has become a live, vivid and picturesque subject, for they have breathed new life into old books. Their methods are now widely and generally recognised and appreciated.—*Western Mail*.

A HISTORY OF EVERYDAY THINGS IN ENGLAND, 1066-1934

Written and Illustrated by MARJORIE and C. H. B. QUENNEL. In Four Volumes. Medium 8vo, 8s. 6d. net each; also Vols. I and II, and III and IV, issued each pair bound in one volume, 16s. 6d. net.

VOL. I—EVERYDAY THINGS IN ENGLAND, 1066-1499

With 90 Illustrations, many full-page, and 3 Plates in colour. Second Edition, revised and enlarged, with additional illustrations.

VOL. II—EVERYDAY THINGS IN ENGLAND, 1500-1799

By MARJORIE and C. H. B. QUENNEL. With 4 Coloured Plates and 111 other Illustrations from the Author's Drawings. Second Edition, revised and enlarged, with additional Illustrations.

Issued in Parts for Schools and Class Teaching. Stiff paper covers. 3s. net each.

PART I. ENGLAND UNDER FOREIGN KINGS (1066-1199). Containing 2 Colour Plates, 5 full-page line Illustrations, and 15 in the text.

PART II. THE RISE OF PARLIAMENT (1200-1399). Containing 2 Colour Plates, 8 full-page Illustrations, and 22 in the text.

PART III. THE HUNDRED YEARS' WAR (1400-1499). Containing 1 Colour Plate, 11 full-page line Illustrations, and 13 in the text.

PART IV. THE AGE OF ADVENTURE (1500-1599). Containing 2 Colour Plates, 16 full-page line Illustrations, and 30 in the text.

PART V. THE CROWN'S BID FOR POWER (1600-1699). Containing 1 Colour Plate, 11 full-page line Illustrations, and 21 in the text.

PART VI. THE RISE OF MODERN ENGLAND (1700-1799). Containing 1 Colour Plate, 11 full-page line Illustrations, and 19 in text.

VOL. III—EVERYDAY THINGS IN ENGLAND, 1733-1851

THE COMING OF THE INDUSTRIAL ERA. An Account of the Transition from Traditional to Modern Life and Civilization. Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Tracing the Transformation of Agriculture, the coming of Steam Power, the application of Inventions, Trends in Social Life in Town and Country, Costume, Building, etc. Illustrated by 4 Coloured Plates, 120 full-page and smaller Drawings specially prepared by the Authors, and a series of Reproductions of contemporary Engravings and Drawings. Medium 8vo, art cloth, 8s. 6d. net.

VOL. IV.—EVERYDAY THINGS IN ENGLAND, 1852-1934

THE AGE OF PRODUCTION. An Account of Modern Life and Civilization. Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Treating of old and new methods regarding the Farmer and Food, Buildings, Town Planning, Slums, Schools, Furniture, Production and Distribution, Public Health, Transport, Social Life in Clothes, etc. Illustrated by 4 single and 3 double Plates in colour, 120 full-page and smaller Drawings specially prepared by the authors, and numerous Plates from Photographs and contemporary Prints. Medium 8vo, art cloth, 8s. 6d. net.

ARCHITECTURAL DRAWING

By G. GORDON HAKE, F.R.I.B.A., and E. H. BURTON, Architects. An Introductory Treatise for Architects and Students on work of every type and in every medium. With 96 pages, 16 pages of Half-tone Illustrations and 90 Line Illustrations. Cheaper reissue. 8vo, cloth, 7s. 6d. net.

THE QUENNELLS EVERYDAY LIFE SERIES

A Graphic and Popular Survey of the Efforts and Progress of the Human Race, now completed in 4 volumes. Crown 8vo, cloth. 5s. net each

EVERYDAY LIFE IN THE OLD STONE AGE

Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Containing 128 pages, including 70 Illustrations, and a coloured Frontispiece, from the Authors' Drawings, with a Chronological Chart. Second Edition, revised.

EVERYDAY LIFE IN THE NEW STONE, BRONZE AND EARLY IRON AGES

Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Containing 144 pages, with 90 original Illustrations from the Authors' Drawings, of Household Life, Agriculture, Pottery, Weapons, Ornaments, etc., including 2 Plates in colour, a marked Map, and a Chronological Chart. Second Edition, revised.

The above two works may now be obtained bound in one handy volume as follows:

EVERYDAY LIFE IN PREHISTORIC TIMES

Containing 272 pages, 3 Plates in colour and 2 in monochrome, with 160 Illustrations from the Authors' Pen-and-Ink Drawings, two Chronological Charts and a Comparative Map. The Old Stone Age Section has an account of the Rhodesian Skull and Nebraskan Tooth, with 2 additional Illustrations. Crown 8vo, cloth, lettered. 10s. net.

EVERYDAY LIFE IN ROMAN BRITAIN

Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Containing 128 pages, with over 100 original Illustrations from the Authors' Pen Drawings, of Cities and Camps, Villas, Ships, Chariots, Monuments, Costume, Military Life, Household Objects, Pottery, etc. Including 3 Colour Plates, Chart, and Map of Roads. Second edition, revised and enlarged.

EVERYDAY LIFE IN SAXON, VIKING & NORMAN TIMES

Written and Illustrated by MARJORIE and C. H. B. QUENNEL. Containing 128 pages, with over 100 original Illustrations from the Authors' Pen and Pencil Drawings of Ships, Cooking, Metalwork, Caskets, Crosses, Buildings, Pottery, and Illuminated MSS., including 2 coloured Plates, Historical Chart, etc. Crown 8vo, cloth. 5s. net.

ENGLAND IN TUDOR TIMES

An Account of its Social Life and Industries. By L. F. SALZMAN, M.A. F.S.A., Author of "English Industries of the Middle Ages," etc. A remarkable survey of a great period in England's Social history. Containing chapters on The Spirit of the Tudor Age—Life in the Country—Life in the Town—Life in the Home—The Church—Adventure on Land and Sea. With 138 pages of text, 64 full-page Illustrations and plentiful illustrations in the text from Drawings, Engravings, etc. Cheaper reissue. Demy 8vo, cloth. 5s. net.

TOURING LONDON

By W. TEIGNMOUTH SHORE, Author of "Dinner Building," etc. With an Introduction by the Rt. Hon. John Burns, P.C. A Series of 4 Tours, covering the chief parts of Inner London, written in a bright and pleasant style, but conveying much practical and historical information. Illustrated by 28 Photographs, with Drawings and Sketches in the text by well-known artists. Also a two-colour Map of the City, and Plans. Cheaper reissue. Large crown 8vo, cloth. 2s. 6d. net.

*A New Illustrating Series of Classical Social Life. Uniform with the Authors
"Everyday Things in England"*

The Queen's illustrations are likely to attract some of the most potent of institutions of the post-war world. A book that is written with great scholarship, and is so pleasantly illustrated. To speak in superlatives is not to do it justice. Its only competitor is the *Illustrated Library* between publisher and author. The illustration is the best of the kind. —*The K. N. Weekly*

EVERYDAY THINGS IN ANCIENT GREECE (HOMERIC—ARCHAIC—CLASSICAL)

An "Omnibus" Volume of the three following works. Written and Illustrated by MARJORIE and C. H. B. QUENNELL. A full review of Social Life and the Arts. Containing 3 coloured Plates, some 235 full-page and smaller Illustrations from Drawings in Pen and Ink, Pencil, and Wash and 20 from Photographs. Large thick 8vo. 21s. net.

VOL. I. EVERYDAY THINGS IN HOMERIC GREECE

Written and Illustrated by MARJORIE and C. H. B. QUENNELL. Presenting a vivid picture based on the Social Life in the *Iliad* and *Odyssey*, etc. Illustrated by 70 Drawings by the Authors, after Vase Paintings and their own restorations. With Colour Frontispiece, Photographic Illustrations, Map, etc. Large 8vo, decoratively bound. 7s. 6d. net.

VOL. II. EVERYDAY THINGS IN ARCHAIC GREECE

Written and Illustrated by MARJORIE and C. H. B. QUENNELL. An Account of Social Life from the close of the Trojan War to the Persian Struggle. Illustrated by 85 full-page and smaller Drawings by the Authors. With a coloured Frontispiece, a number of Photographic Illustrations, Map, etc. Large 8vo, decoratively bound, cloth, lettered. 7s. 6d. net.

VOL. III. EVERYDAY THINGS IN CLASSICAL GREECE

Written and Illustrated by MARJORIE and C. H. B. QUENNELL. A vivid picture of Social Life in the Golden Age of Pericles, Socrates, Phidias, and Plato, 480-404 B.C. With Sections on Architecture; the Town and its Planning; Everyday Life; Sea Fights and Land Battles, etc. Illustrated by 83 Drawings specially made by the Authors. With coloured Frontispiece, Photographic Illustrations, Chart, Map, etc. Large 8vo, cloth, lettered. 8s. net.

If ordered at one time the three volumes of this series are priced at 22s. net.

ARCHITECTURAL DRAWING, PERSPECTIVE AND RENDERING

By CYRIL A. FAREY, A.R.I.B.A., and A. TRYSTAN EDWARDS, A.R.I.B.A. Containing accounts of Measured Work, Colouring, Sketching, Methods of Technique, Shading, Competition Drawings, Publicity and Posters, etc. Including a specially prepared Perspective in various stages by C. A. FAREY and Drawings by William Walcot, R.A., F. Brangwyn, R.A., W. Curtis Green, R.A., P. D. Hepworth, J. D. M. Harvey, and other well-known draughtsmen. With 43 Plates in half-tone, 9 in colour, 31 Line Reproductions, and 196 pages of Text. Cr. 4to, cloth. 16s. net.

SPEED ON SALT

By GEORGE EYSTON and W. F. BRADLEY. With a Foreword by SIR MALCOLM CAMPBELL. A graphic first-hand review of their pioneer record-breaking motor-runs on the Bonneville Salt Flats, Utah, U.S.A., including the world's land speed record of 300 m.p.h., and the world's 24-hour record. Describing also the strange wild romance of the surroundings and the desert village of Wardmer, etc. With 132 attractive illustrations from special photographs of machines and men. Frontispiece in colour and coloured decorative jacket by BRIAN COOK. Quarto, cloth, lettered, 7s. net.

A SHORT CRITICAL HISTORY OF ARCHITECTURE

By H. HEATHCOTE STATHAM, F.R.I.B.A. Second Edition, revised and enlarged by G. MAXWELL AYLWIN, F.R.I.B.A. Containing 600 pages and 750 Illustrations from Photographs, Drawings, Plans, Prints, etc., with Chronological Charts and Glossary. Demy 8vo, cloth, gilt. 16s. net.

Also supplied in 3 parts, cloth, gilt. 6s. net each.

- I. ARCHITECTURE OF ANTIQUITY AND THE CLASSIC AGES
- II. BYZANTINE, ROMANESQUE AND SARACENIC STYLES
- III. THE MIDDLE AGES AND THE RENAISSANCE TO MODERN TIMES

Each part contains about 200 pages, with 250 full-page and smaller Illustrations, and is complete with Prefaces, Charts, Glossary and Indexes.

"Within the limits of its size and price it is the most valuable handbook that has appeared in English for those who wish to understand the architecture of the past."
—*The Architect*.

THE STORY OF ARCHITECTURE

From the Earliest Ages to the Present Day. By P. LESLEY WATERHOUSE, F.R.I.B.A. With numerous Illustrations of the great buildings of all time from Photographs and Drawings, and many Diagrams in the text. Fcap 8vo, boards, lettered. 6s. net.

THE STORY OF ARCHITECTURE IN ENGLAND

By WALTER H. GODFREY, F.S.A., F.R.I.B.A. A popular illustrated account, in which the aims and methods of Architectural Design are simply explained, and linked up with the social life of the time. In Two Parts: I. Early and Medieval, to 1500, chiefly Churches; II. Renaissance, 1500-1800, chiefly Houses. Demy 8vo, cloth. 6s. 6d. net per part, or the two volumes bound in one, 12s. 6d. net.

I. PRE-REFORMATION, THE PERIOD OF CHURCH BUILDING
Illustrated by 133 full-page and smaller Photographs and Drawings. Large crown 8vo, cloth. 6s. 6d. net.

II. RENAISSANCE, THE PERIOD OF HOUSE BUILDING
Illustrated by 150 full-page and smaller Photographs and Drawings. Large crown 8vo, cloth, 6s. 6d. net.

NEW EDITION, REVISED AND ENLARGED, NOW READY OF
THIS GREAT STANDARD WORK

THE DOMESTIC ARCHITECTURE OF ENGLAND DURING THE TUDOR PERIOD

Illustrated in a Series of Photographs and Measured Drawings of Country Houses, Manor Houses and Other Buildings. By THOMAS GARNER and ARTHUR STRATTON, F.R.I.B.A. Second Edition, Revised and Enlarged, comprising 210 Plates, mostly full-page, finely reproduced in Collotype, and 250 pages of Historical and Descriptive Text, including 462 Illustrations of Additional Views, Plans, Details, etc., from photographs and drawings, making a total of over 800 Illustrations in all. In two volumes, small folio, buckram, gilt. £9 9s. net the set. (The volumes cannot be obtained separately *but can be purchased by instalments.*)

ANCIENT ARCHITECTURE, PREHISTORIC, EGYPTIAN, WEST ASIAN, GREEK AND ROMAN

A Chronicle in Verse, by H. CHESLER JONES, M.A., F.S.A. Comprising also an outline history of Architecture, brief Prose Introductions to each Section, and a full Glossary of Terms, etc. Illustrated by numerous large Charts and Compositions, and many Drawings and Plans of Buildings by the Author. Including a photogravure portrait and appreciative Forewords by Sir EDWIN LUTYENS, R.A., Dr. HADEN GUEST, M.P., and others. Large 8vo, cloth, gilt. 15s. net.

BYZANTINE ARCHITECTURE AND DECORATION

By J. ARNOTT HAMILTON, M.A., author of "The Churches of Palermo," etc. A careful, scholarly and thorough account of the development and character of constructional methods and decoration, and types of extant buildings in Constantinople, Greece, the Balkans, Cyprus, Armenia, Italy, etc. With coloured Frontispiece and 125 Photographic Illustrations of exteriors and interiors, Reconstructions, Constructional Diagrams, Carving, Details, etc., and numerous Line Plans, Measured Drawings, and Sketches in the text. Medium 8vo, cloth, gilt. 18s. net.

ANDERSON AND SPIERS' "ARCHITECTURE OF GREECE AND ROME"

Now reissued in two volumes, obtainable separately, revised and much enlarged. Small Royal 8vo, cloth, gilt. 21s. net each volume, or £2 the two.
I. ARCHITECTURE OF ANCIENT GREECE. Rewritten, remodelled and much enlarged by WILLIAM BELL DINSMOOR, Professor of Architecture at Columbia University, New York, and the American Academy at Athens. With over 200 Illustrations in Collotype, half-tone and line.

II. ARCHITECTURE OF ANCIENT ROME. Revised and rewritten by THOMAS ASHBY, LL.D., Late Director of the British School at Rome. With about 200 Illustrations in half-tone and line.

ARCHITECTURE OF THE RENAISSANCE IN ITALY

By WILLIAM J. ANDERSON, A.R.I.B.A. Revised and Enlarged, with an additional Chapter on Baroque and later work, by ARTHUR STRATTON, F.S.A., F.R.I.B.A. With 80 Plates, including 16 in Collotype, and 120 Illustrations in the text. Small Royal 8vo, cloth, gilt. 21s. net.

ARCHITECTURE OF THE RENAISSANCE IN FRANCE

By W. H. WARD, M.A., F.R.I.B.A. Revised and Enlarged by Sir JOHN W. SIMPSON, K.B.E., PP.R.I.B.A. In two volumes, obtainable separately. Small Royal 8vo, cloth, gilt. 21s. net, each volume, or £2 for the two.

IV. THE EARLY RENAISSANCE (1495-1640). With 259 Illustrations.
V. THE LATER RENAISSANCE (1640-1830). With 214 Illustrations.

DESIGN AND MEDIEVAL ARCHITECTURE

By HELEN ROSENAU, Ph.D., Hamburg. A study of Orientation, Planning and Design. The medieval architect and his design. With 17 Illustrations from Photographs of contemporary architectural drawings and designs, Interiors and details of cathedrals, etc., in Europe and England. A concise and able thesis incorporating the results of much close research. Large 8vo, paper covers. 2s. 6d. net.

THE SMALLER ENGLISH HOUSE FROM THE RESTORATION TO THE VICTORIAN ERA, 1660-1840

By A. E. RICHARDSON, F.S.A., F.R.I.B.A., and HAROLD DONALDSON EBERLEIN, B.A. Treating of the Characteristics and Periods of Style; the Evolution of Plan; Materials and Craftsmanship: Roofing, Windows, Ironwork, Fireplaces, Staircases, Wall Treatment, Ceilings. With over 200 Illustrations, many full-page, from Photographs and Drawings. Demy 4to, cloth, gilt. Cheaper reissue, 15s. net.

A NEW AND IMPORTANT SERIES OF SCHOOL WALL CHARTS
In Two Series now ready, consisting of 25 large lithographed Plates, 32cm. by 20in. Price, 6 plates 2ss. net each, or 12 plates, or £3 2s. 6d. net mounted on linen, with bound edges. Single diagrams, 1s. 4d. net each, or mounted, 2s. 10d. net each. Introductory Handbooks to each Series, 1s. 6d. net each, stiff paper, or 1s. 10d. net each, cloth, decorated.

THE STYLES OF ENGLISH ARCHITECTURE

A SERIES OF COMPARATIVE WALL OR LECTURE DIAGRAM. For Schools, Teachers, Students, etc. By ARTHUR STRATTON, F.S.A., F.R.I.B.A. Series I: THE MIDDLE AGES (Saxon Times to the Start of the Tudor Period). Consisting of 12 large double crown Plates, 22in. by 32in. clearly lithographed from the Author's specially prepared Drawings. 12s. net paper, 32s. net mounted.

Series II: THE RENAISSANCE (Tudor, Elizabethan, Stuart, and Georgian Periods). Comprising 12 large diagrams, as in Series I. 12s. net paper, 30s. net mounted.

The 32 pp. Introductory Handbooks contain reduced reproductions of all the Plates with all their sources, and an outline account of each style with numerous further Illustrations. The first Handbook on the Middle Ages is in its second edition, revised, with additional illustrations. Paper covers 1s. 6d. net; cloth 2s. 6d. net each.

ELEMENTS OF FORM AND DESIGN IN CLASSIC ARCHITECTURE

Shown in Exterior and Interior Motives collated from Fine Buildings of all Times. By ARTHUR STRATTON, F.S.A., F.R.I.B.A. Presenting in 80 full-page Plates about 600 motives of Facades, Loggias, Halls, Staircases, etc. Including a Series of 16 Plates of Classic and Renaissance Composition and Designs. With Introduction, Analytical Account to each Section. Descriptive Notes, and Foreword by Prof. A. E. RICHARDSON, F.S.A., F.R.I.B.A. 4to, cloth, gilt, 28s. net.

THE ORDERS OF ARCHITECTURE

GREEK, ROMAN, and RENAISSANCE, with EXAMPLES of their historic APPLICATION IN ITALIAN, FRENCH, ENGLISH, and AMERICAN COLONIAL. By ARTHUR STRATTON, F.S.A. With an Introduction by A. TRYSTAN EDWARDS, A.R.I.B.A. Illustrated in a Series of 80 full-page Plates from Drawings, mostly specially prepared, including a complete series of Vignola's Orders, and rendered examples of French, Italian, and English buildings. With full historical and practical notes and numerous Text Illustrations. 4to, cloth, gilt, or in portfolio, 21s. net; or in 3 parts: CLASSIC, ITALIAN and APPLICATIONS, cloth 8s. net each.

ENGLISH GOTHIC CHURCHES

THE STORY OF THEIR ARCHITECTURE. By CHARLES W. BUDDEN, M.A. A simple informative account of the Planning, Design, and Details of Parish Churches, Cathedrals, etc., 1066-1500, including Chapters on Local Building, Towers, Spires, Ornaments, etc. Illustrated by 53 Plans and Line Diagrams, and 40 Photographic Plates of 80 Views and Details, including a County List of the chief Churches worth seeing. Crown 8vo, cloth, cheaper reissue, 5s. net.

LITTLE KNOWN TOWNS OF SPAIN

A series of Water-colours and Drawings in facsimile colour and monochrome from the originals of VERNON HOWE BAILEY. Comprising 57 full-page Plates, many in colour, others in sepia, wash, lithography, etc., with text, including historical and descriptive short notes. Large 4to, in decorative paper binding, £1 10s. net.

CHILDREN'S TOYS OF BYGONE DAYS

A History of Playthings of all Peoples from Prehistoric Times to the XIXth Century. By KARL GROER. English Version by PHILIP HERFORD. A beautifully produced survey, with a Frontispiece and 11 Plates in colour, and 326 photographic illustrations of Dolls, Dolls-houses, Mechanical Toys, Carts, Ships, Tin Soldiers, etc., etc., of every country and period from the earliest times. With 66 pages of historical and descriptive text. 4to, canvas, gilt, with decorative wrapper. New and cheaper edition, 12s. 6d. net.

RENAISSANCE PALACES OF NORTHERN ITALY

(With some Buildings of Earlier Periods). From the XIIIth to the XVIIth Centuries. Edited by PROFESSOR DR. ALBRECHT HAUPT, in 3 vols., each containing 160 full-page Plates in Collotype from specially taken Photographs or Measured Drawings. With full text. Vol. I, TUSCANY, FLORENCE, PISA, SIENA, MONTECATINI, LUCCA, PISTOIA, etc.; Vol. II, VENICE, including also VENEZIA, MANTUA, VICENZA, and PADUA; Vol. III, GENOVA, including also BOLOGNA, FERRARA, MODENA, MILAN, TURIN, PAVIA, BERGAMO, BRESCIA, etc. Small folio, cloth, lettered, £2 15s. net each volume, or the set of 3 for £7 10s. net.

THE ARCHITECTURAL WORK OF SIR BANISTER FLETCHER, M.Arch., PP.R.I.B.A., F.S.A.

A Monograph Edited with Introductory and Descriptive Text, including a short Account of his Life and Activities, by W. HANSLFORD SMITH, Hon. A.R.I.B.A., F.R.S.E., Assoc. Inst. C.E. With numerous Plates of Sketches and Drawings of Historic Buildings at home and abroad, together with Photographs and Drawings of Town and Country Houses, Banks, Business Premises, Schools, Town Halls, Memorials, Gates, Furniture, etc., designed by the author. Quarto, cloth, fully gilt, gilt top. £2 2s. net. Edition limited to 500 copies, of which 400 are for sale.

A HISTORY OF ARCHITECTURE ON THE COMPARATIVE METHOD

For the Student, Craftsman, and Amateur. By Sir BANISTER FLETCHER, PP.R.I.B.A. Ninth Edition, completely rewritten. Containing over 1,000 pages, with about 3,500 Illustrations (1,560 recently added and nearly 2,000 reproduced larger for this Edition), from Photographs and Drawings of Buildings of all Countries and Times. Royal 8vo, cloth, gilt. £2 2s. net.

THE OLD HALLS AND MANOR HOUSES OF NORTHAMPTONSHIRE

By J. ALFRED GOTCH, M.A., F.S.A., F.R.I.B.A., Author of "The Growth of the English Houses," and numerous other standard works. With full Historical Introduction and Descriptive text, and 100 Plates of some 150 Illustrations from photographs, largely specially taken, and from original drawings and old prints, comprising Interior and Exterior Views, Features, Details and Gardens. Including also numerous plans and sketches in the text. Crown 4to, cloth, lettered. Strictly limited edition offered before publication to subscribers, 21s. net.

THE ART AND CRAFT OF GARDEN MAKING

By THOMAS H. MAWSON, assisted by E. PRINCE MAWSON, Fifth Edition, Revised and Enlarged. Containing 440 pages, illustrated by 544 Plans, Sketches and Photographs, and 5 colour Plates. Including Site, Entrances, Gates, Avenues, Terraces, Beds, Pergolas, Treillage, Rock and Water, Greenhouses, etc., etc., and list of Shrubs and Trees. Small folio, buckram, gilt. £3 15s. net.

GEORGIAN ENGLAND (1700-1830)

A Review of its Social Life, Arts and Industries. By Professor A. E. RICHARDSON, F.S.A., F.R.I.B.A., Author of "The English Inn," etc. Containing sections on the Social Scene, Navy, Army, Church, Sport, Architecture, Building Crafts, the Trades, Decorative Arts, Painting, Literature, Theatres, etc. Illustrated by 220 subjects from Photographs and contemporary Prints, Engravings and Drawings, by Hogarth, Wheatley, Gainsborough, Reynolds, Rowlandson, and other artists largely unpublished. With 54 Line Text Illustrations, and a Colour Frontispiece from an unpublished aquatint by ROBERT DIGHTON. Med. 8vo, cloth, gilt. 21s. net.

SPANISH GARDENS

By Mrs. C. M. VILLIERS-STUART. A finely illustrated volume describing the beautiful and most famous gardens by a foremost authority. With 6 Plates in colour from the Author's original Water-colour Drawings, 80 pages of reproductions of gardens, statuary, cascades, garden features, etc., from Photographs, and numerous Illustrations in the text from old Engravings, Pen Drawings, etc. Small royal 8vo, cloth. 25s. net.

TOURING ENGLAND BY ROAD AND BY-WAY

A Popular Illustrated Guide, in a new form, to the Beauties of Rural England. By SYDNEY R. JONES. Comprising 20 Typical Tours under Five Divisions, with General Introduction and complete Map, Introduction to each District and specially drawn simplified Route Map of each Tour, which is described in detail, with finger-post reference to features, and buildings of Interest. Illustrated by 54 Drawings, including a number full-page, specially drawn by the Author, and 50 Illustrations from Photographs by the Artist and others. New and cheaper issue. Crown 8vo, cloth. 5s. net.

ANCIENT CHURCH CHESTS AND CHAIRS IN THE HOME COUNTIES ROUND GREATER LONDON

With some Reference to their Surroundings. By FRED ROE, R.I., R.B.C. With a Foreword by C. REGINALD GRUNDY. A survey of the finest of these survivals of ancient craftsmanship by the leading authority on the subject. With 95 Illustrations, many full-page, from Drawings by the Author and from Photographs, and a number of Line Illustrations in the text. Cheaper reissue. Demy 4to, cloth, gilt. 12s. 6d. net.

EARLY CHURCH ART IN NORTHERN EUROPE

With special Reference to Timber Construction and Decoration. By Professor JOSEF SZRZYGOWSKI, Author of "Origin of Christian Church Art," etc. Dealing with PRE-ROMANESQUE ART OF THE CROATIANS; WOODEN ARCHITECTURE IN EASTERN EUROPE; HALF-TIMBER CHURCHES IN WESTERN EUROPE; THE MAST CHURCHES OF NORWAY; ROYAL TOMBS IN SCANDINAVIA. With 190 Illustrations. Royal 8vo, cloth, gilt. 21s. net.

REPRESENTATIVE BRITISH ARCHITECTS OF THE PRESENT DAY

By PROFESSOR C. H. REILLY, M.A., F.R.I.B.A., late Director of the Liverpool School of Architecture. An Account of Twelve Typical Figures, their Careers and Work, including Professor Adshead, Robert Atkinson, Sir Herbert Baker, Sir R. Blomfield, A. J. Davis, E. Guy Dawber, Clough Williams-Ellis, W. Curtis Green, H. V. Lanchester, Sir E. L. Lutyens, Sir Giles Gilbert Scott and Walter Tapper. Illustrated by 130 Exterior and Interior Views of well-known Buildings, and including 12 Portraits. Large 8vo, cloth, gilt. 7s. 6d. net.

(New Volume in "English Church Art" Series)

ENGLISH CHURCH SCREENS

A comprehensive Review of their Evolution and Design, including Great Roods, Tympana and Celures in Parish Churches during Medieval and Renaissance Times. By **AYMER VALLANCE, M.A., F.S.A.**, author of "Crosses and Lychgates," "The Old Colleges of Oxford," etc. Illustrated by some 300 reproductions of typical examples, detail, carving, etc., from photographs, measured drawings and sketches, including many no longer extant and a series in colour from special water-colour drawings. The fullest account of an exceptionally interesting subject. Small 4to, cloth, lettered, 21s. net. Only a limited edition is available.

THE ENGLISH CHURCH ART SERIES

OLD CROSSES AND Lychgates

A Study of their Design and Craftsmanship. By **AYMER VALLANCE, M.A., F.S.A.** With over 200 fine Illustrations from special Photographs, Old Prints, and Drawings. Crown 4to, art linen. Cheaper reissue, 12s. 6d. net.

ENGLISH CHURCH WOODWORK AND FURNITURE

A Study in Craftsmanship from A.D. 1250-1550. By **F. E. HOWARD and F. H. CROSSLEY, F.S.A.** Illustrating, in over 480 examples from Photographs, the Development of Screens, Stalls, Benches, Font-Covers, Roofs, Doors, Porches, etc., with details of the Carved and Painted Decoration, etc., etc. Second and cheaper Edition, revised, with a new series of 16 Colotype Plates. Crown 4to, cloth, gilt. 25s. net.

ENGLISH CHURCH MONUMENTS, A.D. 1150-1550

By **F. H. CROSSLEY, F.S.A.** A survey of the work of the old English craftsmen in stone, marble, and alabaster. Containing over 250 pages, with upwards of 350 Illustrations, from special Photographs and Drawings. Crown 4to, cloth, gilt. Cheaper reissue. 21s. net.

ENGLISH CHURCH FITTINGS AND FURNITURE

By the Rev. **J. C. COX, LL.D., F.S.A.** A Popular Survey, treating of Churchyards, Bells, Fonts and Covers, Pulpits, Lecterns, Screens, Chained Books, Stained Glass, Organs, Plate and other features of interest. With upwards of 250 Illustrations from Photographs and Drawings. 8vo, cloth, gilt. New and cheaper reissue. 12s. 6d. net.

THE GROWTH OF THE ENGLISH HOUSE

A short History of its Design and Development from 1100 to 1800 A.D. By **J. ALFRED GOTCH, F.S.A., PP.R.I.B.A.** Containing 300 pages, with over 150 Illustrations from Photographs, and many pictures in the text from Measured Drawings, Sketches, Plans, and Old Prints. Second Edition, revised and enlarged. Large crown 8vo, cloth, gilt. 12s. 6d. net.

THE SMALLER HOUSE OF TO-DAY

By **GORDON ALLEN, F.R.I.B.A.**, Winner of the *Daily Mail* Prize for the Best £1,500 House. Containing Notes on Sites and Subsoils, Plans, Exteriors, Methods, Interiors, Hygiene, Gardens, Finance, etc. With 2 Plates in colour, 64 from Photographs, and 153 Illustrations from Line Drawings of Houses, Plans, and Designs. Medium 8vo, cloth. 10s. 6d. net.

THE CHEAP COTTAGE AND SMALL HOUSE

By **GORDON ALLEN, F.R.I.B.A.** New Edition, remodelled and enlarged, containing over 150 Illustrations from Drawings and Photographs of Cottages and their Plans, Housing Schemes, etc., from typical Designs. Medium 8vo, cloth. 8s. 6d. net.

THE FOUR VOLUMES OF BATSFORD'S LIBRARY OF DECORATIVE ART

form an attractive Series of remarkable scope and completeness. It reviews the Development of English Decoration and Furniture during the three Renaissance Centuries, XVI, XVII, and XVIII (1550-1820). Each volume has an extensive series of Plates, and is a complete guide to the work of its Period. The volumes are remarkable for the beauty and number of their illustrations, the simplicity and clearness of their arrangement, and their moderate prices. The complete series is published at prices amounting to £10, but is supplied for the present at the special price of £9 net.

"These four handsome volumes with their extremely fine and copious illustrations provide a full survey of English Furniture and Decoration. —*The Books*."

VOL. I. DECORATION AND FURNITURE IN ENGLAND DURING THE EARLY RENAISSANCE, 1550-1660

An Account of their Development and Characteristic Forms during the Tudor, Elizabethan and Jacobean Periods, by M. JOURDAIN. Containing about 300 pages, and over 200 full-page Plates (with Coloured Frontispiece and some in Photogravure), including over 400 Illustrations, from specially made Photographs and Measured Drawings, and from Engravings. Folio (size 14 x 10½ in.), cloth, gilt. £2 10s. net.

VOL. II. FURNITURE IN ENGLAND FROM 1660 TO 1760

By FRANCIS LENYXON. A Survey of the Development of its Chief Types. Containing 300 pages with over 400 Illustrations, from special Photographs, together with 5 in colour. Second Edition, revised with many new Illustrations. Folio (14 in. x 10½ in.), cloth, gilt. £2 10s. net.

VOL. III. DECORATION IN ENGLAND FROM 1640 TO 1770

By FRANCIS LENYXON. A Review of its Development and Features. Containing 300 pages with over 350 Illustrations, of which 133 are full-page, from special Photographs, and 4 in colour. Second Edition, Revised and Enlarged. Folio (14 in. x 10½ in.), cloth, gilt. £2 10s. net.

VOL. IV. DECORATION AND FURNITURE IN ENGLAND DURING THE LATER XVIIITH CENTURY, 1760-1820

An Account of their Development and Characteristic Forms, by M. JOURDAIN. Containing about 300 pages, with over 180 full-page Plates (a selection in Collotype), including over 400 Illustrations, from specially made Photographs and Measured Drawings, and from Engravings. Folio (size 14 x 10½ in.), cloth, gilt. £2 10s. net.

OLD ENGLISH FURNITURE FOR THE SMALL COLLECTOR

Its History, Types and Surroundings from Medieval to Early Victorian Times. By J. P. BLAKE and A. E. REVEIRS-HOPKINS. Containing 150 pages with about 130 Illustrations from Photographs, Old Prints and Pictures, Original Designs, Ornaments, etc. The book is planned as the first systematic and comprehensive guide to the simpler types of old furniture within the scope of the collector of average means. Med. 8vo. 12s. 6d. net.

THE DECORATIVE ARTS IN ENGLAND, 1660-1780

By H. H. MULLINER, with an Introduction by J. STARKIE GARDNER. A Series of 110 full-page Plates illustrating 256 Specimens of Furniture, Lacquering, Marquetry, Chandeliers, Clocks, Silver, Enamels, Locks, Ormolu Vases, Tapestry, Needlework, Bookbindings. With brief Historical Introductions and full descriptions. Folio, half-parchment, gilt. The few remaining copies offered at 30s. net, published at £3 10s. net.

A BOOK OF BUNGALOWS AND MODERN HOMES

A series of Typical Designs and Plans. By CECIL J. H. KEELEY, F.S.I. A.R.S.A.L. Architect. Comprising 36 Designs, with large scale Plans, Brief Descriptions and Estimated Cost, including some two-Storey Houses, Frontispiece in colour, Interior Views, Photographic Plates, etc. Large 8vo, cloth, lettered. 7s. 6d. net.

"The work may be recommended to those people who are on the look-out for homes designed with intelligence and convenience, and who have an eye for charm and artistic finish"—*P.A.L.*

MODERN THEATRES AND CINEMAS

By P. MORTON SHAND. A series of 80 plates giving over 100 examples of exteriors, interiors, foyers, vestibules, lighting, mural decoration, details, etc., of Theatres and Cinemas in the modern post-war style in France, Germany, England, Scandinavia, Italy, America, etc. Containing reproductions of the work of such architects as Margold, Kaufmann, Siclis, Gropius, Lipp, Ionides, Sauvage, de Soissons, Wilms, Mendelsohn, etc. Containing in addition numerous plans, elevations, sections in the text. Cr. 4to, art canvas. 15s. net.

THE NEW STYLE

Architecture and Design. A Survey of its First Phase in Europe and America. With an Introduction adapted from the French of MAURICE CASTEELS, and descriptive notes on the Plates. Comprising 144 full-page Plates in Photogravure of Buildings, Interiors, Furniture, Lighting, etc., by well-known modern architects such as Le Corbusier, Mendelsohn, Gropius, Dudock, Mallet-Stevens, etc., chosen to illustrate the new movement in all its most representative manifestations. 4to, cloth, gilt. 12s. 6d. net.

ENGLISH INTERIORS FROM SMALLER HOUSES OF THE XVIITH to XIXTH CENTURIES, 1660-1820

By M. JOURDAIN. Illustrating the simpler type of Design during the Stuart, Georgian, and Regency Periods. Containing 200 pages, and 100 Plates, comprising 200 illustrations, from Photographs and Measured Drawings of Interiors, Chimney-pieces, Staircases, Doors, Ceilings, Panelling, Metalwork, Carving, etc., from minor Country and Town Houses. With Introduction and Historical Notes. Cheaper reissue. Large 4to, cloth, gilt. 15s. net.

ENGLISH PLASTERWORK OF THE RENAISSANCE

A Review of its Design during the Period from 1500 to 1800. By M. JOURDAIN. Comprising over 100 full-page Plates of Elizabethan, Stuart, Georgian, and Adam ceilings, friezes, overmantels, panels, ornament, detail, etc., from specially taken Photographs and from Measured Drawings and Sketches. With an Illustrated Historical Survey on Foreign Influences and the Evolution of Design, Work and Names of Craftsmen, etc. New and cheaper reissue. Demy 4to, cloth. 15s. net.

OLD ENGLISH FURNITURE: THE OAK PERIOD, 1550-1630

Its Characteristics, Features, and Detail from Tudor Times to the Regency. For the use of Collectors, Designers, Students, and Others. By J. T. GARSIDE. Containing 30 Plates reproduced from the Author's specially prepared Drawings illustrating about 400 details of Table Legs; Bedposts; Corbels; Friezes; Capitals; Panels; Inlay Motives; Metal Fittings, etc. Including also Drawings of type-pieces of the period and 20 Photographic Illustrations. With an Historical Introduction, etc. Cheaper reissue 8vo, cloth, gilt. 7s. 6d. net.

THE ART AND CRAFT OF HOME MAKING

A Comprehensive Guide with an Appendix of Household Recipes. By EDWARD W. GREGORY. Second Edition, revised, with additional Chapters and new Illustrations. Containing Practical Hints and Information on such subjects as Taking a House—Wallpapers—Furnishing Various Rooms—Pictures—Kitchen—Heating—Carpets—Curtains—Things that Get Out of Order—Costs, etc. Containing 224 pages, with 9 Plates in full colour of decorative schemes by GORDON BURN, numerous Photographs of Interiors by well-known architects, and many Sketches, Plans and Diagrams in the text. Square 8vo, cloth lettered. 7s. 6d. net.

THE NEW INTERIOR DECORATION

An Introduction to its Principles and International Survey of its Methods. By DOROTHY TODD and RAYMOND MORTIMER. With over 200 Illustrations on 96 Plates of Interiors of every sort, Furniture, Carpets, Textiles, Lighting, Wall Painting, etc., of the new school by such Architects and Artists as Le Corbusier, Mallet-Stevens, Gropius, Oud, Duncan Grant, Lescage, etc. With a Frontispiece in colour from a drawing by E. McKNIGHT KAUFFER and full Introductory and Practical Text. Demy 4to, art canvas, with decorative wrapper by E. McKNIGHT KAUFFER. 12s. 6d. net.

OLD PEWTER: ITS MAKERS AND MARKS

A Guide for Collectors, Connoisseurs, and Antiquaries. By HOWARD HERSCHEL COTTERELL, First Vice-President of the Society of Pewter Collectors. Containing about 500 pages, with 64 Plates of 200 Specimens of British Pewter, dated and described, and a List of 5,000 to 6,000 Pewterers, with Illustrations of their Touches and Secondary Marks, Facsimile Reproductions of existing Touch-Plates, and Text Illustrations. Cheaper reissue. Demy 4to, cloth, gilt. £3 3s. net.

OLD SILVER OF EUROPE AND AMERICA

From Early Times to the XIXth Century. By E. ALFRED JONES. A Survey of the Old Silver of England, America, Austria, Belgium, Canada, Czechoslovakia, Denmark, France, Germany, Holland, Hungary, Ireland, Italy, Norway, Poland, Portugal, Russia, Scotland, Spain, Sweden, Switzerland, etc. With a Chapter on Spurious Plate and 96 Photogravure Plates, comprising Illustrations of 537 subjects. Cheaper reissue. Crown 4to, art canvas, lettered in silver. 18s. net.

ENGLISH LEADWORK: ITS ART AND HISTORY

A Book for Architects, Antiquaries, Craftsmen, and Lovers of Gardens. By SIR LAWRENCE WEAVER, F.S.A. Containing 280 pages, with 441 Illustrations from Photographs and drawings. Large 4to, art linen, gilt. 30s. net.

BATSFORD'S COLLECTORS' LIBRARY

A Series of Handbooks written by experts, providing information of practical value to Connoisseurs, Collectors, Designers, and Students. Each volume forms an ideal introduction to its subject, and is fully illustrated by Reproductions in Colour and from Photographs. The following volumes are still available. 8vo, cloth, gilt, price 6s. net each.

OLD ENGLISH FURNITURE. By F. FENN and B. WYLLIE. With 94 Illustrations. *New Impression.*

OLD PEWTER. By MALCOLM BELL. With 106 Illustrations.

SHUTTLEFIELD PLATE. By BLURIE WYLLIE. With 121 Illustrations.

FRENCH FURNITURE. By ANDRÉ SAGLIO. With 59 Illustrations.

DUTCH POTTERY AND PORCELAIN. By W. P. KNOWLES. With 54 Illustrations.

PORCELAIN. By WILLIAM BURTON. With over 50 full-page Plates illustrating 87 fine examples of the Porcelain of Various Countries and Periods.

A HANDBOOK OF CHINESE ART

Including an Introduction by ROGER FRY and articles on Painting, Sculpture, Bronzes, Ceramics, Textiles, Jade, Enamels and Lacquer, etc., by LAURENCE BINYON, OSVALD SIREN, BERNARD RACKHAM, A. F. KENDRICK and W. W. WINKWORTH. With 23 fine full-page coloured plates, beautifully reproduced, of outstanding examples in public and private collections, and including also between 70 and 80 Photographic Illustrations on 52 plates, and a number of line cuts in the text, with maps, marks, tables of dynasties, etc. Large royal 8vo, cloth, lettered. 15s. net.

THE BURLINGTON MAGAZINE MONOGRAPHS

Issued by the Publishers jointly with The Burlington Magazine

MONOGRAPH NO. I—CHINESE ART (*Out of print*)

MONOGRAPH NO. II—SPANISH ART

An Introductory Review of Architecture, Painting, Sculpture, Textiles, Ceramics, Woodwork, Metalwork, by ROYALL TYLER, SIR CHARLES HOLMES and H. ISHERWOOD KAY, GEOFFREY WEBB, A. F. KENDRICK, B. RACKHAM and A. VAN DE PUT, BERNARD BEVAN, and P. DE ARTINANO, respectively. With a General Introduction by R. R. TATLOCK, late Editor of *The Burlington Magazine*. Illustrated by 120 large scale reproductions of Paintings, Decorative Art, Buildings, etc., including 9 Plates in full colour, comprising 280 pictures in all. With Maps, Bibliography, etc. Royal 4to, cloth. Cheaper reissue, 25s. net.

MONOGRAPH NO. III—GEORGIAN ART

A Survey of Art in England during the reign of George III, 1760-1820, by leading authorities. The Sections comprise: *Painting* by J. B. MANSON; *Architecture and Sculpture* by GEOFFREY WEBB; *Ceramics* by BERNARD RACKHAM; *Woodwork* by OLIVER BRACKETT; *Textiles* by A. F. KENDRICK; *Minor Arts* by LOUISE GORDON-STABLES. With an Introduction by ROGER FRY. The Illustrations include 6 Plates in colour and 64 in half-tone, comprising some 100 subjects, and forming a gallery of the fine and decorative arts of the Period. Cheaper reissue. Royal 4to, cloth. 21s. net.

COLOUR: A MANUAL OF ITS STUDY AND PRACTICE

By H. BARRETT CARPENTER, late Headmaster of the School of Art, Rochdale. A Series of 16 concise but very practical chapters, based on the Author's experiments, on Harmony—Contrast—Discord—Keynotes—Intermingling—Effect of Lighting—Dirty Colour—Black-and-White, etc. Illustrated by 24 Plates (some double size), printed in colour; giving 40 Examples of Colour Combinations, Grading, Toning, etc., including some new examples in colour of application in Historic Design. New and Revised Impression. 8vo, cloth, gilt. 9s. net.

A COLOUR CHART

Issued in connection with the above book. Consisting of a circle 17 inches in diameter, printed in Graded Colour, showing 14 shades, Combinations and Contrasts. With explanatory letterpress. Folio, stout paper. 2s. 6d. net.

FASHION DRAWING AND DESIGN

By LOUIE E. CHADWICK. Illustrated by numerous examples of Historic Fashion Plates, Explanatory Sketches by the Author, Figure Studies, and a series of about 80 full-page and double Plates of Contemporary Fashion Drawings by well-known artists. Cheaper reissue. Large 8vo, cloth, lettered. 7s. 6d. net.

ART IN THE LIFE OF MANKIND

A Survey of its Achievements from the Earliest Times. By ALLEN W. SEABY. Planned in a series of concise volumes, each containing about 80 pages of text, with about 70 full-page and smaller Illustrations from the author's specially prepared Sketches and Drawings, and a series of 16 Photographic Plates. Crown 8vo, cloth. 5s. net per volume.

I. A GENERAL VIEW OF ART: ITS NATURE, MEANING, PRINCIPLES AND APPRECIATION. II. ANCIENT TIMES: THE ART OF ANCIENT EGYPT, CHALDEA, ASSYRIA, PERSIA, and other lands. III. GREEK ART & ITS INFLUENCE. IV. ROMAN & BYZANTINE ART & THEIR INFLUENCE.

These concise little volumes are designed to serve as an Introduction to the Appreciation and Study of Art in general. They are simply and graphically written and fully illustrated by many Drawings and Photographs.

A SHORT HISTORY OF ART

From Prehistoric times to the Nineteenth Century. Translated from the French of Dr. ANDRÉ BLUM. Edited and Revised by R. R. TATLOCK. Illustrated by 128 full-page Photographic Plates, comprising about 250 examples of the finest Painting, Sculpture, Architecture, and Decorative Art of Early, Classic, Byzantine, Gothic, Renaissance, and Recent Times. Including also about 100 Illustrations in the text from Drawings, Engravings, and Plans. Medium 8vo, gilt. 12s. 6d. net.

HISTORY OF ART

By JOSEPH PIGOAN, Professor at Pomona College, California. In 3 volumes, Royal 8vo, bound in cloth, gilt. A few sets specially available at 30s. net set. Published at 36s. net per volume.

VOL. I. PRIMITIVE, ANCIENT AND CLASSIC ART. With 61 full-page Plates, including many in colour, and 876 Illustrations from Photographs, Plans, Drawings, Restorations, etc.

VOL. II. BYZANTINE, ISLAMIC, ROMANESQUE AND GOTHIC ART. With 52 double- and full-page Plates, including many in colour, and 856 Illustrations from Photographs, etc.

VOL. III. THE RENAISSANCE TO MODERN TIMES. With 34 full-page Plates, including many in colour and 776 Illustrations from Photographs, etc.

THE DRAWINGS OF ANTOINE WATTEAU, 1684-1721

By Dr. K. T. PARKER, of the Ashmolean Museum, Oxford, Editor of "Old Master Drawings." A full, original and critical Survey. Illustrated by 100 Collotype Reproductions of selected characteristic Drawings from private and public collections, many unpublished, a Frontispiece in colour and 16 of the Master's most important pictures. With full, critical and descriptive letterpress, 4to, canvas cloth, gilt. £2 2s. net.

A HISTORY OF BRITISH WATER-COLOUR PAINTING

By H. M. CUNDALL, F.S.A. With a Foreword by Sir H. HUGHES-STANTON, P.R.W.S. A New and Cheaper Edition, revised and enlarged, of this important standard work, with 64 full-page Illustrations in colour, and a full biographical list, arranged alphabetically, of the principal English Water-colourists. Large Medium 8vo, cloth, 15s. net.

HISTORIC TEXTILE FABRICS

By RICHARD GLAZIER. Containing: Materials—The Loom—Pattern—Tapestries—Dyed and Printed Fabrics—Church Vestments, etc., with about 100 Plates from Photographs and from the Author's Drawings including 4 in colour, and 43 Line Diagrams, illustrating over 200 varieties of Textile Design. Large 8vo, cloth, gilt. 21s. net.

THE ART AND CRAFT OF OLD LACE

In all Countries, from the XVIth to the Early XIXth Centuries. By ALFRED VON HENNEBERG. With an Introduction by WILHELM PINDER. Containing a full original account of the Development of Style and an Analysis of Technique and Texture. Including descriptive Notes and a Bibliography. Illustrated by 190 full-page Plates, 8 in colour, giving 60 specimens from scale diagrams and 250 of the finest pieces of Old Lace. Large 4to, cloth, gilt. £3 3s. net.

JOHN OBRISSET

Huguenot, Carver, Medallist, Horn and Tortoise-shell Worker, and Snuff-box Maker. With examples of his Works dated 1705-1728. By PHILIP A. S. PHILLIPS. Containing Text on the Records of the Obrisset family. Writings on his Craftsmanship, and Notes. With 104 Illustrations on 40 Plates, finely reproduced in Collotype, of Horn and Tortoise-shell Tobacco-boxes, Medals, Plaques in different Materials, Medallions, etc. Edition limited to 250 numbered copies, of which 210 are for sale. 4to, canvas, gilt, gilt top. £3 3s. net.

DESIGN IN WOODWORK

A practical manual. By PERCY A. WELLS, late Head of the Woodwork Department, L.C.C., Shoreditch Technical Institute; Author of "Modern Cabinetwork," "Furniture for Small Houses," etc. Comprising chapters on Design (Introductory), Craftsmanship—Decoration—Finishing—Staining—Polishing—Suggestions for courses in Trade Schools and Training Colleges, etc. Illustrated by 25 full-page specially prepared Drawings comprising 150 diagrams and 47 Plates from photographs specially taken of 100 Mirrors, Stools, Clocks, Cabinets, Tables, Bookcases, etc. Demy 8vo, cloth, lettered, 6s. net.

FURNITURE FOR SMALL HOUSES

A Series of Designs. By PERCY A. WELLS. Containing 56 Plates reproduced from Photographs and Working Drawings by the Author, together with Illustrations in the text. Cheaper reissue. Small 4to, cloth. 7s. 6d. net.

HANDCRAFT IN WOOD AND METAL

A Handbook for the use of Teachers, Students, Craftsmen, and others. By JOHN HOOPER and ALFRED J. SHIRLEY. With over 300 Illustrations from Drawings and Photographs. Second Edition, revised and enlarged. Large 8vo, cloth, lettered. 10s. 6d. net.

CRAFTWORK IN METAL

A Practical Elementary Textbook for Teachers, Students, and Workers. By ALFRED J. SHIRLEY. Comprising a series of progressive Lessons and Exercises, illustrated by numerous full-page Plates from the Author's Drawings, each accompanied by detailed working directions, including also Practical Notes, Tables, etc. Medium 8vo, cloth; cheaper reissue with additional plates. 5s. net.

"It bears the imprint of the successful practical teacher—hence its value to other teachers of the craft. We predict the book will be extensively used by teachers and students in the metalwork centres."—*The London Schoolmaster*.

BOOKCRAFTS AND BOOKBINDINGS. A Practical Course.

By JOHN MASON, Teacher at Leicester College of Arts and Crafts, etc., with an Introduction by S. I. HERMAN, A.R.C.A., Principal of Hull Arts and Crafts College. Containing sections on Historical Developments, various Binding Processes, Lettering, Leather, Paper, etc., with some 300 Illustrations from diagrams and photographs of operations and finished designs. Large 8vo, cloth, hand-marbled by the Author. 8s. 6d. net.

A MANUAL OF HISTORIC ORNAMENT

Being an Account of the Development of Architecture and the Historic Arts, for the use of Students and Craftsmen. By RICHARD GLAZIER, A.R.I.B.A. Fifth Edition, revised and enlarged. Containing 700 Illustrations, chiefly from the Author's Pen Drawings, including many new to this Edition from various sources, and a special series of coloured and Photographic Plates of Ornament of the Orient and the Renaissance. Large 8vo, cloth. 12s. 6d. net.

A HANDBOOK OF ORNAMENT

By Professor F. SALES MEYER. With 3,000 Illustrations of the Elements and the Application of Decoration to Objects, e.g. Vases, Frets, Diapers, Consoles, Frames, Jewellery, Heraldry, etc., grouped on over 300 Plates, reproduced from the Author's specially prepared Drawings. With descriptive text to each subject. Large 8vo, cloth, lettered. 15s. net.

"IT IS A LIBRARY, A MUSEUM, AN ENCYCLOPEDIA, AND AN ART SCHOOL IN ONE. TO RIVAL IT AS A BOOK OF REFERENCE ONE MUST FILL A BOOKCASE. The quality of the drawings is unusually high, and the choice of examples is singularly good. . . . The text is well digested, and not merely descriptive or didactic, but an admirable mixture of example and precept. So good a book needs no praise."—*The Studio*.

THE STYLES OF ORNAMENT

From Prehistoric Times to the Middle of the XIXth Century. A Series of 3,500 Examples Arranged in Historical Order, with descriptive text. By ALEXANDER SPELTZ. Revised and Edited by R. PHENÉ SPIERS, F.S.A., F.R.I.B.A. Containing 560 pages, with 400 full-page Plates exhibiting upwards of 3,500 separate Illustrations. Large 8vo, cloth, gilt. 15s. net.

Mr. WALTER CRANE, in a lengthy review in the *Manchester Guardian*, wrote: ". . . To pack into a single volume of some 626 pages and 400 illustrations a really intelligible account of the styles of ornament prevailing in the world from prehistoric times to the middle of the nineteenth century is a REMARKABLE FEAT. . . . The illustrations are for the most part well chosen and characteristic, and are drawn with decision and facility."

ABSTRACT DESIGN

A Practical Manual on the Making of Pattern. By AMOR FENN, late Head of the Art Section, Goldsmith's College, New Cross. A series of careful, informative sections on Conditions, Elements, etc. Illustrated by about 180 full-page Designs from the Author's specially-prepared Drawings. 8vo, cloth, lettered. 12s. 6d. net.

PATTERN DESIGN

For Students, treating in a practical way the Anatomy, Planning, and Evolution of Repeated Ornament. By LEWIS F. DAY. Containing about 300 pages, and 300 practical Illustrations from specially prepared Drawings and Photographs of the Principles of Repeat Design, the "Drop," the "Spot" Geometrical Ornament, etc. New edition, revised and enlarged by AMOR FENN, with many fresh Illustrations, including a series in colour. Demy 8vo, cloth, gilt. 10s. 6d. net.

NATURE AND ORNAMENT

By LEWIS F. DAY. NATURE THE RAW MATERIAL OF DESIGN, treating chiefly of the decorative possibilities of Plant Form, its growth, features, and detail. With 350 Illustrations, chiefly grouped comparatively under Flowers, Seed Vessels, Fruits, Berries, etc., specially drawn by Miss J. FOORD. New and cheaper Edition, revised, with a Chapter by MARY HOGARTH. Demy 8vo, cloth, lettered. 5s. net.

SHOULD WE STOP TEACHING ART?

By C. R. ASHBEE. An interesting and outspoken account of modern Art Education. 8vo, boards, buckram back. 3s. 6d. net.

THE PRACTICAL DRAWING SERIES

COMPOSITION

An Analysis of the Principles of Pictorial Design. By CYRIL C. PEARCE, R.B.A. With chapters on Tone, Distribution, Gradation, Scale, Perspective, Rhythm, Harmony and Balance of Colour, Discords. Illustrated by 130 comparative and analytical Drawings, Sketches, and Diagrams, 6 Plates in colour, and 28 full-page Illustrations from great Masters. Med. cloth, gilt, paper sides. 10s. 6d. net each.

ANIMAL ANATOMY AND DRAWING

By EDWIN NOBLE. Illustrated by a series of Plates in facsimile of the Author's Drawings of HORSES, CATTLE, DOGS, BIRDS and WILD ANIMALS, representing also Features, Details, etc. Including also numerous full-page and smaller Line Drawings of Anatomy, Muscles, Bones, etc.

PEN DRAWING

A Practical Manual on Materials, Technique, Style, Texture, etc. By G. M. ELLWOOD. Containing sections on History—Technique—Materials—Figures, Faces and Hands—Style and Methods—Landscape and Architecture—Modern Work—Magazine Illustration—Humorous Drawing Advertisements—Fashion. With numerous practical Diagrams by the Author, and 100 pages of Illustrations by the chief Pen Draughtsmen of present and recent times.

THE ART AND PRACTICE OF SKETCHING

A Comprehensive Treatise on the Practice of Sketching by every method. By JASPER SALWEY, A.R.I.B.A. The Author deals successively with various media—Pen, Pencil, Water-colour, Oil, Wash, Crayon, Chalk, etc., and gives a complete account of the Technique of each. Illustrated by 64 Plates of half-tone Illustration and 6 Plates in colour, with various Line Illustrations in the text, from the work of great Artists.

THE ART OF DRAWING IN LEAD PENCIL

By JASPER SALWEY, A.R.I.B.A. A Practical Manual dealing with Materials, Technique, Notes and Sketching, Building up, Form and Style, Process Reproduction, etc. Second Edition, revised and enlarged. Containing 232 pages with 122 finely printed reproductions of selected Pencil Drawings of Land and Seascapes, Figure-Studies, Book-Illustrations, etc.

SKETCHING IN LEAD PENCIL

By JASPER SALWEY, A.R.I.B.A. An Introduction to the same author's "Art of Drawing in Lead Pencil," but dealing entirely with sketching as differentiated from the making of finished Drawings. A practical manual for the Architect, Student and Artist. Containing 111 pages and 56 Illustrations, by well-known artists in the medium, and by the author. 7s. 6d. net.

SKETCHING FROM NATURE

A Practical Treatise on the Principles of Pictorial Composition. By F. J. GLASS. CONTENTS: Choice of Subject and Planning of Sketch—Tones—Exercise in Composition—Examples from the Old Masters. With 6 Plates in colour, numerous compositions from the Author's Drawings, and a series by de Wint, Crome, Constable, Harpignies, Bonnington, etc.

DRAWING FOR ART STUDENTS AND ILLUSTRATORS

By ALLEN W. SEABY. Containing 220 pages, with 133 Illustrations printed in Sepia, mostly full-page Plates, from Drawings by Old and Modern Artists. Second Edition, revised and enlarged. 8vo, cloth.

ART IN DAILY LIFE FOR YOUNG AND OLD

By D. D. SAWER. A companion and complement to the following work with a Foreword by P. H. JOWELL, A.R.C.A., Principal of the Central School of Arts and Crafts, London. A comprehensive practical course for Teachers, Students, and Art Lovers; treating of the Place of Drawing, Plants and their Use, Figure Drawing and Drapery, Animal Drawing, Modelling Shapes and Figures, Casting, Clay Modelling, Object Drawing, Notes on Crafts, Composition, Design, applied and graphic. Each chapter is divided into three sections. A historical résumé, a note on educational significance, and a brief review of its practice and technique. With 10 Plates in Colour, and numerous full-page and text Illustrations in Line and Half-tone. Medium 8vo, cloth, lettered. 10s. 6d. net.

EVERYDAY ART AT SCHOOL AND HOME

By D. D. SAWER. With an appreciative Foreword by Sir Michael Sadler, C.B., Oxford. A Practical Course based on the new Board of Education "Suggestions to Teachers," and adaptable to Dalton Methods, containing graduated lessons on Brushwork, Design, Flower-painting, etc., with sections on Architectural Drawing, Lettering, Stained Glass, Leatherwork, and other Crafts. With 64 Plates in half-tone, from the Author's Drawings, numerous full-page and smaller Line Illustrations, and 8 Plates in colour, many Verse Extracts, etc. Second and cheaper edition, revised and enlarged. Medium 8vo, cloth. 10s. 6d. net.

PERSPECTIVE IN DRAWING

A simple Introductory Account. By Miss D. D. SAWER, late Art Lecturer at the Diocesan College, Brighton, Author of "Everyday Art at School and Home." With an Introduction by Professor ALLEN W. SEABY, late Professor of Fine Art, University of Reading. With Sections on Basic Principles, the Cube, Cylinder, Shadows, Reflections, Aerial Perspective, Colour, and Drawing. Illustrated by over 100 Diagrams and Sketches, a Frontispiece in colour, specially drawn by the Author, and reproductions from Photographs. Crown 8vo, cloth. 7s. net.

SKETCHING AND PAINTING FOR YOUNG AND OLD

An Elementary Practical Manual. By D. D. SAWER, late Art Mistress, Brighton Diocesan Training College, Author of "Everyday Art," "Perspective," etc. With a Foreword by Lord BADEN-POWELL. With chapters on: Ungathered Wealth, a Day Out, Materials Practice, the First Sketch Out of Doors, Composition, Mounting and Framing. Illustrated by coloured Frontispiece, 8 Plates in Line and half-tone, and 31 text Illustrations from the Author's specially prepared Sketches Diagrams, etc. Crown 8vo, stiff covers, 1s. 6d. net, or quarter-cloth, lettered, 2s. net.

THE ART OF THE BODY

Rhythmic Exercises for Health and Beauty. By MARGUERITE AGNIEL, Dancer and Physical Instructress. A series of simple, easy and enjoyable exercises, illustrated by numerous Photographic Plates, specially posed by the Author. With 100 subjects on 64 Plates, including many reproductions of dance poses and figure studies, draped and nude. CONTENTS: Functions of the Spine—How to Walk Well—Figure Reducing—Exercises for the Digestive Organs, Back and Neck—Legs and Ankles—The Care of the Hands and Feet—Skin, Eyes and Teeth—Constipation—Women's Disorders, etc. Large 8vo, cloth, gilt. 12s. 6d. net.

THE HUMAN FORM AND ITS USE IN ART

A Series of 118 Photographic Studies on 73 Plates from specially selected Female and Child Models, by F. R. YERBURY, including a Series of Male Studies by F. H. CROSSLEY, F.S.A. With an Introduction by G. M. ELLWOOD. Illustrated by 17 Photographic Plates and numerous Text Figures. With descriptive Notes on the Poses. Large 8vo, cloth. 18s. net.

LIVING SCULPTURE

A Record of Expression in the Human Figure. By BERTRAM PARK and YVONNE GREGORY. With an historical and descriptive Introduction by G. MONTAGUE ELLWOOD. Comprising a Series of 47 full-page Studies of Selected Male and Female Figures with descriptive Notes. The Introduction is illustrated by 9 plates, giving 16 examples of the Human Form in Prehistoric, Greek, Renaissance and newest Art. Cheaper reissue. Small 4to, cloth, gilt. 12s. 6d. net.

LAUGHS AND SMILES and How to Draw Them. By A. A. Braun, author of "Figures, Faces and Folds" and other works.

Containing 45 Plates, printed in tints, of numerous constructional sketches, building up in successive stages humorous likenesses of well-known personages, and also figures from old Masters. Comprising in all about 300 Sketches by the Author, with concise instructive Text, including numerous anatomical Diagrams. Oblong 4to, decorative boards, cloth back. 3s. 6d. net. "A book which young art students, or anyone with a practical taste for art, would appreciate. This attractive manual on humorous portrait-drawing should have a wide appeal."—*Overseas Daily Mail*.

FIGURES, FACES AND FOLDS

A Reference Book on Costume and the Female Countenance and Form. For Fashion Artists, Dress Designers, and Art Students. By ADOLPHE ARMAND BRAUN. Containing 112 comparative Plates, giving over 300 Illustrations of Costumes and Drapery, and of typical Women's Faces, from antique statues and paintings. Including a special series of nude and draped studies from selected models specially posed for fashion work. With practical text, Dress diagrams, Figure details, Anatomy analysis, etc. Cheaper reissue. Demy 4to, stiff paper covers, 10s. 6d. net; cloth, gilt, 12s. 6d. net.

THE CHILD IN ART AND NATURE

By A. A. BRAUN. Containing chapters on Anatomy, Development, and Expression, and over 300 Illustrations from Photographs and Drawings of child poses, expressions, the Child Figure in Art. Second Edition, revised and enlarged. Cheaper reissue. 4to, in stiff covers, 10s. 6d. net; or cloth, gilt, 12s. 6d. net.

ALPHABETS, OLD AND NEW

With 224 complete Alphabets, 30 series of Numerals, many Ancient Dates, etc. Selected and Arranged by LEWIS F. DAY. With a short account of the Development of the Alphabet. Crown 8vo, cloth. 5s. net.

"A book which has, perhaps, proved more helpful than any ever before issued on the subject of alphabets."—*The Decorator*.

A valuable and attractive little Manual

PEN PRACTICE

By WALTER HIGGINS. Chapters on Tools, Broad-pen Practice, Spacing, Italics, Uncials and Half-uncials, Setting out, A Cursive Hand, etc. With 27 Plates specially drawn by the Author, giving some hundreds of Letters, Ornaments and Exercises, and 6 from selected Historical Examples. Second Edition, revised. Crown 8vo, stiff paper covers, 1s. 6d. net, or boards lettered, 2s. 6d. net.

THE ROMAN ALPHABET AND ITS DERIVATIVES

A large-sized Reproduction of the Alphabet of the Trajan Column. By ALLEN W. SEABY. A Series of large Plates, printed from the wood blocks, and including typical examples of Renaissance, Gothic, and Modern Alphabets and Types. With Introduction and descriptive Notes. Medium 4to, half-bound, lettered, or in portfolio. 4s. 6d. net.

DRAWING, DESIGN AND CRAFTWORK

For Teachers, Students, and Designers. By FREDK. J. GLASS. Containing 262 pages, with some 2,000 Illustrations on 156 Plates, from Drawings by the Author and others, and Historic Designs: Chinese, Persian, Japanese, Medieval, etc. Third Edition revised and enlarged with many new Plates, including a special series in colour of Historic and Modern Designs. Demy 8vo, cloth. 12s. net.

MODELLING

A Practical Treatise for the Use of Students, etc. By F. J. GLASS. Containing Chapters on Modelling for Bronze, Wood, Stone, Terra-Cotta, etc.; Modelling a Bust from Life; Figure Modelling. Relief Work; Composition; Casting; Gelatine Moulding; Proportionate Enlargement, etc. With an additional section on the History of Sculpture and Modelled Ornament. Illustrated by about 30 Plates of comparative stages and processes of Modelling, with about 35 Plates of the greatest Sculpture of all Periods, together with many Line Illustrations in the text. Royal 8vo, cloth, gilt. 15s. net.

THE ART AND CRAFT OF LINO CUTTING AND PRINTING

A Manual for the use of Schools and Amateurs. By CLAUDE FLIGHT, author of "Lino-Cuts," "Tinker, Tailor," etc. With a Foreword by J. E. BARTON, Headmaster Bristol Grammar School, author of "Purpose and Admiration." Treating of Designing, Cutting the Blocks, Printing the Blocks, Alterations, Criticism, Rise and Future, etc. The volume contains 80 Pages, with 77 Illustrations, largely full-page, of which 72 are in black and white or single tone and 5 in full colour, by the author and other well-known modern artists, including practical diagrams and prints in various stages. Tall 8vo, decorative boards. 3s. 6d. net.

PRACTICAL WOODCARVING

By ELEANOR ROWE. Third Edition, revised and enlarged, in Two Parts; I. ELEMENTARY WOODCARVING, embodying "Hints on Woodcarving." With numerous Illustrations, many full-page, from Drawings and Photographs of carving operations, examples and details. II. ADVANCED WOODCARVING. With numerous Illustrations, many full-page from Drawings and Photographs of historic and modern carvings. Demy 8vo, limp cloth, lettered, 5s. net each; or two parts in one volume, cloth, gilt, 10s. net.

ONE HUNDRED AND ONE THINGS FOR A BOY TO MAKE

By A. C. HORTH. With Notes on Workshop Practice and Processes, Tools, Joints, and full reliable directions for making Working Models. Illustrated by numerous full-page and smaller practical Diagrams and Sketches specially prepared. Second Edition, revised and enlarged. Crown 8vo, cloth. 5s. net.

Uniform with "101 Things for Boys to Make"

ONE HUNDRED AND ONE THINGS FOR GIRLS TO DO

By A. C. HORTH, Editor of "Educational Handwork," etc. With practical sections on Sutchery, the making of decorative Household Articles in felt, leather, gesso, raffia, Hints on Mending, Cleaning, First-Aid, etc. Illustrated by numerous Line Diagrams, Photographs of finished objects, etc. Crown 8vo, cloth, lettered. 5s. net.

SAMPLERS AND STITCHES

A Handbook of the Embroiderer's Art. By MRS. ARCHIBALD CHRISTIE. Containing 40 full-page Reproductions from Photographs, a Frontispiece in colour, and 289 Text Drawings. Third Edition, revised and enlarged. Crown 4to, boards, canvas back. 25s. net.

ART IN NEEDLEWORK

A BOOK ABOUT EMBROIDERY. By LEWIS F. DAY and MARY BUCKLE. Fourth Edition, revised by MARY HOGARTH. Including a specially worked Series of Stitch-Samplers, numerous supplementary Diagrams and many Plates of Historic Embroidery—Chinese, Medieval, Italian, French and Modern English. With additional Examples of Modern Work by DUNCAN GRANT, MRS. NEWALL, MRS. STOLL, D. HAGER, and others. Containing 280 pages, 80 full-page Plates, reproduced from Photographs, and 50 Illustrations in the text. Crown 8vo, cloth. 7s. 6d. net.

SIMPLE STITCH PATTERNS FOR EMBROIDERY

By ANNE BRANDON-JONES. With coloured Frontispiece and 13 Photographic Plates illustrating 44 Patterns, 4 Plates from the Author's Pen Drawings, showing 31 Stitch Diagrams and 11 Complete Objects. With an Introduction, Chapters on the Method, Sketches, Colour Materials and Application of Designs, also descriptive Notes, with Colour Schemes. Crown 4to, paper wrappers, 2s. 6d. net; or in cloth, 3s. 6d. net.

"There is valuable help in this book. There are excellent plates in line and colour. The directions are clear and concise, and the articles suggested for practice are such as will please young people to make."—*Education Outlook*.

STITCH PATTERNS AND DESIGNS FOR EMBROIDERY

By ANNE BRANDON-JONES. An independent companion volume to the above work, containing 48 pages with 45 photographic examples on 12 Plates of simple and effective embroidery Motives, a Frontispiece in colour and numerous Text Illustrations of Stitches and Methods. Crown 4to, paper wrappers, 3s. net; or in cloth, 4s. net.

CANVAS EMBROIDERY

A Manual for Students and Amateurs by LOUISA F. PESEL. Containing 48 pages of text, a coloured Frontispiece, and 14 specially prepared Plates showing Stitches and methods. Medium oblong 4to, paper wrappers, 3s. net; or bound in cloth, 4s. net.

ENGLISH EMBROIDERY. I. DOUBLE-RUNNING, OR BACK-STITCH

By LOUISA F. PESEL. With coloured Frontispiece, 10 specially drawn Plates of 45 Working Designs, and 8 Plates from Photographs of 10 English and Coptic Samplers, comprising numerous Patterns and Motives. With Practical Text and a Preface by ETTA CAMPBELL, Embroidery Teacher, Winchester School of Arts. Uniform with "Canvas Embroidery." Large oblong 4to, paper wrappers, 3s. net; or boards, cloth back, 4s. net.

ENGLISH EMBROIDERY. II. CROSS-STITCH

By LOUISA F. PESEL. With a Coloured Frontispiece, 10 specially drawn Plates of 32 Working Designs, etc., and 8 Plates from Photographs of 15 typical English Samplers and Objects. Comprising 43 subjects, giving hundreds of Patterns and Motives. With Practical Text and a Preface by Professor R. GLEADOWE, late Slade Professor of Fine Arts, Oxford University. Large oblong 4to, paper wrappers, 3s. net; or boards, cloth back, 4s. net.

ILLUSTRATED STITCHERY DECORATIONS

By WINIFRED M. CLARKE. Containing 19 Plates from the Author's specially prepared Drawings, giving some 120 useful original Motives: Borders, Rosettes, Floral Elements, Patterns, Lettering and Worked Objects, such as Bags, Blotters, etc. Including a coloured Frontispiece, Introductory Text and full descriptive Notes on the Plates. Crown 4to, stiff paper wrappers, 3s. net; boards, cloth back, 4s. net.

"A new and extremely useful little book for the embroidery worker. Miss Clarke has succeeded admirably in her task."—*Edinburgh Evening News*.

INDEX TO AUTHORS' NAMES

- Agniet, *Art of the Book*, 28
 Allen, *Cheap Cottage*, 19
 — *Small House*, 19
 Anderson & Spiers, *Greece and Rome*, 15
 Anderson, *Italy*, 15
 Ashbee, *Teaching Art*, 26
 Ashbee, *Arch. of Rome*, 15

 Bailey, *Spanish Towns*, 16
 Buttsford & Fry, *The Cathedrals of England*, 4
 — *The Face of Scotland*, 5
 Bell, *Old Peasier*, 22
 Beattie, *of Britain*, 7
 Blake, *The Heart of S. Hand*, 5
 Blase & Hopains, *Old Furniture*, 20
 Blum, *History of Art*, 24
 Book of Speed, 7
 Brandon-Jones, *Stitch Patterns*, 31
 Brandt, *English at Home*, 6
 Braun, *Child in Art*, 29
 — *Figures, Faces, Fields*, 29
 — *Laughs and Smiles*, 29
 Breton, *Clothing*, 9
 — *Travel*, 9
 Brown, *The Heart of England*, 5
 Budden, *Gothic Churches*, 16
 Burlington Magazine Monographs, 23
 Burton, *Porcelain*, 22

 Carpenter, *Colour*, 23
 Castells, *New Lace*, 21
 Chadwick, *Fashion Drawing*, 23
 Chancellor, *18th Century*, 9
 — *Regency Period*, 9
 Chinese Art, 23
 Christie, *Samplers*, 30
 Cities of Northern Europe, *Pictorial Guide*, 9
 Clarke, *Stitchery: Decorations*, 31
 Cohen-Portman, *Spirit of London*, 4
 Collectors' Liter., 22
 Colour, *Art and Life Library*, 8
 Cotterell, *Old Peasier*, 22
 Cox, J. C., *Church Filings*, 4
 — & Ford, *Parish Churches*, 4
 Crossley, *English Abbey*, 4
 — *Monuments*, 19
 Crossley & Howard, *Church Woodwork*, 19
 Cundall, *Water Colour Painting*, 24

 Day, *Alphabets*, 29
 — *Needlework*, 31
 — *Pattern Design*, 26
 — *Nature and Ornament*, 26
 Dinsmoor, *Green Architecture*, 15
 Doyle, *Spirit of Ireland*, 3
 Dutton, *Country House*, 3

 Ellwood, *Pen Drawing*, 27
 Ellwood & Verbury, *Human Form*, 28
 Eyston, *Motor Racing*, 6
 — *Speed on Sault*, 13

 Farey & Edwards, *Architectural Drawing*, 13
 Fenn, *Abstract Design*, 26
 Fenn & Wylie, *Furniture*, 22
 Ferns, *1 & 15 Lanes*, 7
 Fletcher, *Architecture*, 17
 — *The Architectural Work of*, 17
 Flight, *Line-Cutting*, 30
 Ford, *Parish Churches*, 4

 Garner & Stratton, *Tudor Architecture*, 14
 Garside, *Furniture*, 21
 Georgian Art, 23
 Glass, *Drawing Design*, 30
 — *Making*, 30
 — *Sketching*, 27
 Glazer, *Ornament*, 26
 — *Textiles*, 24
 Godfrey, *English Architecture*, 14
 — *Gardens*, 5
 Gotch, *English House*, 19
 — *Northamptonshire Houses*, 17
 Gregory, *Home Making*, 22
 Grober, *Foss*, 17

 Hake & Button, *Arch. Drawing*, 11
 Hamilton, *Byzantine Arch.*, 15
 Hartley, *Medieval Costume*, 10
 — *Countryman's Eng. ind.*, 5
 Hartley & Elliott, *Life and Work*, 10
 Haupt, *Italian Palaces*, 17
 Henneberg, *Old Lace*, 25
 Higgins, *Pen Practice*, 29
 Hooper & Searle, *Handicraft*, 25
 Horth, *101 Things for Boys and Girls*, 30
 Howard, *Styles of Parish Church*, 5

 Jekyll, *Household Life*, 8
 Jones, *Ancient Architecture*, 14
 — *Old Silver*, 22
 — *Touring England*, 18
 Jourdain, *Decoration and Furniture*, 20
 — *Interiors*, 21
 — *Plasterwork*, 21
 Keeley, *Bungalows*, 21
 Kelly & Schwabe, *Costume*, 10
 — *Costume and Armour*, 10
 Knowles, *Dutch Pottery*, 22

 Legacy of England, 7
 Lenygon, *Decoration and Furniture*, 20
 Library of Decorative Art, 20
 Mason, *Bookcrafts*, 25
 Ma-sin-cham, *English Downland*, 6
 Mawson, *Garden-making*, 17
 Meyer, *Ornament*, 26
 Mulliner, *Decorative Arts*, 20
 Nature in Britain, 7
 Noble, *Animal Drawing*, 27
 Pakington, *Villages and Hamlets of England*, 4

 Park, *Living Sculpture*, 29
 Parker, *Watteau Drawings*, 24
 Pearce, *Composition*, 27
 Peck, *Embroidery Works*, 31
 Phillips, *O. risset*, 25
 Pichon, *History of Art*, 24
 Practical Drawing Series, 27
 Pullbrook, *Country Life*, 8
 — *Country-side*, 8

 Quennell, *Everyday Life*, 12
 — *Everyday Things*, 11
 — *Greece*, 13
 — *God's New Days*, 9
 Quigley, *Scottish Highlands*, 6

 Reilly, *Mid Devon Architects*, 18
 Richards, *Georgian England*, 18
 — *Summer House*, 15
 — *The Old Inns of England*, 5
 Roe, *Church Chests*, 18
 Rosenau, *Design and Medieval Architecture*, 15
 Rouse, *Old Towns*, 3
 Rowe, *Woodcarving*, 30

 Sagho, *French Furniture*, 22
 Salwey, *Leaf Pencil*, 27
 — *Sketching*, 27
 Salzman, *Tudor England*, 12
 Sawyer, *Everyday Art*, 28
 — *Art in Daily Life*, 28
 — *Perspective*, 28
 — *Sketching*, 28
 Seaby, *Art of Manhood*, 24
 — *Drawing*, 27
 — *Roman Alphabet*, 29
 Shand, *Theatres & Cinemas*, 21
 Shore, *Dinner Building*, 7
 — *Touring London*, 12
 Smith, *Arch. Work of Sir Banister Fletcher*,
 Spanish Art, 23
 Speed, *Book of*, 7
 Speltz, *Styles of Ornament*, 26
 Statham, *Architecture*, 14
 Stratton, *Arch. Diagrams*, 16
 — *Elements*, 16
 — *Orders*, 16
 — *Stakes*, 16
 Strzygowski, *Church Art*, 18

 Todd & Mortimer, *Modern Decoration*, 22
 Vale, *Seas and Shores*, 3
 Vallance, *Crosses and Lychgates*, 19
 — *English Church Screens*, 19
 Villiers-Stuart, *Spanish Gardens*, 18

 Ward, *French Architecture*, 15
 Waterhouse, *Story of Archt.*, 14
 Weaver, *Leadwork*, 22
 Wells, *Furniture*, 25
 — *Design in Woodwork*, 25
 Wylie, *Furniture*, 22
 — *Sheffield Plate*, 22



D.G.A. 80.

CENTRAL ARCHAEOLOGICAL LIBRARY
NEW DELHI

Issue Record.

Catalogue No.

701.0942/One/One

34714

Author—Marjorie A. Quennell, J.H.S.

Title—A history of Everyday things
in England. Vol.III.

Borrower No.

Date of Issue

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.